



## Local Government & Community Development Department

### Punjab Cities Program Improvement and Rehabilitation of P1- Gojra Toba Road in Gojra City

# PC-I

Estimated Cost PKR 291.705 Million

March 2023

Municipal Committee Gojra



#### JERS CONSULTANCY (PVT) LTD

(Formerly Jers Engineering Consultants)

24-Civic Center, Quid-e-Azam Town, Township, Lahore (Pakistan)

Tel: +92 42 35113123, +92 42 35113124

Fax: +92 42 35113125

E-mail: [info@jers.com.pk](mailto:info@jers.com.pk), [mail@jers.com.pk](mailto:mail@jers.com.pk)

Web: <http://www.jers.com.pk>



**Punjab Cities Program**  
**PC-I Form for Improvement of P1-Gojra Toba Road Project in**  
**Gojra City**  
**Table of contents**

| <b>S. No.</b> | <b>Description</b>  | <b>Page No.</b> |
|---------------|---|-----------------|
| 1             | PC-I Form   | 1-15            |
| 2             | <b>Annexure-A</b> Location map  | 16-18           |
| 3             | <b>Annexure-B</b> Project cost Estimates                              | 19-125          |
| 4             | <b>Annexure-C</b> Project Economic Analysis                           | 126-138         |
| 5             | <b>Annexure-D</b> Project Implementation Period (Gant Chart)          | 139-140         |
| 6             | <b>Annexure-E</b> Environment and Social Mitigation & Management Plan | 141-170         |
| 7             | <b>Annexure-F</b> Project Drawings                                    | 171-278         |

**PC-I FORM**  
**for**  
**Improvement & Rehabilitation of P1-Gojra Toba Road Project in Gojra City**

*Project Serial Number*

*Sector :* **Local Government & Community Development Department**

*Sub Sector:* **Social**

|  |   |                           |
|--|---|---------------------------|
| <b>1. Name of the project</b>  | <b>Punjab Cities Program<br/>Improvement &amp; Rehabilitation of P1-Gojra Toba Road Project in Gojra city</b>   |                           |
| <b>2.Location</b>  | Gojra was given the status of a Tehsil Headquarter and affiliated with newly established district Toba Tek Singh in 1982.The town of Gojra is located at 72°-41' East and 31°-9' North. The city is located at 50 km from Faisalabad, 170 km from Lahore and 32 km north of Toba Tek Singh. Location map of the city is attached in <b>Annexure-A</b> |                           |
| <b>3. Authorities responsible for</b>  |   |                           |
| i- Sponsoring  | Government of the Punjab (through World Bank funding)   |                           |
| ii- Execution  | Municipal Committee Gojra   |                           |
| iii- Operation and Maintenance   | Municipal Committee Gojra   |                           |
| iv-Concerned Provincial Department   | Local Government and Community Development Department Punjab  |                           |
| <b>4a.Plan Provision</b>   |   |                           |
| i. If the project is included in medium term/five year plan, specify actual allocation | Punjab Cities Program (PCP) is a World Bank funded Program with a total cost of USD 236.00 million and comprises of below mentioned components.   |                           |
|  | Total loan from World Bank  | USD 200.00 million        |
|  | Component-1 Infrastructure development (PforR)  | USD 180.00 million<br>USD |
|  | Component-2 Technical Assistance  | USD 20.00 million         |
|  | MCs share (20% of PforR component) equivalent to:   | USD 36.00 million         |
|  | Total Program cost  | USD 236.00 million        |
|  | Component-1 i-e Infra Structure Development component of Program costing USD 180.00 million is meant for management cost of the Program and capacity building of Municipal Units & Government Departments and   |                           |

|  |   |
|--|---|
|  | is included in the medium term/ five-year plan and has been funded now in ADP 2022-23 - under General Serial No-1769 with allocation of PKR 1329.90 million as foreign component.   |
| ii- If not included in the current plan, what warrants its inclusion and how it is now proposed to be accommodated | Not applicable  |
| iii If the project is proposed to be financed out of block provision indicate.                                     | The Project is being financed by World Bank as Donor along with 20% co-financing from the Program Units and is not proposed to be financed out of block allocation.   |
| 4b- Provision in the current year PSDP/ADP   | PKR.1329.90 million under ADP 2022-23 General Serial No 1769 for Component-1 of the Program i-e Infra Structure Development as described above.   |
| 5. Project objectives and its relationship with sector objectives  | <p><b><u>Sector Objectives</u></b><br/>The sector objectives include:</p> <ol style="list-style-type: none"> <li>1. Provision of efficient and effective municipality services to the masses.</li> <li>2. Community development through improving basic infrastructure.</li> <li>3. Clean and green environment for better living standards.</li> <li>4. Effective use of land through master planning of urban areas.</li> <li>5. Social uplifting and cohesion through provision of public open spaces and play grounds.</li> <li>6. Ease in mobility and communication.</li> <li>7. Cost efficient Solid Waste Management through waste to energy initiatives.</li> <li>8. Capacity building of Local Governments.</li> <li>9. Efficient Road network to make areas easily accessible</li> </ol> <p><b><u>Objectives of the Project</u></b><br/>The Project aims at improvement of infrastructure of municipal services such as roads, chowks, cross roads, street lights, parks and parking shed for SWM machinery for improved communication and recreational facilities.</p> <p>Scope of the work for this particular project includes the rehabilitation and improvement of existing roads, chowks and drainage system along with the construction of new drainage system where needed. However, the cleaning and de-silting of existing drains and pipes will be arranged by MC Gojra from their own resources.</p> |



|   |  |
|---|--|
|   | <p>The Project has the following objectives;</p> <ol style="list-style-type: none"> <li>1. Improvement of service delivery level of the municipal services in the sector of communication.</li> <li>2. Better travelling facilities for the commuters.</li> <li>3. Reduction in road accidents.</li> <li>4. Saving in travelling and repair cost of the vehicles.</li> <li>5. Reduction in annual maintenance charges of roads and parks</li> <li>6. Better lit roads and streets adding to security of people travelling at night.</li> <li>7. Improvement in environments of the city making them livable.</li> <li>8. Improvement in local and province economy.</li> <li>9. Improvement in the economic growth potential of the city.</li> </ol> <p>Hence, the objectives of the project are in line with the sector objectives mentioned at Sr. No-1, 2, 3, 5 and 6 above and the project forms integral part of the concerned sector.</p>  |
| <p><b>6. Description, justification, technical parameters and technology transfer aspects</b></p> |  |
| <p>i. Present Condition</p>   | <p>As per PLGA-12019 Urban Local Governments (ULGs) are basically and wholly responsible for delivery of the municipal services with a service delivery level which should satisfy the consumers and citizen. Unfortunately, the prevalent conditions of the service delivery are not encouraging in the city.</p> <p>The major reason of unsatisfactory service delivery is the lack of proper maintenance of the municipal infrastructure in all sectors causing consumer dissatisfaction at one end and degradation of the infrastructure on the other end apart from very low revenue recovery as the consumers are reluctant to pay because of deteriorated service delivery.</p> <p>The roads infrastructure has been damaged and degraded because of lack of repairs and upgradation due to shortage of money and constrained municipal budgets. If these roads &amp; chowks are not improved at this stage, then this infrastructure will be further damaged / degraded giving financial loss to the public as well as private sectors and the growth potential of the city will be adversely affected. Damaged roads will increase the operational expenditure of the vehicles apart from wasting time and giving rise to public frustration and mental agony.</p> <p>The only way to keep the infrastructure in operational and functional condition for better travelling and recreational facilities to the inhabitants of the city and the surrounding areas, is to improve the roads, chowks and important cross roads</p> |

| ii. Description of the subproject-  | The project comprises of improvement of <b>01 Nos</b> damaged roads with total length of <b>3.1 Km</b> in the city. Detail of these roads has been given in the table below.  |  |   |                    |   |                          |              |         |                            |       |                    |  |   |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |
|---|---|--|---|--------------------|---|--------------------------|--------------|---------|----------------------------|-------|--------------------|--|---|---|--|------|---|-----------|------|--|--------------|---------------|---|-------------------|------|---|----------------------|-------|---|-----------------------|-------|--|--------------------|----------------|
| iii Detail of civil works, equipment & machinery and other physical facilities                  | <p>The detail of roads and chowks to be improved, rehabilitated or constructed in the city, is given below</p> <table border="1" data-bbox="544 405 1473 842"> <thead> <tr> <th colspan="4">Improvement and construction of roads</th> </tr> <tr> <th>S. N.</th> <th>Name of road</th> <th>From-To</th> <th>Detail of works involved</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>P1-Gojra Toba Road</td> <td>MC Limit Via Railway Crossing Chowk to Gojra By Pass</td> <td> <ul style="list-style-type: none"> <li>• Geometric Improvement</li> <li>• Rehabilitation of Existing Pavement Structure</li> <li>• Pavement Marking</li> <li>• Street Lighting</li> <li>• Improvement of drainage system</li> </ul> </td> </tr> </tbody> </table>   | Improvement and construction of roads                |   |                    |   | S. N.                    | Name of road | From-To | Detail of works involved   | 1     | P1-Gojra Toba Road | MC Limit Via Railway Crossing Chowk to Gojra By Pass | <ul style="list-style-type: none"> <li>• Geometric Improvement</li> <li>• Rehabilitation of Existing Pavement Structure</li> <li>• Pavement Marking</li> <li>• Street Lighting</li> <li>• Improvement of drainage system</li> </ul> |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |
| Improvement and construction of roads   |   |  |   |                    |   |                          |              |         |                            |       |                    |  |   |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |
| S. N.   | Name of road  | From-To  | Detail of works involved  |                    |   |                          |              |         |                            |       |                    |  |   |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |
| 1   | P1-Gojra Toba Road  | MC Limit Via Railway Crossing Chowk to Gojra By Pass | <ul style="list-style-type: none"> <li>• Geometric Improvement</li> <li>• Rehabilitation of Existing Pavement Structure</li> <li>• Pavement Marking</li> <li>• Street Lighting</li> <li>• Improvement of drainage system</li> </ul> |                    |   |                          |              |         |                            |       |                    |  |   |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |
| iv Indicate governess issues of the sector relevant to the project and strategy to resolve them | <ul style="list-style-type: none"> <li>• MC Gojra is facing acute shortage of staff. The smooth sailing of the Punjab Cities Program can only be assured when the required staff is available with Unit.</li> <li>• The Repair and maintenance of the municipal services is not up to the mark in such Unit. Trainings will be imparted by PMDFC to the officers as well as the field staff under the Program but practicing the interventions and method/procedures learnt in these trainings is the actual requirement in which Units are lacking at present. Hence inculcating the mind set for good repair and maintenance is the major requirement for improving the service delivery level.</li> </ul>  |  |   |                    |   |                          |              |         |                            |       |                    |  |   |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |
| <b>7- Capital Cost of Project</b>   | <p>The summary of the works included in the project is given below;</p> <table border="1" data-bbox="544 1357 1473 1883"> <thead> <tr> <th>S. No</th> <th>Name of road</th> <th>Cost (PKR million)</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>P1-Gojra Toba Road Works</td> <td>182.69</td> </tr> <tr> <td>2</td> <td>Stormwater Drainage System</td> <td>36.61</td> </tr> <tr> <td>3</td> <td>Electrical Works</td> <td>36.94</td> </tr> <tr> <td>4</td> <td>Environment And Social Mitigation Cost</td> <td>1.33</td> </tr> <tr> <td>5</td> <td>ARAP Cost</td> <td>0.54</td> </tr> <tr> <td></td> <td style="text-align: right;"><b>Total</b></td> <td><b>258.14</b></td> </tr> <tr> <td>6</td> <td>Contingencies @2%</td> <td>5.16</td> </tr> <tr> <td>7</td> <td>Punjab Sales Tax @5%</td> <td>12.90</td> </tr> <tr> <td>8</td> <td>Price Escalation @ 6%</td> <td>15.48</td> </tr> <tr> <td></td> <td style="text-align: right;"><b>Grand Total</b></td> <td><b>291.705</b></td> </tr> </tbody> </table> <p>See <b>Annexure-B</b> for details</p> | S. No  | Name of road  | Cost (PKR million) | 1 | P1-Gojra Toba Road Works | 182.69       | 2       | Stormwater Drainage System | 36.61 | 3                  | Electrical Works                                     | 36.94   | 4 | Environment And Social Mitigation Cost | 1.33 | 5 | ARAP Cost | 0.54 |  | <b>Total</b> | <b>258.14</b> | 6 | Contingencies @2% | 5.16 | 7 | Punjab Sales Tax @5% | 12.90 | 8 | Price Escalation @ 6% | 15.48 |  | <b>Grand Total</b> | <b>291.705</b> |
| S. No   | Name of road  | Cost (PKR million)                                   |   |                    |   |                          |              |         |                            |       |                    |  |   |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |
| 1   | P1-Gojra Toba Road Works  | 182.69   |   |                    |   |                          |              |         |                            |       |                    |  |   |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |
| 2   | Stormwater Drainage System  | 36.61  |   |                    |   |                          |              |         |                            |       |                    |  |   |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |
| 3   | Electrical Works  | 36.94  |   |                    |   |                          |              |         |                            |       |                    |  |   |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |
| 4   | Environment And Social Mitigation Cost  | 1.33   |   |                    |   |                          |              |         |                            |       |                    |  |   |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |
| 5   | ARAP Cost   | 0.54   |   |                    |   |                          |              |         |                            |       |                    |  |   |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |
|   | <b>Total</b>  | <b>258.14</b>  |   |                    |   |                          |              |         |                            |       |                    |  |   |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |
| 6   | Contingencies @2%   | 5.16   |   |                    |   |                          |              |         |                            |       |                    |  |   |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |
| 7   | Punjab Sales Tax @5%  | 12.90  |   |                    |   |                          |              |         |                            |       |                    |  |   |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |
| 8   | Price Escalation @ 6%   | 15.48  |   |                    |   |                          |              |         |                            |       |                    |  |   |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |
|   | <b>Grand Total</b>  | <b>291.705</b>                                       |   |                    |   |                          |              |         |                            |       |                    |  |   |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |
| i- Indicate date of estimation of the project cost  | The project estimates have been framed during the month of March 2023.  |  |   |                    |   |                          |              |         |                            |       |                    |  |   |   |  |      |   |           |      |  |              |               |   |                   |      |   |                      |       |   |                       |       |  |                    |                |

| ii- Basis of determining the estimates be provided.                             | <p>The cost estimates have been framed on the basis of bill of quantities actually required at site and unit rates from the Market Rate System (MRS) issued by the Government of Punjab (District Toba Tek Singh 1<sup>st</sup> biannual of year 2023).</p> <p>For items not available in the MRS, the same have been analyzed as per prevailing market rates.</p>   |                     |                       |                     |                       |                    |                          |        |        |   |                            |       |       |   |                  |       |       |   |  |      |      |   |           |      |      |  |              |               |               |   |                   |      |      |   |                      |       |       |   |                       |       |       |  |                    |                |                |
|---|--|---------------------|-----------------------|---------------------|-----------------------|--------------------|--------------------------|--------|--------|---|----------------------------|-------|-------|---|------------------|-------|-------|---|--|------|------|---|-----------|------|------|--|--------------|---------------|---------------|---|-------------------|------|------|---|----------------------|-------|-------|---|-----------------------|-------|-------|--|--------------------|----------------|----------------|
| iii- Provide year wise estimation of physical activities                        | <p>The physical and financial requirements, year wise are included in the following table:</p> <table border="1" data-bbox="547 577 1441 701"> <thead> <tr> <th data-bbox="547 577 619 656">S. #</th> <th data-bbox="619 577 1249 656">Name of road / chowk</th> <th data-bbox="1249 577 1441 656">Year 2022-2023</th> </tr> </thead> <tbody> <tr> <td data-bbox="547 656 619 701">1</td> <td data-bbox="619 656 1249 701">P1-Gojra Toba Road</td> <td data-bbox="1249 656 1441 701">100%</td> </tr> </tbody> </table>   | S. #                | Name of road / chowk  | Year 2022-2023      | 1                     | P1-Gojra Toba Road | 100%                     |        |        |   |                            |       |       |   |                  |       |       |   |  |      |      |   |           |      |      |  |              |               |               |   |                   |      |      |   |                      |       |       |   |                       |       |       |  |                    |                |                |
| S. #  | Name of road / chowk   | Year 2022-2023      |                       |                     |                       |                    |                          |        |        |   |                            |       |       |   |                  |       |       |   |  |      |      |   |           |      |      |  |              |               |               |   |                   |      |      |   |                      |       |       |   |                       |       |       |  |                    |                |                |
| 1   | P1-Gojra Toba Road   | 100%                |                       |                     |                       |                    |                          |        |        |   |                            |       |       |   |                  |       |       |   |  |      |      |   |           |      |      |  |              |               |               |   |                   |      |      |   |                      |       |       |   |                       |       |       |  |                    |                |                |
| iv- Phasing of capital cost on the basis of each item of work.                  | <p>The phasing of capital cost of the project is included in the following table:</p> <p>(All figures are in million rupees)</p> <table border="1" data-bbox="547 846 1485 1440"> <thead> <tr> <th data-bbox="547 846 603 969">S. #</th> <th data-bbox="603 846 1121 969">Items of Road/chowk</th> <th data-bbox="1121 846 1313 969">Total (PKR million)</th> <th data-bbox="1313 846 1485 969">Year 2022-2023 (100%)</th> </tr> </thead> <tbody> <tr> <td data-bbox="547 969 603 1014">1</td> <td data-bbox="603 969 1121 1014">P1-Gojra Toba Road Works</td> <td data-bbox="1121 969 1313 1014">182.69</td> <td data-bbox="1313 969 1485 1014">182.69</td> </tr> <tr> <td data-bbox="547 1014 603 1059">2</td> <td data-bbox="603 1014 1121 1059">Stormwater Drainage System</td> <td data-bbox="1121 1014 1313 1059">36.61</td> <td data-bbox="1313 1014 1485 1059">36.61</td> </tr> <tr> <td data-bbox="547 1059 603 1104">3</td> <td data-bbox="603 1059 1121 1104">Electrical Works</td> <td data-bbox="1121 1059 1313 1104">36.94</td> <td data-bbox="1313 1059 1485 1104">36.94</td> </tr> <tr> <td data-bbox="547 1104 603 1193">4</td> <td data-bbox="603 1104 1121 1193">Environment and Social Mitigation Cost</td> <td data-bbox="1121 1104 1313 1193">1.33</td> <td data-bbox="1313 1104 1485 1193">1.33</td> </tr> <tr> <td data-bbox="547 1193 603 1238">5</td> <td data-bbox="603 1193 1121 1238">ARAP Cost</td> <td data-bbox="1121 1193 1313 1238">0.54</td> <td data-bbox="1313 1193 1485 1238">0.54</td> </tr> <tr> <td data-bbox="547 1238 603 1283"></td> <td data-bbox="603 1238 1121 1283"><b>Total</b></td> <td data-bbox="1121 1238 1313 1283"><b>258.14</b></td> <td data-bbox="1313 1238 1485 1283"><b>258.14</b></td> </tr> <tr> <td data-bbox="547 1283 603 1328">6</td> <td data-bbox="603 1283 1121 1328">Contingencies @2%</td> <td data-bbox="1121 1283 1313 1328">5.16</td> <td data-bbox="1313 1283 1485 1328">5.16</td> </tr> <tr> <td data-bbox="547 1328 603 1373">7</td> <td data-bbox="603 1328 1121 1373">Punjab Sales Tax @5%</td> <td data-bbox="1121 1328 1313 1373">12.90</td> <td data-bbox="1313 1328 1485 1373">12.90</td> </tr> <tr> <td data-bbox="547 1373 603 1417">8</td> <td data-bbox="603 1373 1121 1417">Price Escalation @ 6%</td> <td data-bbox="1121 1373 1313 1417">15.48</td> <td data-bbox="1313 1373 1485 1417">15.48</td> </tr> <tr> <td data-bbox="547 1417 603 1451"></td> <td data-bbox="603 1417 1121 1451"><b>Grand Total</b></td> <td data-bbox="1121 1417 1313 1451"><b>291.705</b></td> <td data-bbox="1313 1417 1485 1451"><b>291.705</b></td> </tr> </tbody> </table> | S. #                | Items of Road/chowk   | Total (PKR million) | Year 2022-2023 (100%) | 1                  | P1-Gojra Toba Road Works | 182.69 | 182.69 | 2 | Stormwater Drainage System | 36.61 | 36.61 | 3 | Electrical Works | 36.94 | 36.94 | 4 | Environment and Social Mitigation Cost | 1.33 | 1.33 | 5 | ARAP Cost | 0.54 | 0.54 |  | <b>Total</b> | <b>258.14</b> | <b>258.14</b> | 6 | Contingencies @2% | 5.16 | 5.16 | 7 | Punjab Sales Tax @5% | 12.90 | 12.90 | 8 | Price Escalation @ 6% | 15.48 | 15.48 |  | <b>Grand Total</b> | <b>291.705</b> | <b>291.705</b> |
| S. #  | Items of Road/chowk  | Total (PKR million) | Year 2022-2023 (100%) |                     |                       |                    |                          |        |        |   |                            |       |       |   |                  |       |       |   |  |      |      |   |           |      |      |  |              |               |               |   |                   |      |      |   |                      |       |       |   |                       |       |       |  |                    |                |                |
| 1   | P1-Gojra Toba Road Works   | 182.69              | 182.69                |                     |                       |                    |                          |        |        |   |                            |       |       |   |                  |       |       |   |  |      |      |   |           |      |      |  |              |               |               |   |                   |      |      |   |                      |       |       |   |                       |       |       |  |                    |                |                |
| 2   | Stormwater Drainage System   | 36.61               | 36.61                 |                     |                       |                    |                          |        |        |   |                            |       |       |   |                  |       |       |   |  |      |      |   |           |      |      |  |              |               |               |   |                   |      |      |   |                      |       |       |   |                       |       |       |  |                    |                |                |
| 3   | Electrical Works   | 36.94               | 36.94                 |                     |                       |                    |                          |        |        |   |                            |       |       |   |                  |       |       |   |  |      |      |   |           |      |      |  |              |               |               |   |                   |      |      |   |                      |       |       |   |                       |       |       |  |                    |                |                |
| 4   | Environment and Social Mitigation Cost   | 1.33                | 1.33                  |                     |                       |                    |                          |        |        |   |                            |       |       |   |                  |       |       |   |  |      |      |   |           |      |      |  |              |               |               |   |                   |      |      |   |                      |       |       |   |                       |       |       |  |                    |                |                |
| 5   | ARAP Cost  | 0.54                | 0.54                  |                     |                       |                    |                          |        |        |   |                            |       |       |   |                  |       |       |   |  |      |      |   |           |      |      |  |              |               |               |   |                   |      |      |   |                      |       |       |   |                       |       |       |  |                    |                |                |
|   | <b>Total</b>   | <b>258.14</b>       | <b>258.14</b>         |                     |                       |                    |                          |        |        |   |                            |       |       |   |                  |       |       |   |  |      |      |   |           |      |      |  |              |               |               |   |                   |      |      |   |                      |       |       |   |                       |       |       |  |                    |                |                |
| 6   | Contingencies @2%  | 5.16                | 5.16                  |                     |                       |                    |                          |        |        |   |                            |       |       |   |                  |       |       |   |  |      |      |   |           |      |      |  |              |               |               |   |                   |      |      |   |                      |       |       |   |                       |       |       |  |                    |                |                |
| 7   | Punjab Sales Tax @5%   | 12.90               | 12.90                 |                     |                       |                    |                          |        |        |   |                            |       |       |   |                  |       |       |   |  |      |      |   |           |      |      |  |              |               |               |   |                   |      |      |   |                      |       |       |   |                       |       |       |  |                    |                |                |
| 8   | Price Escalation @ 6%  | 15.48               | 15.48                 |                     |                       |                    |                          |        |        |   |                            |       |       |   |                  |       |       |   |  |      |      |   |           |      |      |  |              |               |               |   |                   |      |      |   |                      |       |       |   |                       |       |       |  |                    |                |                |
|   | <b>Grand Total</b>   | <b>291.705</b>      | <b>291.705</b>        |                     |                       |                    |                          |        |        |   |                            |       |       |   |                  |       |       |   |  |      |      |   |           |      |      |  |              |               |               |   |                   |      |      |   |                      |       |       |   |                       |       |       |  |                    |                |                |
| 8-Annual recurrent cost after completion of the project and source of financing | <p>The roads &amp; chowks are already being repaired and maintained by MC Gojra out of its own financial resources. No additional cost will be required after completion of the improvement and upgradation of the roads and chowks, rather the repairs cost will be reduced for the initial years. However, the efficiency of the infrastructure and service delivery level will be improved after completion of the project.</p>   |                     |                       |                     |                       |                    |                          |        |        |   |                            |       |       |   |                  |       |       |   |  |      |      |   |           |      |      |  |              |               |               |   |                   |      |      |   |                      |       |       |   |                       |       |       |  |                    |                |                |
| 9- Demand & Supply Analysis<br><br>i- Existing Capacity of services             | <p><b>Existing supply level</b></p> <ul style="list-style-type: none"> <li>Existing geometry of the roads and chowk is not well enough to sustain the smooth traffic flow. Existing pavement structure of the roads and chowk is deteriorated which needs the rehabilitation to bear the traffic loading and better riding quality.</li> <li>DC T.T Singh Unit Gojra is unable to render satisfactory service to the entire area of the city because of degraded infrastructure wherein some rehabilitation and improvement are direly needed but could not</li> </ul>   |                     |                       |                     |                       |                    |                          |        |        |   |                            |       |       |   |                  |       |       |   |  |      |      |   |           |      |      |  |              |               |               |   |                   |      |      |   |                      |       |       |   |                       |       |       |  |                    |                |                |

|  |  |
|--|--|
|  | <p>be able to accomplish them because of low revenue recovery and funding constraints. Very few areas are reasonably served but others are deprived of the required level of the service. This is resulting in low credibility of the municipal services and citizen dissatisfaction. Further the infrastructure has not been developed and extended keeping in pace with the growth of population mainly due to migration from rural areas to urban areas. The market prices of the materials and labor have also increased drastically during the last decade which increased the O&amp;M cost of services. This has further degraded the situation and the service delivery level is further deteriorating.</p>   |
| ii- Projected Demand for 10 years  | <ul style="list-style-type: none"> <li>• Traffic is increasing day by day in Gojra city. Projected traffic of 1 project roads for 10 year is 44.5 million. Project roads of Unit Gojra needs to be improved to save the travel time and better riding quality.</li> <li>• The municipal services require radical improvement to enhance the efficiency of the service to increase service delivery to a satisfactory level. For this purpose, the existing infrastructure will have to be improved.</li> <li>• Many shortcomings, problems and bottlenecks have been observed in the existing infrastructure which could not be addressed by MC due to funding constraints and now have been proposed to be addressed by rehabilitation of defective and outlived components of all the municipal services infrastructure.</li> </ul>  |
| iii- Capacity of other similar projects being implemented in public/private sector | <p>No other project of this nature is being implemented in public as well as private sector because of funding constrains in the Unit.</p>   |
| iv- Supply and Demand gaps   | <p>The nature of supply and demand gap has been explained in the preceding paras which concludes;</p> <ul style="list-style-type: none"> <li>• Existing condition of the road network is not good enough to bear the traffic load. It's causing excessive delays, increasing travel time, occurring accidents at intersections and vehicles wear and tear due to the poor condition of pavement surface. Increasing traffic load requires the improvement of existing road network and chowk.</li> <li>• The existing infrastructure has poor efficiency resulting in unsatisfactory service delivery level.</li> <li>• The O&amp;M cost of the infrastructure services is very high because of low efficiency and high market rates while there in a large gap between the O&amp;M expenditure and the revenue recovery.</li> <li>• Large subsidies are being injected by Municipal Units to the keep the services in operation</li> <li>• Numerous public complaints are the talk of the day.</li> </ul> |

|  | <ul style="list-style-type: none"> <li>Unsatisfactory municipal delivery is not encouraging the city to become engines of economic growth and hence the GDP of our city is much lower than the peers in the developing world.</li> </ul> <p>Hence there is a large gap between the supply and demand which is to be bridged by improvement in the infrastructure and its management.</p>  |  |                    |  |                             |  |                    |  |                |  |                    |                          |                  |             |                             |   |     |
|--|---|--|--------------------|--|-----------------------------|--|--------------------|--|----------------|--|--------------------|--------------------------|------------------|-------------|-----------------------------|---|-----|
| v-Designed capacity and output of the project  | <p>1. Table showing Name of roads, From and to reaches, length, ROW, metaled width and type of pavement of each road and total length is given below:</p> <table border="1" data-bbox="544 616 1489 907"> <thead> <tr> <th>Sr. #</th> <th>Road Name</th> <th>From and To</th> <th>Pavement Type</th> <th>ROW</th> <th>Carriageway Type</th> <th>Metaled Width</th> <th>Length (km)</th> </tr> </thead> <tbody> <tr> <td>2</td> <td>P1-Gojra Toba Road</td> <td>MC limit to Gojra bypass</td> <td>Asphalt Concrete</td> <td>72ft varies</td> <td>Single and Dual with Median</td> <td>15 ft single varies 53 ft dual (varies)</td> <td>3.1</td> </tr> </tbody> </table> <p>2. Roads and chowk are designed for 10-year life.<br/> 3. These roads will carry out the 44 Million traffic cumulatively for 10 years.<br/> 4. Improvement of these roads and chowk will decrease the travel time of commuters which will ultimately improve the economy of city.</p> | Sr. #  | Road Name          | From and To                                    | Pavement Type               | ROW  | Carriageway Type   | Metaled Width                                | Length (km)    | 2  | P1-Gojra Toba Road | MC limit to Gojra bypass | Asphalt Concrete | 72ft varies | Single and Dual with Median | 15 ft single varies 53 ft dual (varies) | 3.1 |
| Sr. #  | Road Name   | From and To  | Pavement Type      | ROW  | Carriageway Type            | Metaled Width  | Length (km)        |  |                |  |                    |                          |                  |             |                             |   |     |
| 2  | P1-Gojra Toba Road  | MC limit to Gojra bypass                                   | Asphalt Concrete   | 72ft varies                                    | Single and Dual with Median | 15 ft single varies 53 ft dual (varies)  | 3.1                |  |                |  |                    |                          |                  |             |                             |   |     |
| <b>10. Financial Plan</b><br><b>Sources of financing</b><br><u>Debt</u><br>a) Indicate the local and foreign debt Loan       | <p>Below given loan for the Punjab Cities Program has been funded by World Bank for 16 PCP cities in Punjab.</p> <table border="1" data-bbox="544 1288 1489 1624"> <tr> <td>Total loan to Government of Pakistan/Punjab</td> <td>USD 200 million</td> </tr> <tr> <td>Component-1 for Infrastructure Development</td> <td>USD 180 million</td> </tr> <tr> <td>Component-2 for Investment Project Financing For capacity building of MCs &amp; three Govt. organization and program management.</td> <td>USD 20 million</td> </tr> <tr> <td>20% share of Municipalities is equivalent to</td> <td>USD 36 million</td> </tr> <tr> <td>Total funds available for Infrastructure Development</td> <td>USD 216 million</td> </tr> </table> <p>This project will be funded under this financing.</p>   | Total loan to Government of Pakistan/Punjab                | USD 200 million    | Component-1 for Infrastructure Development     | USD 180 million             | Component-2 for Investment Project Financing For capacity building of MCs & three Govt. organization and program management. | USD 20 million     | 20% share of Municipalities is equivalent to | USD 36 million | Total funds available for Infrastructure Development | USD 216 million    |                          |                  |             |                             |   |     |
| Total loan to Government of Pakistan/Punjab  | USD 200 million   |  |                    |  |                             |  |                    |  |                |  |                    |                          |                  |             |                             |   |     |
| Component-1 for Infrastructure Development   | USD 180 million   |  |                    |  |                             |  |                    |  |                |  |                    |                          |                  |             |                             |   |     |
| Component-2 for Investment Project Financing For capacity building of MCs & three Govt. organization and program management. | USD 20 million  |  |                    |  |                             |  |                    |  |                |  |                    |                          |                  |             |                             |   |     |
| 20% share of Municipalities is equivalent to   | USD 36 million  |  |                    |  |                             |  |                    |  |                |  |                    |                          |                  |             |                             |   |     |
| Total funds available for Infrastructure Development   | USD 216 million   |  |                    |  |                             |  |                    |  |                |  |                    |                          |                  |             |                             |   |     |
| b) Equity  | <p><b>A. Loan/grant to MC</b></p> <p>The amount of loan converted to grant to Gojra Unit will be <b>PKR. (233.36) million</b>. The financing of the project will be as given below:</p> <table border="1" data-bbox="544 1848 1489 2054"> <tr> <td>Grant to Unit for the year 2022-2023 (80% of cost of PC-I)</td> <td>PKR 233.36 million</td> </tr> <tr> <td>20% Co-finance by MC (20% of the cost of PC-I)</td> <td>PKR 58.34 million</td> </tr> <tr> <td>Total available funds</td> <td>PKR 291.70 million</td> </tr> </table>   | Grant to Unit for the year 2022-2023 (80% of cost of PC-I) | PKR 233.36 million | 20% Co-finance by MC (20% of the cost of PC-I) | PKR 58.34 million           | Total available funds  | PKR 291.70 million |  |                |  |                    |                          |                  |             |                             |   |     |
| Grant to Unit for the year 2022-2023 (80% of cost of PC-I)   | PKR 233.36 million  |  |                    |  |                             |  |                    |  |                |  |                    |                          |                  |             |                             |   |     |
| 20% Co-finance by MC (20% of the cost of PC-I)   | PKR 58.34 million   |  |                    |  |                             |  |                    |  |                |  |                    |                          |                  |             |                             |   |     |
| Total available funds  | PKR 291.70 million  |  |                    |  |                             |  |                    |  |                |  |                    |                          |                  |             |                             |   |     |

|   |  |
|---|--|
|   | <p><b>B. Project Cost PKR 291.70 million</b></p> <p>*The loan is from World Bank to Government of Pakistan/Punjab which will trickle down to Gojra Unit as grant.</p>  |
| c) Grants   | No grant is being given by Government of Punjab out of ADP funds. The World Bank loan to Government of Pakistan/Punjab will trickle down as grant to MC Gojra from Government of Punjab.   |
| d) Weighted cost of capital                           | Nil  |
| <b>11-Project benefits and analysis</b>               |  |
| i.Financial:<br>Income to the project with assumption | <ul style="list-style-type: none"> <li>• The project comprises of improvement of roads, chowks and cross roads in the city.</li> <li>• Gojra Unit has no plan to levy user charges /toll tax on the roads as these are internal roads of city and levying of toll tax is not feasible.</li> <li>• However, it is an infrastructure sector project but the capital cost of the project is not intended to be recovered. The MC will meet the cost of repair and maintenance out of its own resources. The project economic analysis is given as <b>Annexure-C</b>.</li> </ul>   |
| ii.Social benefits to the target group                | <p>The completion of the project will result in:</p> <ul style="list-style-type: none"> <li>• Up gradation of the infrastructure.</li> <li>• Enhanced life of the roads and chowks.</li> <li>• Reduction in travelling time of the commuters.</li> <li>• Reduction of road accidents.</li> <li>• Reduction in consumption of POL resulting in saving of the foreign exchange.</li> <li>• Reduction in the operation and maintenance cost of the vehicles.</li> <li>• Improvement in the environment of the city;</li> <li>• Minimized public mental tension and frustration</li> <li>• Improved local economy</li> <li>• Improvement of city growth potential</li> </ul>   |
| iii.Environmental Impact negative/positive            | <p>Construction/Rehabilitation of Roads and Chowks and their subsequent long-term use lead to many changes in the environment. There will be some negative impacts during rehabilitation of the Roads and Chowks in the form of noise of the machinery, dismantling of the existing roads, dust pollution, nuisance caused by higher traffic, risked caused by animal intersecting routes or consequences of any crossing water courses etc. Therefore, it is recommended to develop variant solutions in order to choose the one that would be least harmful to the environment, and then to incorporate them in an Environmental and Social Management Framework. However, the impacts will be temporary and there will be no negative impacts after completion of the project, rather, positive impacts, because of improvement in environments of the city, will be observed and</p> |

|  |   |                      |                    |                                     |                 |                              |             |
|--|---|----------------------|--------------------|-------------------------------------|-----------------|------------------------------|-------------|
|  | <p>present traffic hazards and jams will be eliminated. Hence overall positive impacts will be experienced due to execution and operation of the sub-projects.</p> <p>To facilitate the selection of an optimal solution and for the inclusion of Safe Operating Procedures for Construction workers/labors; assessment indicators or an Environmental Screening Checklists have been developed which is attached as Annexure E (A) of this PC-1. The checklist focuses on Environmental Issues and social concerns and ensure that all environmental and social dimensions are adequately considered. Based on. The Environment, Health and Safety SOPs for labor/workers are provided as Annexure E (B).</p> <p>E&amp;S Screening Involuntary resettlement checklists and Environment &amp; Social Mitigation plan will be the part of bidding documents</p>  |                      |                    |                                     |                 |                              |             |
| iv.Quantifiable project outputs                | <p>The quantifiable project out puts have been given above in Sr. No-9 (V). The social benefits to the citizen have been described at Sr. No-11(ii).</p>  |                      |                    |                                     |                 |                              |             |
| v.Unit cost analysis                           | <p>The unit cost analysis is produced below;</p> <table border="1" data-bbox="555 869 1469 1003"> <tr> <td>Project capital cost</td> <td>PKR 291.70 million</td> </tr> <tr> <td>Population of the city in year 2023</td> <td>276,925 persons</td> </tr> <tr> <td>Unit capital cost per capita</td> <td>PKR 1053.36</td> </tr> </table> <ul style="list-style-type: none"> <li>• Unit R&amp;M cost: – The Repair &amp; maintenance cost is already being borne by Gojra Unit and there will be no increase in this cost. Due to improvement of the infrastructure R&amp;M cost will reduce for at least 5 years after completion of the project.</li> </ul>  | Project capital cost | PKR 291.70 million | Population of the city in year 2023 | 276,925 persons | Unit capital cost per capita | PKR 1053.36 |
| Project capital cost                           | PKR 291.70 million  |                      |                    |                                     |                 |                              |             |
| Population of the city in year 2023            | 276,925 persons   |                      |                    |                                     |                 |                              |             |
| Unit capital cost per capita                   | PKR 1053.36   |                      |                    |                                     |                 |                              |             |
| vi.Employment generation (direct and indirect) | <p><b><u>Employment Analysis</u></b></p> <p><b>Direct Employment</b></p> <p><i>a) Planning and Design of projects</i></p> <p>The planning and design of the project has been entrusted to local consultants who have appointed staff and experts in road and related disciplines along with their support staff. The consultants will also appoint their staff for resident supervision of the project to verify and certify the items of works to be executed under this PC-I.</p> <p><b>b) Execution of the Project</b></p> <p><i>a) PMDFC</i></p> <p>PMDFC has the project monitoring and supervisory role and the company has enough experts and staff to complete this assignment. PMDFC has already deployed under mentioned staff for these projects:</p> <ul style="list-style-type: none"> <li>• Civil Engineers</li> <li>• Accounts, administration and audit personnel</li> <li>• Urban planners</li> <li>• GIS experts</li> </ul> |                      |                    |                                     |                 |                              |             |



|  |   |
|--|---|
|  | <ul style="list-style-type: none"> <li>• Support staff like computer operators, vehicle drivers, office boys and guards.</li> <li>• Procurement experts</li> <li>• Communication experts</li> <li>• Environmental and social experts</li> <li>• Contract management experts</li> </ul> <p><b>b) Consultants</b><br/>PMDFC has employed consultants for detailed design and resident supervision of the projects who will deploy their staff for execution of the project.</p> <p><b>c) Municipality</b><br/>Gojra Unit has regular staff like engineers, sub engineers and other administrative &amp; accounts keeping staff which will be responsible for execution of the project and contract management. No additional staff will be needed for execution of this project</p> <p><b>d) Contractor</b><br/>The contractor responsible for execution of the sub project will employ skilled and un-skilled labor on this work.</p> <p><b>Indirect Employment</b><br/>Indirect employment for production of material such as cement, steel, stone metal, bitumen, bricks etc. will be generated.</p> |
| vii. Impacts of delays on project cost and viability                 | <p>The impact of delay in project implementation will;</p> <ul style="list-style-type: none"> <li>• Result in increased project cost due to escalation in cost of material and labor.</li> <li>• Delay the benefits to the target group</li> <li>• Result in further deterioration of the infrastructure and the service delivery level.</li> </ul>   |
| <b>12-Implementation Schedule</b>                                    |   |
| a) Indicate starting and completion date of the project              | The project is anticipated to commence by May 2023 and to be completed by August 2023 with project implementation period of 4 months.   |
| b) Item wise/year wise schedule in line chart                        | The Gantt chart has been attached at <b>Annexure-D</b>  |
| <b>13- Management Structure and manpower requirements</b>            |   |
| i. Administrative arrangements for the implementation of the project | <p><b>ii. Planning &amp; design of the project</b><br/>The project has been designed by the consultants employed by PMDFC and will also carry out the resident supervision of the project.</p> <p><b>iii. Preparation of cost estimation</b></p>  |


|   |   |  |  |  |  |
|---|---|--|--|--|--|
|   | <p>The cost estimates have been prepared by the design consultants by actual measurements are required at site. The execution of the items of works included in these estimates /PC-I will be certified by these consultants.</p> <p><b>iv. Execution of the project</b></p> <ul style="list-style-type: none"> <li>• The project will be executed by MC Gojra and supervised by the Consultants appointed by PMDFC in resident supervision mode. The technical staff &amp; experts in PMDFC will oversee, co-ordinate and collaborate in the project planning, design and implementation through their experts in head office located in Lahore and regional offices. The reporting of progress to LG &amp; CDD &amp; World bank and troubleshooting will also be responsibility of PMDFC.</li> <li>• MO (I&amp;S) of the Unit has been designated as Project Manager /Engineer in Charge of the project. The supervision of the works will also be carried out by these municipal officers along with their support engineering staff. All supervisory staff is available with unit Gojra</li> <li>• The procurement of works and goods will be done by Procurement Committee of Gojra Unit as per PPRA Rules.</li> </ul> <p><b>v. Verification of quantities included in PC-Is and Resident Supervision of the works by consultants</b></p> <p>The works will be supervised by Supervision Consultants in resident supervision mode by assuring the quantity and quality of works. The consultants will verify the items of work and their quantities contained in the PC-Is and cost estimates initially and then the quantities and quality of works included in the contractor claims at the stage of payments. Payments will be made by the Unit after these contractor claims have been entered in the measurement books by the Project Manager/Engineer in Charge and pre audited as per LG Works Rules.</p> |  |  |  |  |
| <p>ii- The manpower requirements by skills during execution and operation of the project and;<br/>The job description, qualification, experience, age and salary of each post</p> | <p><b>a) PMDFC experts and staff</b></p> <p>For rendering assistance in implementation of infrastructure projects in 16 MCs, PMDFC has the experts and staff in the required fields. In order to facilitate the Program Units, three regional offices have been established by PMDFC at Gujranwala, Faisalabad and Multan/Khanewal.</p> <p><b>b) Resident Supervision Consultants</b></p> <p>The project will be supervised by consultants. The tentative staff to be employed/deployed by the consultants for the certification of quantities of works and resident supervision of the project is given below.</p> <table border="1" data-bbox="544 2016 1493 2049"> <tr> <td></td> <td></td> <td></td> <td></td> </tr> </table>   |  |  |  |  |
|   |   |  |  |  |  |



| S #  | Personnel  | Nos | Qualification   |
|--|--|-----|---|
| 1  | Chief Resident Engineer/Team Leader  | 01  | BSc;/BE in Civil engineering from HEC approved University with minimum 20 years' professional experience and 5 years' experience on similar assignment or MSC; Civil Engineering/Public Health Engineering/Environmental Engineering with Bachelor in Civil Engineering and minimum 15 years, experience, with 5 years on similar assignments on urban planning, designing and construction supervision assignment. |
| 2  | Assistant Resident Engineer  | 01  | Bachelor Degree in Civil engineering with minimum 8 years' experience in site supervision and execution for projects of similar nature  |
| 3  | Environmentalist   | 01  | Bachelor Degree in Environmentalist/ Environmental Sciences with minimum 16 years education and 5 years' experience in site supervision and execution for projects of similar nature  |
| 4  | social Safeguards /Resettlement Specialist   | 01  | Master Degree in Sociology Sciences with minimum 18 years education and 5 years' experience in site supervision and execution for projects of similar nature  |
| 5  | Site Inspectors  | 01  | DAE in Civil with minimum 10 years' experience in site supervision for projects of similar nature   |
| <p><b>c) Contractor's Technical staff, skilled &amp; non skilled labor</b><br/> The contractors will employ the supervisory technical staff and skilled &amp; non skilled labor for execution of works. The works will be supervised by experienced Engineers and sub engineers and the number of slots for engineers and skilled and non-skilled will depend upon the type and quantity of work and its period of completion.</p> <p><b>d) Repair &amp; maintenance of the project</b><br/> MC has its own regular staff which has been deployed for repair and maintenance of the municipal services infrastructure. However, it has been observed that the existing staff is not adequate to repair and maintain the services in a manner which can give good service delivery. Hence it is proposed to;</p> <ul style="list-style-type: none"> <li>• Fill up the presently vacant slots</li> <li>• Recruit additional staff as per need of the infrastructure after obtaining the sanctions from the competent authorities.</li> </ul> |  |     |   |
| 14-Additional projects /decisions required to optimize the investment being undertaken   | <p><b>1) Shortage &amp; frequent transfers of Provincially appointed staff</b><br/> MC is facing shortage in provincially appointed and locally appointed cadres. This will seriously affect the pace of progress of the program and the implementation of the infrastructure projects may be delayed.</p> |     |   |

|                |  |
|----------------|--|
|                | <p>Provincial Government should fill up the vacant staff immediately for optimizing the investments in MC.</p> <p><b>2) Repair &amp; Maintenance (R&amp;M) staff</b></p> <p>The R&amp;M staff is also deficient and this is adversely affecting the service delivery level. Number of slots are vacant but MC is not allowed to recruit the persons to fill these slots due to ban on recruitments.</p> <p>Further the sanctioned strength of the field staff is much lesser than the actual requirement because with the increase in population and extension of services, additionally required staff has not been sanctioned by the competent authorities.</p> <p>Both of the above issues need to be addressed for optimal utilization of the investments and giving targeted benefits to the resident population of these cities.</p> |
| 15-Certificate | <p>Certified that the project proposal has been prepared on the basis of guidelines provided by the Planning Commission for the preparation of PC-I for social sectors projects.</p>   |

|                    |   |            |  |
|--------------------|---|------------|--|
| <b>Prepared by</b> | JERS Consultancy (Pvt) Ltd                                      | Signatures |  |
| <b>Checked by</b>  | Municipal Officer (Infrastructure)<br>Municipal Committee Gojra | Signatures |  |
|                    | Chief Officer<br>Municipal Committee Gojra                      | Signatures |  |
|                    | Administrator<br>Municipal Committee Gojra                      | Signatures |  |
| <b>Vetted by</b>   | Senior Program Officer<br>PMDFC                                 | Signatures |  |

**Annexure-A**  
**Location Map**



| <p>CLIENT:</p>  <p><b>PUNJAB MUNICIPAL DEVELOPMENT FUND COMPANY (PMDFC)</b></p> | <p>CONSULTANTS:</p>  <p><b>JERS CONSULTANCY (PVT) LTD</b><br/>         24-Civic Center, Quaid-e-Azam Town, Township, Lahore (Pakistan)<br/>         Tel: +92 42 35113123, +92 42 35113124<br/>         Fax: +92 42 35113125<br/>         E-mail: info@jers.com.pk, mail@jers.com.pk<br/>         Web: http://www.jers.com.pk</p> | <p>PROJECT:</p> <p><b>PUNJAB CITIES PROGRAM (PCP)</b><br/>         DETAILED DESIGN OF INFRASTRUCTURE<br/>         SUB-PROJECTS AND RESIDENTS SUPERVISION IN<br/>         16 CITIES OF PUNJAB.</p> | <p>DRAWING TITLE:</p> <p><b>PROJECT KEY PLAN (GOJRA)</b></p> | <table border="1"> <thead> <tr> <th>REV.</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table> | REV. | DATE | DESCRIPTION |  |  |  |  |  |  |  |  |  | <table border="1"> <tr> <td>DRAWN BY:<br/>Hassan</td> <td colspan="2">DRAWING NO:<br/><b>SV-01</b></td> </tr> <tr> <td>CHECKED BY:<br/>Umer</td> <td>SCALE:<br/>1"=1500'</td> <td>SHEET:<br/>-</td> </tr> <tr> <td>DATE:<br/>Feb,2023</td> <td colspan="2">JOB NO:<br/>488-01</td> </tr> </table> | DRAWN BY:<br>Hassan | DRAWING NO:<br><b>SV-01</b> |  | CHECKED BY:<br>Umer | SCALE:<br>1"=1500' | SHEET:<br>- | DATE:<br>Feb,2023 | JOB NO:<br>488-01 |  |
|---|---|---|--|---|------|------|-------------|--|--|--|--|--|--|--|--|--|---|---------------------|-----------------------------|--|---------------------|--------------------|-------------|-------------------|-------------------|--|
| REV.  | DATE  | DESCRIPTION   |  |   |      |      |             |  |  |  |  |  |  |  |  |  |   |                     |                             |  |                     |                    |             |                   |                   |  |
|   |   |   |  |   |      |      |             |  |  |  |  |  |  |  |  |  |   |                     |                             |  |                     |                    |             |                   |                   |  |
|   |   |   |  |   |      |      |             |  |  |  |  |  |  |  |  |  |   |                     |                             |  |                     |                    |             |                   |                   |  |
|   |   |   |  |   |      |      |             |  |  |  |  |  |  |  |  |  |   |                     |                             |  |                     |                    |             |                   |                   |  |
| DRAWN BY:<br>Hassan   | DRAWING NO:<br><b>SV-01</b>   |   |  |   |      |      |             |  |  |  |  |  |  |  |  |  |   |                     |                             |  |                     |                    |             |                   |                   |  |
| CHECKED BY:<br>Umer   | SCALE:<br>1"=1500'  | SHEET:<br>-   |  |   |      |      |             |  |  |  |  |  |  |  |  |  |   |                     |                             |  |                     |                    |             |                   |                   |  |
| DATE:<br>Feb,2023   | JOB NO:<br>488-01   |   |  |   |      |      |             |  |  |  |  |  |  |  |  |  |   |                     |                             |  |                     |                    |             |                   |                   |  |

**Annexure-B**  
**Cost Estimate**



**PUNJAB CITIES PROGRAM (PCP)  
 DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
 SUPERVISION IN 16 CITIES OF PUNJAB**

**ROAD WORKS**

**MC GOJRA**

**DETAILED COST ESTIMATE**

**SUMMARY**

| Sr. No. | Description                            | Amount (Rs.)       |
|---------|--|--------------------|
| 1       | ROAD WORKS                             | 182,696,310        |
| 2       | STORMWATER DRAINAGE SYSTEM             | 36,619,832         |
| 3       | ELECTRICAL WORKS                       | 36,948,214         |
| 4       | ENVIRONMENT AND SOCIAL MITIGATION COST | 1,333,000          |
| 5       | ARAP COST                              | 548,847            |
|         | <b>Total Amount (Rs.)</b>              | <b>258,146,203</b> |
|         | Contingencies @ 2%                     | 5,162,924          |
|         | PRA Charges @ 5%                       | 12,907,310         |
|         | Price Escalation @ 6%                  | 15,488,772         |
|         | <b>Total Amount. Rs.</b>               | <b>291,705,209</b> |

**PUNJAB CITIES PROGRAM (PCP)  
DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
SUPERVISION IN 16 CITIES OF PUNJAB**

**INFRASTRUCTURE WORK**

**MC GOJRA**

**DETAILED COST ESTIMATE**

**SUMMARY**

| Sr.<br>No. | Description                                   | Amount (Rs.)       |
|------------|---|--------------------|
| <b>1</b>   | <b>ROAD WORKS</b>                             |                    |
| 1.1        | P-1 GOJRA TOBA ROAD (3.11 Km)                 | 182,696,310        |
|            | <b>1) Total Amount. Rs.</b>                   | <b>182,696,310</b> |
| <b>2</b>   | <b>STORMWATER DRAINAGE SYSTEM</b>             |                    |
| 2.1        | P-1 GOJRA TOBA ROAD                           | 36,619,832         |
|            | <b>2) Total Amount. Rs.</b>                   | <b>36,619,832</b>  |
| <b>3</b>   | <b>ELECTRICAL WORKS</b>                       |                    |
| 3.1        | P-1 GOJRA TOBA ROAD                           | 36,948,214         |
|            | <b>3) Total Amount. Rs.</b>                   | <b>36,948,214</b>  |
| <b>4</b>   | <b>ENVIRONMENT AND SOCIAL MITIGATION COST</b> | <b>1,333,000</b>   |
| <b>5</b>   | <b>ARAP COST</b>                              | <b>548,847</b>     |
|            | <b>Total Amount (Rs.) "1+2+3+4"</b>           | <b>258,146,203</b> |
|            | <b>Say Millions</b>                           | <b>258.15</b>      |

# ROAD WORKS

**PUNJAB CITIES PROGRAM (PCP)  
DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
SUPERVISION IN 16 CITIES OF PUNJAB**

**DETAILED COST ESTIMATE**

**P-1 GOJRA TOBA ROAD**

**ROADS NETWORK**

| Sr. No | 1st BI-Annual-2023 (Jan to July)<br>Toba Tek Singh | Description   | Unit    | Qty      | Unit Rate (Rs.) | Amount (Rs.) |
|--------|--|---|---------|----------|-----------------|--------------|
|        |  | <b>ROAD WORK</b>  |         |          |                 |              |
|        |  | <b>Dismantling</b>  |         |          |                 |              |
| 1      | N.S  | Dismantling / Demolishing of existing kerb stone as directed by Engineer's Incharge, Complete in all respect  | Rft     | 400.00   | 27.72           | 11,088       |
| 2      | 4/46   | Dismantling and removing road pavement, etc., including screening and stacking of byproducts upto one chain lead (30 metre).  | 100Cft  | 228.90   | 2,960.50        | 677,658      |
|        |  | <b>Scarifying</b>   |         |          |                 |              |
| 3      | 18/11  | Scarifying old road surface including removal of debris within 1 chain (30 m).  | 100Sft  | 2,315.70 | 462.00          | 1,069,853    |
|        |  | <b>Excavation</b>   |         |          |                 |              |
| 4      | 3/7  | Earthwork excavation in open cutting upto 5'-0" (1.5 m) depth for storm water channels, drains, sullage drains in open areas, roads, streets, lanes, including under pinning of walls and shoring to protect existing works, shuttering and timbering the trenches, dressed to designed level and dimensions, trimming, removal of surface water from trenches, back filling and surplus excavated material disposed of and dressed within 50 ft. (15 m) lead:- |         |          |                 |              |
|        |  | i) ordinary   | 1000Cft | 167.34   | 9,852.50        | 1,648,717    |
| 5      | 7/30   | Supplying and filling sand under floor; or plugging in wells  | 100Cft  | 123.93   | 2,982.00        | 369,559      |
| 6      | 18/3<br>Labor Rate                                 | Relaying sub-base course of stone product of approved quality and grade including, placing, mixing, spreading and compaction of sub base material to required depth, camber and grade to achieve 98% maximum dry density determined according to AASHTO T-180 method-D, including carriage of all material to site of work complete in all respect as per specifications and as directed by the engineer incharge.  | 1000Cft | 20.60    | 6,035.25        | 124,326      |

**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**DETAILED COST ESTIMATE**

**P-1 GOJRA TOBA ROAD**

**ROADS NETWORK**

| Sr. No | 1st BI-Annual-2023 (Jan to July)<br>Toba Tek Singh | Description  | Unit   | Qty       | Unit Rate (Rs.) | Amount (Rs.) |
|--------|--|--|--------|-----------|-----------------|--------------|
|        |  | <b>Sub Base Course</b>   |        |           |                 |              |
| 7      | 18/3/a/<br>(i)<br>+<br>1/1                         | Providing and laying sub-base course of stone product of approved quality and grade including, placing, mixing, spreading and compaction of sub base material to required depth, camber and grade to achieve 98% maximum dry density determined according to AASHTO T-180 method-D, including carriage of all material to site of work complete in all respect as per specifications and as directed by the engineer incharge. (Crushed stone aggregate from Sargodha quarry to site, actual compacted depth shall be considered for payment)  | 100Cft | 831.72    | 14,979.75       | 12,458,958   |
|        |  | <b>Road Edging</b>   |        |           |                 |              |
| 8      | 18/5   | Providing and laying road edging of 3" (75 mm) wide and 9" (225 mm) deep brick on end, complete in all respects.   | Rft    | 18,966.00 | 54.75           | 1,038,389    |
|        |  | <b>Water Bound Macadam</b>   |        |           |                 |              |
| 9      | 18/4/a<br>+<br>1/1                                 | Providing and laying base course of crushed stone ( <b>Water Bound Macadam</b> ) of approved quality and grade including, placing, mixing, spreading and compaction of base course material to required depth, camber and grade to achieve 100% maximum modified AASHTO dry density, including carriage of all material to site of work complete in all respect as per specifications and as directed by the engineer incharge. (Crushed stone aggregate from Sargodha quarry to site, actual compacted depth shall be considered for payment) | 100Cft | 1,987.93  | 22,483.43       | 44,695,475   |
|        |  | <b>Prime Coat</b>  |        |           |                 |              |
| 10     | 18/6   | Providing and laying bituminous priming coat, using 10 lbs. kerosene oil and 10 lbs. binder per 100 Sft. or 0.5 Kg kerosene and 0.5 Kg binder per square metre.  | 100Sft | 3,377.95  | 1,968.15        | 6,648,312    |

**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**DETAILED COST ESTIMATE**

**P-1 GOJRA TOBA ROAD**

**ROADS NETWORK**

| Sr. No | 1st BI-Annual-2023 (Jan to July)<br>Toba Tek Singh | Description  | Unit                           | Qty       | Unit Rate (Rs.) | Amount (Rs.) |
|--------|--|--|--------------------------------|-----------|-----------------|--------------|
| 11     | 18/7   | Providing and laying bituminous tack coat, using 10 lbs. of bitumen per 100 Sft (0.49 Kg of bitumen per sq.m.)   | 100Sft                         | 2,620.80  | 1,033.85        | 2,709,514    |
|        |  | <b>Carpeting</b>   |                                |           |                 |              |
|        |  | <b>ABC</b>   |                                |           |                 |              |
| 12     | 18/10/a<br>+<br>1/1                                | Providing and laying plant premixed bituminous carpet, including compaction and finishing to required camber, grade and density. (2 inch thick)<br>(iii) 4% Bitumen                          | Per inch thickness per 100Sft. | 2,620.80  | 13,829.32       | 36,243,882   |
|        |  | <b>AWC</b>   |                                |           |                 |              |
| 13     | 18/10/a<br>+<br>1/1                                | Providing and laying plant premixed bituminous carpet, including compaction and finishing to required camber, grade and density. (1.5 inch thick) (iv) 4.5% Bitumen                          | Per inch thickness per 100Sft. | 2,620.80  | 11,280.45       | 29,563,803   |
| 14     | 18/10/a<br>+<br>1/1                                | Providing and laying plant premixed bituminous carpet, including compaction and finishing to required camber, grade and density. (2 inch thick) (iv) 4.5% Bitumen                            | Per inch thickness per 100Sft. | 730.90    | 14,747.92       | 10,779,255   |
|        |  | <b>Paint For Traffic Lanes</b>   |                                |           |                 |              |
| 15     | 13/36  | Painting Traffic Lane Marking of specified width (1.5mm thick), with Thermoplastic (TP) Paint including Glass Beads, complete in all respect, as approved and directed by Engineer incharge. |                                |           |                 |              |
|        |  | ii) 6" wide  | Rft                            | 37,358.00 | 59.20           | 2,211,594    |
|        |  | <b>Kerb Stone</b>  |                                |           |                 |              |
| 16     | 6/52/b   | Providing and fixing precast Edge Kerb Stone (4" to 6" thick), of 3500 PSI Compressive Strength, embeded in PCC 1:2:4 over lean concrete 1:4:8 etc. complete in all respect.                 |                                |           |                 |              |
|        |  | b) With Painting   |                                |           |                 |              |
|        |  | (i) 14" high   | P.Rft                          | 10,920.00 | 535.05          | 5,842,746    |

**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**DETAILED COST ESTIMATE**

**P-1 GOJRA TOBA ROAD**

**ROADS NETWORK**

| Sr. No | 1st BI-Annual-2023 (Jan to July)<br>Toba Tek Singh | Description   | Unit   | Qty        | Unit Rate (Rs.) | Amount (Rs.) |
|--------|--|---|--------|------------|-----------------|--------------|
|        |  | <b>Tuff Paver</b>   |        |            |                 |              |
| 17     | 10/41  | Providing and laying Tuff pavers, having 7000 PSI, crushing strength of approved manufacturer, over 2" to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope. complete in all respect. (50% Grey / 50% Coloured)   |        |            |                 |              |
|        |  | c) 80-mm thick  | Sft    | 111,435.50 | 197.40          | 21,997,368   |
|        |  | <b>P.C.C (Between Asphalt and Tuff Paver)</b>   |        |            |                 |              |
| 18     | 6/5  | Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate):  |        |            |                 |              |
|        |  | (f) Ratio 1: 2: 4   | 100Cft | 32.12      | 38,723.50       | 1,243,799    |
|        |  | <b>Cat Eyes</b>   |        |            |                 |              |
| 19     | 18/28  | Providing & fixing Cat Eyes of size 4"x4"x3/4" duly casted with specified material having plastic strip containing mini retro-reflective glass beads of color white /red/ yellow having specifid reflections, quality & shape i/c the cost of self built in12mm dia x120mm long steel zinc plate dnail, fixing to road with epoxy/ hammering with separate nail complete. |        |            |                 |              |
|        |  | b) Aluminium Alloy  |        |            |                 |              |
|        |  | (1) Dual-Directional  |        |            |                 |              |
|        |  | (ii) 43x2=86 Glass beads a side   | Each   | 976.00     | 747.70          | 729,755      |
|        |  | (B) Uni-Directional   |        |            |                 |              |
|        |  | (ii) 43 Glass beads a side  | Each   | 3,040.00   | 585.70          | 1,780,528    |
| 20     | 18/25/a  | Providing, fabrication and fixing pole mounted Direction Board/ road delineator of any shape and size, with specified Sheet and thickness, supported with G.I Channel, (excluding the cost of vertical post and painting) etc complete in all respect.  |        |            |                 |              |
|        |  | (a) G.I Sheet 14 SWG  |        |            |                 |              |
|        |  | <b>CIRCULAR/TRIANGULAR</b>  |        |            |                 |              |
|        |  | 3 ft size   | P. Sft | 90.00      | 997.20          | 89,748       |



**PUNJAB CITIES PROGRAM (PCP)  
DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
SUPERVISION IN 16 CITIES OF PUNJAB**

**DETAILED COST ESTIMATE**

**P-1 GOJRA TOBA ROAD**

**ROADS NETWORK**

| Sr. No | 1st BI-Annual-2023 (Jan to July)<br>Toba Tek Singh | Description   | Unit   | Qty    | Unit Rate (Rs.) | Amount (Rs.)       |
|--------|--|---|--------|--------|-----------------|--------------------|
| 21     | 18/27/b  | Providing, fabrication and fixing Vertical Post comprising of medium quality G.I Pipe of specified diameter, including the cost of clamping arrangements, top cover,hold fasts embedded in PCC 1:2:4 etc, complete in all respect |        |        |                 |                    |
|        |  | (b) 3 inch diameter   | Rft    | 165.00 | 1,538.20        | 253,803            |
| 22     | 13/42/a  | Lettering and printing of signage /direction boards/ road delineators of any colour by machine i/c cost of Digital Lettering, Lamination & pasting etc complete in all respect.   |        |        |                 |                    |
|        |  | a) High Intensity Prismatic (HIP) Tape  | P. Sft | 90.00  | 1,203.95        | 108,356            |
|        |  | <b>For Green Belt</b>   |        |        |                 |                    |
| 23     | 3/32   | Turfing slopes of banks or lawns with grass sods including ploughing, laying, setting and watering (Turf got from within a distance of 5 miles (8 Km.) and maintenance for 15 days).  | 100Sft | 238.00 | 1,848.00        | 439,824            |
|        |  | <b>Deduction</b>  |        |        |                 |                    |
| 24     |  | Kerb Stone (Input Rate)   | Rft    | 400.00 | 100.00          | (40,000)           |
|        |  | <b>Total Amount Rs.</b>   |        |        |                 | <b>182,696,310</b> |
|        |  | <b>DRAINAGE SYSTEM</b>  |        |        |                 |                    |
|        |  | <b>Dismantling</b>  |        |        |                 |                    |
| 1      | 4/19/c   | c) Dismantling cement concrete 1:2:4 plain.   | 100Cft | 0.62   | 12,196.80       | 7,509              |

**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**DETAILED COST ESTIMATE**

**P-1 GOJRA TOBA ROAD**

**ROADS NETWORK**

| Sr. No | 1st BI-Annual-2023 (Jan to July)<br>Toba Tek Singh | Description   | Unit    | Qty    | Unit Rate (Rs.) | Amount (Rs.) |
|--------|--|---|---------|--------|-----------------|--------------|
|        |  | <b>Excavation</b>   |         |        |                 |              |
| 2      | 3/7/i  | Earthwork excavation in open cutting upto 5'-0" (1.5 m) depth for storm water channels, drains, sullage drains in open areas, roads, streets, lanes, including under pinning of walls and shoring to protect existing works, shuttering and timbering the trenches, dressed to designed level and dimensions, trimming, removal of surface water from trenches, back filling and surplus excavated material disposed of and dressed within 50 ft. (15 m) lead:-<br>i) in ordinary soil. | 1000Cft | 76.10  | 9,852.50        | 749,805      |
|        |  | <b>P.C.C</b>  |         |        |                 |              |
| 3      | 6/5  | Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate):  |         |        |                 |              |
|        |  | (i) Ratio 1: 4: 8   | 100Cft  | 62.39  | 29,723.50       | 1,854,449    |
|        |  | (f) Ratio 1: 2: 4   | 100Cft  | 163.40 | 38,723.50       | 6,327,420    |
|        |  | <b>Brick Work</b>   |         |        |                 |              |
| 4      | 7/7/i  | Pacca brick work other than building upto 10ft. (3 m) Cement, sand mortar:- Ratio 1:3   | 100Cft  | 270.89 | 33,467.90       | 9,066,246    |
| 5      | 7/10   | Extra for pacca brick work in steining of wells or any other circular masonry.  | 100Cft  | 1.23   | 288.12          | 355          |
|        |  | <b>Plaster</b>  |         |        |                 |              |
| 6      | 11/8/b   | Cement plaster 1:3 upto 20' (6.00 m) height:-<br>b) ½" (13 mm) thick  | 100Sft  | 304.30 | 3,639.10        | 1,107,390    |

**PUNJAB CITIES PROGRAM (PCP)  
DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
SUPERVISION IN 16 CITIES OF PUNJAB**

**DETAILED COST ESTIMATE**

**P-1 GOJRA TOBA ROAD**

**ROADS NETWORK**

| Sr. No | 1st BI-Annual-2023 (Jan to July)<br>Toba Tek Singh | Description  | Unit  | Qty      | Unit Rate (Rs.) | Amount (Rs.) |
|--------|--|--|-------|----------|-----------------|--------------|
|        |  | <b>R.C.C Work</b>  |       |          |                 |              |
| 7      | 6/6/a/i/3  | Providing and laying reinforced cement concrete (i/c pre-stressed concrete), using coarse sand and screened graded and washed aggregate, in required shape and design, i/c forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete (but excluding the cost of steel reinforcement, its fabrication and placing in position, complete |       |          |                 |              |
|        |  | (a)(iii) Reinforced cement concrete in slab of rafts / strip foundation, base slab of column and retaining walls; etc and footing beams, other structural members other than those mentioned in 6(a) (i)&(ii) above not requiring form work (i.e. horizontal shuttering) complete in all respects:-  |       |          |                 |              |
|        |  | (3) Type C (nominal mix 1: 2: 4)   | P Cft | 51.00    | 473.85          | 24,166       |
|        |  | a).(i) Reinforced cement concrete in roof slab, beams, columns, lintels, girders and other structural members laid in situ or pre-cast laid in position, or pre-stressed members cast in situ, complete in all respect. Type C (nominal mix 1:2:4)   | P Cft | 9,745.00 | 583.25          | 5,683,771    |
|        |  | <b>Steel</b>   |       |          |                 |              |
| 8      | 6/12/c   | Fabrication of mild steel reinforcement for cement concrete, i/c cutting, bending, laying in position, making joints and fastening, i/c cost of bending wire and labour charges for bending of steel reinforcement (also includes removal of rust from deformed bars) Gade 60  | 100Kg | 300.01   | 31,944.50       | 9,583,785    |
|        |  | <b>Gully Grating Chamber</b>   |       |          |                 |              |
| 9      | 21/8   | Constructing standard gully grating chamber, 3'x2½' (900x750 mm), with chinaware trap as per PHED Drawing STD/PD No. 3 of 1977, complete in all respects.  | Each  | 15.00    | 17,047.40       | 255,711      |

**PUNJAB CITIES PROGRAM (PCP)  
DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
SUPERVISION IN 16 CITIES OF PUNJAB**

**DETAILED COST ESTIMATE**

**P-1 GOJRA TOBA ROAD**

**ROADS NETWORK**

| Sr. No | 1st BI-Annual-2023 (Jan to July)<br>Toba Tek Singh | Description  | Unit   | Qty      | Unit Rate (Rs.) | Amount (Rs.)      |
|--------|--|--|--------|----------|-----------------|-------------------|
| 10     | 7/30   | Supplying and filling sand under floor; or plugging in wells.  | 100Cft | 7.50     | 2,982.00        | 22,365            |
|        |  | <b>uPVC Pipe</b>   |        |          |                 |                   |
| 11     | 19/47  | Providing, fixing, testing and commissioning of $\mu$ -PVC (Unplasticized polyvinyl Chloride)Nikasi /waste pipe make of dadex / Popular / Beta/ BBJ plain / socket ended conforming to code EN-1401 of specified SDR (Standard Dimension Ratio) including the cost of specials and Solvents complete in all respect as approved and directed by the Engineer Incharge. |        |          |                 |                   |
|        |  | <b>Type (SDR 41/SN-4)</b>  |        |          |                 |                   |
|        |  | (vii) 8"(200 mm)   | Rft    | 300.00   | 455.00          | 136,500           |
|        |  | <b>Kerb Stone</b>  |        |          |                 |                   |
| 12     | 6/52/b   | Providing and fixing precast Edge Kerb Stone (4" to 6" thick), of 3500 PSI Compressive Strength, embedded in PCC 1:2:4 over lean concrete 1:4:8 etc. complete in all respect.  |        |          |                 |                   |
|        |  | b) With Painting   |        |          |                 |                   |
|        |  | (i) 14" high   | P.Rft  | 2,926.50 | 535.05          | 1,565,824         |
|        |  | <b>RPC Manhole Cover</b>   |        |          |                 |                   |
| 13     | N.S  | Providing and fixing RPC Manhole Cover Manufactured with 100% Reinforced Plastic Composite Material, 650 mm dia with clear opening size 600 mm (24" dia) and RPC manhole frame having dia meter 790 mm (Complete)<br>(Certified under ISO 9001-2015)   | Each   | 19.00    | 11,844.00       | 225,036           |
|        |  | <b>Manhole Cover</b>   |        |          |                 |                   |
| 14     | MR   | Old/existing Manhole cover and Frame complete set shift to MC store.   | Set    | 19.00    | 500.00          | 9,500             |
|        |  | <b>Total Amount (Rs)</b>   |        |          |                 | <b>36,619,832</b> |

**PUNJAB CITIES PROGRAM (PCP)  
DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
SUPERVISION IN 16 CITIES OF PUNJAB**

**DETAILED COST ESTIMATE**

**P-1 GOJRA TOBA ROAD**

**ROADS NETWORK**

| Sr. No | 1st BI-Annual-2023 (Jan to July)<br>Toba Tek Singh | Description  | Unit  | Qty      | Unit Rate (Rs.) | Amount (Rs.)   |
|--------|--|--|-------|----------|-----------------|----------------|
|        |  | <b>ELECTRICAL WORKS</b>  |       |          |                 |                |
|        |  | <b>Scheduled Items (A)</b>   |       |          |                 |                |
|        |  | <b>Excavation</b>  |       |          |                 |                |
| 1      | 3/21   | Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain (30 m) and lift upto 5 ft. (1.5 m)   |       |          |                 |                |
|        |  | <b>a) By Manual</b>  |       |          |                 |                |
|        |  | ii) in ordinary soil.  | %oCft | 31.97    | 11,658.25       | <b>372,714</b> |
|        |  | <b>RCC Foundation for Poles</b>  |       |          |                 |                |
| 2      | 6/6  | Providing and laying reinforced cement concrete (including prestressed concrete), using coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete (but excluding the cost of steel reinforcement, its fabrication and placing in position, etc.):- |       |          |                 |                |
|        |  | (a)(iii) Reinforced cement concrete in slab of rafts / strip foundation, base slab of column and retaining walls; etc and footing beams, other structural members other than those mentioned in 6(a) (i)&(ii) above not requiring form work (i.e. horizontal shuttering) complete in all respects:-  |       |          |                 |                |
|        |  | (2) Type B (nominal mix 1: 1½: 3)  | Cft   | 2,280.00 | 528.40          | 1,204,752      |
|        |  | <b>Steel Work</b>  |       |          |                 |                |
| 3      | 6/12/c   | Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):-  |       |          |                 |                |
|        |  | (c) Deformed bars (Grade-60)   | 100Kg | 57.00    | 31,944.50       | 1,820,837      |

**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**DETAILED COST ESTIMATE**

**P-1 GOJRA TOBA ROAD**

**ROADS NETWORK**

| Sr. No | 1st BI-Annual-2023 (Jan to July)<br>Toba Tek Singh | Description  | Unit | Qty       | Unit Rate (Rs.) | Amount (Rs.) |
|--------|--|--|------|-----------|-----------------|--------------|
| 4      | 24/6   | Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:-   |      |           |                 |              |
|        |  | i) 50 mm i/d   | Rft  | 11,875.00 | 177.75          | 2,110,781    |
| 5      | 24/12  | Supply and erection of single core PVC insulated, PVC sheathed copper conductor, 660/1100 volts grade cable, in prelaid G.I. pipe/M.S. conduits /PVC pipe/G.I. wire/ trenches, etc (rate for cable only):-   |      |           |                 |              |
|        |  | ii) 6 mm sq (7/0.044")   | Rft  | 1,900.00  | 119.20          | 226,480      |
| 6      | 24/13  | Supply and erection of copper conductor cables for service connection, in prelaid pipe/G.I. wire / trenches, etc. (rate for cable only):-  |      |           |                 |              |
|        |  | b) PVC insulated, PVC sheathed 3 core, 600/1000 volt cable:-   |      |           |                 |              |
|        |  | iii) 7/0.74 mm (7/0.029")  | Rft  | 3,800.00  | 114.25          | 434,150      |
|        |  | c) PVC insulated, PVC sheathed 4 core, 600/1000 volt non armoured cable:-  |      |           |                 |              |
|        |  | vi) 10 mm (7/0.052")   | Rft  | 11,875.00 | 525.75          | 6,243,281    |
|        |  | vii) 16 mm (7/0.064")  | Rft  | 100.00    | 694.80          | 69,480       |
| 7      | 24/68  | Supplying, installation testing and commissioning of Octagonal shape electric street light pole, made of hot dipped 4.5 mm thick (7 SWG) galvanized steel ,tapered from 225 mm at bottom to 100 mm at top,with 1500 mmx60 mm dia. arm for luminaire installation, duly G.I.welded with 470x470x20 mm base plate with the help of 4 no triangular stiffeners 100x350x20 mm of GI sheet,with built in junction box with shutter,i/c the cost of nuts & J-rag bolts, duly fixed in prelaid concrete foundation, foundation will be paid additionally as approved and directed by the Engineer Incharge. |      |           |                 |              |
|        |  | a) Single Arm  |      |           |                 |              |
|        |  | (i) 10 mtr height  | Each | 41.00     | 116,325.30      | 4,769,337    |

**PUNJAB CITIES PROGRAM (PCP)  
DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
SUPERVISION IN 16 CITIES OF PUNJAB**

**DETAILED COST ESTIMATE**

**P-1 GOJRA TOBA ROAD**

**ROADS NETWORK**

| Sr. No | 1st BI-Annual-2023 (Jan to July)<br>Toba Tek Singh | Description   | Unit | Qty    | Unit Rate (Rs.) | Amount (Rs.) |
|--------|--|---|------|--------|-----------------|--------------|
|        |  | b) Double Arm   |      |        |                 |              |
|        |  | (i) 10 mtr height   | Each | 54.00  | 120,141.30      | 6,487,630    |
| 8      | 24/69/c  | Supplying, installation and commissioning of LED Cobra-head Luminaries of specified wattage and lumens conforming to IP 65, Philips/ Osram /Thorn with corrosion resistant die casted aluminum housing, silicon gas kit, thermally hardened glass complete with LED drivers, surge protection i/c the cost of all accessories/components required for proper operation , fully flexible for future upgradation and easy replacements for maintenance purposes, bucket elevator charges as approved and directed by the Engineer Incharge.   |      |        |                 |              |
|        |  | c) 120 Lm/Watt  |      |        |                 |              |
|        |  | (v) 90 Watt with 10800 Lumens   | Each | 149.00 | 52,598.60       | 7,837,191    |
| 9      | 24/77  | Supply and erection of electric energy meter, including meter testing fee, etc.   |      |        |                 |              |
|        |  | b) three phase, 4 wires:  |      |        |                 |              |
|        |  | ii) 3x50 Amp, 400 volts   | Each | 1.00   | 15,843.30       | 15,843       |
| 10     | 24/105/iii   | Supply, insatllation, commissioning and testing of oil cooled type, Step down Power Transformer of specified rating,11/0.415 kV, i/c the cost of lifting hooks, thermometers, LT & HT bushing 5-steps, tap changer, imported double float buchholz relay, 2 earthing terminals, roller wheels, connecting terminals for cables M.S box on transformer in order to cover complete L.T side, all necessary materials required for connections on H.T & L.T side, rated voltage 11000/415/240 V impedance 6.25% or as specified by WAPDA/IEC system earth: Delta / Star, neutral solidly earthed, i/c Wapda testing charges,complete in all respects made of PEL, Siemens, as approved and directed by the Engineer Incharge |      |        |                 |              |



**PUNJAB CITIES PROGRAM (PCP)  
 DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
 SUPERVISION IN 16 CITIES OF PUNJAB**

**DETAILED COST ESTIMATE**

**P-1 GOJRA TOBA ROAD**

**ROADS NETWORK**

| Sr. No | 1st BI-Annual-2023 (Jan to July)<br>Toba Tek Singh | Description   | Unit | Qty   | Unit Rate (Rs.) | Amount (Rs.)      |
|--------|--|---|------|-------|-----------------|-------------------|
|        |  | (iii) 25 KVA  | Each | 1.00  | 581,485.15      | 581,485           |
| 11     | 24/70  | Earthing of iron clad/aluminum switches, etc. with G.I. wire No. 8 SWG in G.I. pipe 15 mm (½") dia, recessed or on surface of wall and floor, complete with 1.5 metre long G.I. pipe, 50 mm (2") dia with reducing socket 4 to 5 metre below ground level, and 2 metre away from building plinth. | Job  | 98.00 | 10,199.15       | 999,517           |
|        |  | <b>Sub Total Scheduled Items: (A)</b>   |      |       |                 | <b>33,173,479</b> |

**PUNJAB CITIES PROGRAM (PCP)  
DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
SUPERVISION IN 16 CITIES OF PUNJAB**

**DETAILED COST ESTIMATE**

**P-1 GOJRA TOBA ROAD**

**ROADS NETWORK**

| Sr. No              | 1st BI-Annual-2023 (Jan to July)<br>Toba Tek Singh | Description   | Unit | Qty  | Unit Rate (Rs.) | Amount (Rs.)       |
|---------------------|--|---|------|------|-----------------|--------------------|
| <b>Non Schedule</b> |  | <b>Part-B</b>   |      |      |                 |                    |
| 12                  | N.S  | Fabrication, Supply, testing and commissioning of following Light control panels (LCP), floor standing weather proof, IP 65 Rated of appropriate size, made of MS Sheet 16 SWG with hinged door, handle, catcher, 2 coats of antirust and powder coated paint of approved colour, AC3 megnatic contactor, photocell for automatic operation of lights, CBs, Hand/Off/Auto switch, push button and all necessary accessories complete in all respects. LCP shall be manufactured as per specifications, single line diagram complete in all respect up to the satisfaction of Engineer incharge. |      |      |                 |                    |
|                     | (a)  | LCP-3 Phase   | No.  | 1.00 | 374,735         | 374,735            |
| 13                  | N.S  | Shifting of 20 Nos. Wapda Electric Poles  | Job  |      |                 | 3,000,000          |
| 14                  | N.S  | Electric Connection Charges   | Each | 1.00 | 400,000         | 400,000            |
|                     |  | <b>Total Cost (Part B)</b>  |      |      | <b>Rs.</b>      | <b>3,774,735</b>   |
|                     |  | <b>Grand Total (Part A + Part B)</b>  |      |      | <b>Rs.</b>      | <b>36,948,214</b>  |
|                     |  | <b>Grand Total Amount Rs.</b>   |      |      |                 | <b>256,264,356</b> |

**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**P-1 GOJRA TOBA ROAD**

**CALCULATION OF QUANTITIES**

**ROADS NET WORK**

| Sr. No             | Description  | No. | Length | Width | Height | Qty.          | Unit.           |             |
|--------------------|--|-----|--------|-------|--------|---------------|-----------------|-------------|
| <b>Dismantling</b> |  |     |        |       |        |               |                 |             |
| 1                  | Dismantling / Demolishing of existing kerb stone as directed by Engineer's Incharge, Complete in all respect                 |     |        |       |        |               |                 |             |
|                    | Rd 0+000 to 0+200  | 2   | 200    |       |        | 400           | Rft             |             |
|                    |  |     |        |       |        | <b>Total.</b> | <b>400</b>      | <b>Rft</b>  |
| 2                  | Dismantling and removing road pavement, etc., including screening and stacking of byproducts upto one chain lead (30 metre). |     |        |       |        |               |                 |             |
|                    | Rd 4+730 to 5+500  | 1   | 770    | 2.00  | 1      | 1,540         | Cft             |             |
|                    | Rd 5+500to 6+300   | 1   | 800    | 5.00  | 1      | 4,000         | Cft             |             |
|                    | Rd 6+300 to 7+000  | 1   | 700    | 2.00  | 1      | 1,400         | Cft             |             |
|                    | Rd 7+000 to 9+100  | 1   | 2,100  | 5.00  | 1      | 10,500        | Cft             |             |
|                    | Rd 9+100 to 10+190   | 1   | 1,090  | 5.00  | 1      | 5,450         | Cft             |             |
|                    |  |     |        |       |        | Total         | 22,890          | Cft         |
|                    |  |     |        |       |        | <b>Total.</b> | <b>228.90</b>   | <b>%Cft</b> |
| <b>Scarifying</b>  |  |     |        |       |        |               |                 |             |
| 3                  | Scarifying old road surface including removal of debris within 1 chain (30 m).   |     |        |       |        |               |                 |             |
|                    | RD 0+000 to 3+400  | 1   | 3,400  | 14.00 |        | 47,600        | Sft             |             |
|                    | RD 3+900 to 4+523  | 1   | 623    | 30.00 |        | 18,690        | Sft             |             |
|                    | RD 4+730 to 5+500  | 1   | 770    | 51.00 |        | 39,270        | Sft             |             |
|                    | RD 5+500 to 6+300  | 1   | 800    | 31.00 |        | 24,800        | Sft             |             |
|                    | Rd 6+300 to 7+000  | 1   | 700    | 34.00 |        | 23,800        | Sft             |             |
|                    | Rd 7+000 to 9+100  | 1   | 2,100  | 27.00 |        | 56,700        | Sft             |             |
|                    | RD 9+100 to 10+190   | 1   | 1,090  | 19.00 |        | 20,710        | Sft             |             |
|                    |  |     |        |       |        | Total         | 231,570         | Sft         |
|                    |  |     |        |       |        | <b>Total.</b> | <b>2,315.70</b> | <b>%Sft</b> |

**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**P-1 GOJRA TOBA ROAD**  
**CALCULATION OF QUANTITIES**  
**ROADS NET WORK**

| Sr. No | Description   | No. | Length | Width | Height | Qty.          | Unit.               |
|--------|---|-----|--------|-------|--------|---------------|---------------------|
|        | <b>Excavation</b>   |     |        |       |        |               |                     |
| 4      | Earthwork excavation in open cutting upto 5'-0" (1.5 m) depth for storm water channels, drains, sullage drains in open areas, roads, streets, lanes, including under pinning of walls and shoring to protect existing works, shuttering and timbering the trenches, dressed to designed level and dimensions, trimming, removal of surface water from trenches, back filling and surplus excavated material disposed of and dressed within 50 ft. (15 m) lead:- |     |        |       |        |               |                     |
|        | <b>For Road</b>   |     |        |       |        |               |                     |
|        | RD 0+000 to 3+400   | 1   | 3,400  | 2.00  | 1.17   | 7,956         | Cft                 |
|        | Rd 5+500 to 6+300   | 2   | 800    | 8.50  | 0.50   | 6,800         | Cft                 |
|        | Rd 7+000 to 9+100   | 2   | 2,100  | 10.50 | 0.50   | 22,050        | Cft                 |
|        | RD 9+100 to 10+190  | 2   | 1,090  | 14.50 | 0.50   | 15,805        | Cft                 |
|        | Rd 4+723 to 6+100 for existing sewer line   | 1   | 1,377  | 18.00 | 0.50   | 12,393        | Cft                 |
|        | <b>For Tuff Paver Shoulders</b>   |     |        |       |        |               |                     |
|        | RD 0+000 to 3+400   | 1   | 3,400  | 8.50  | 1.00   | 28,900        | Cft                 |
|        | RD 3+400 to 3+900   | 1   | 500    | 3.00  | 1.00   | 1,500         | Cft                 |
|        | RD 3+900 to 4+523   | 1   | 623    | 11.00 | 1.00   | 6,853         | Cft                 |
|        | RD 4+730 to 5+500   | 1   | 770    | 15.75 | 0.25   | 3,032         | Cft                 |
|        | RD 5+500 to 6+300   | 1   | 800    | 14.75 | 1.00   | 11,800        | Cft                 |
|        | Rd 6+300 to 7+000   | 1   | 700    | 3.00  | 1.00   | 2,100         | Cft                 |
|        | Rd 7+000 to 9+100   | 1   | 2,100  | 18.00 | 1.00   | 37,800        | Cft                 |
|        | RD 9+100 to 10+190  | 1   | 1,090  | 9.50  | 1.00   | 10,355        | Cft                 |
|        |   |     |        |       |        | Total         | 167,344 Cft         |
|        |   |     |        |       |        | <b>Total.</b> | <b>167.34 %oCft</b> |
| 5      | Supplying and filling sand under floor; or plugging in wells  |     |        |       |        |               |                     |
|        | Rd 4+723 to 6+100 for existing sewer line   | 1   | 1,377  | 18.00 | 0.50   | 12,393        | Cft                 |
|        |   |     |        |       |        | Total         | 12,393 Cft          |
|        |   |     |        |       |        | <b>Total.</b> | <b>123.93 %Cft</b>  |

**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**P-1 GOJRA TOBA ROAD**

**CALCULATION OF QUANTITIES**

**ROADS NET WORK**

| Sr. No | Description   | No. | Length | Width | Height        | Qty.          | Unit.       |
|--------|---|-----|--------|-------|---------------|---------------|-------------|
| 6      | Relaying sub-base course of stone product of approved quality and grade including, placing, mixing, spreading and compaction of sub base material to required depth, camber and grade to achieve 98% maximum dry density determined according to AASHTO T-180 method-D, including carriage of all material to site of work complete in all respect as per specifications and as directed by the engineer incharge.  |     |        |       |               |               |             |
|        | <b>90% of the Dismantle Material</b>  |     |        |       |               | 20,601        |             |
|        |   |     |        |       | Total         | 20,601        | Cft         |
|        |   |     |        |       | <b>Total.</b> | <b>20.60</b>  | <b>%Cft</b> |
|        | <b>Sub Base Course</b>  |     |        |       |               |               |             |
| 7      | Providing and laying sub-base course of stone product of approved quality and grade including, placing, mixing, spreading and compaction of sub base material to required depth, camber and grade to achieve 98% maximum dry density determined according to AASHTO T-180 method-D, including carriage of all material to site of work complete in all respect as per specifications and as directed by the engineer incharge. (Crushed stone aggregate from Sargodha quarry to site, actual compacted depth shall be considered for payment) |     |        |       |               |               |             |
|        | <b>For Road</b>   |     |        |       |               |               |             |
|        | RD 0+000 to 3+400   | 1   | 3,400  | 2.00  | 0.50          | 3,400         | Cft         |
|        | Rd 5+500 to 6+300   | 2   | 800    | 8.50  | 0.50          | 6,800         | Cft         |
|        | Rd 7+000 to 9+100   | 2   | 2,100  | 10.50 | 0.50          | 22,050        | Cft         |
|        | RD 9+100 to 10+190  | 2   | 1,090  | 14.50 | 0.50          | 15,805        | Cft         |
|        | <b>For Tuff Paver Shoulders</b>   |     |        |       |               |               |             |
|        | RD 0+000 to 3+400   | 1   | 3,400  | 8.50  | 0.50          | 14,450        | Cft         |
|        | RD 3+400 to 3+900   | 1   | 500    | 3.00  | 0.50          | 750           | Cft         |
|        | RD 3+900 to 4+523   | 1   | 623    | 11.00 | 0.50          | 3,427         | Cft         |
|        | RD 4+730 to 5+500   | 1   | 770    | 15.75 | 0.50          | 6,064         | Cft         |
|        | RD 5+500 to 6+300   | 1   | 800    | 14.75 | 0.50          | 5,900         | Cft         |
|        | Rd 6+300 to 7+000   | 1   | 700    | 3.00  | 0.50          | 1,050         | Cft         |
|        | Rd 7+000 to 9+100   | 1   | 2,100  | 18.00 | 0.50          | 18,900        | Cft         |
|        | RD 9+100 to 10+190  | 1   | 1,090  | 9.50  | 0.50          | 5,178         | Cft         |
|        |   |     |        |       | Total         | 103,773       | Cft         |
|        | D/d Dismantle Material  |     |        |       |               | (20,601)      |             |
|        |   |     |        |       | <b>Total.</b> | <b>831.72</b> | <b>%Cft</b> |

**PUNJAB CITIES PROGRAM (PCP)  
DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
SUPERVISION IN 16 CITIES OF PUNJAB**

**P-1 GOJRA TOBA ROAD**

**CALCULATION OF QUANTITIES**

**ROADS NET WORK**

| Sr. No | Description   | No. | Length | Width | Height | Qty.          | Unit.             |
|--------|---|-----|--------|-------|--------|---------------|-------------------|
|        | <b>Road Edging</b>  |     |        |       |        |               |                   |
| 8      | Providing and laying road edging of 3" (75 mm) wide and 9" (225 mm) deep brick on end, complete in all respects.  |     |        |       |        |               |                   |
|        | RD 0+000 to 3+400   | 2   | 3,400  |       |        | 6,800         | Rft               |
|        | RD 3+900 to 4+523   | 2   | 623    |       |        | 1,246         | Rft               |
|        | RD 4+730 to 5+500   | 2   | 770    |       |        | 1,540         | Rft               |
|        | RD 5+500 to 6+300   | 2   | 800    |       |        | 1,600         | Rft               |
|        | Rd 6+300 to 7+000   | 2   | 700    |       |        | 1,400         | Rft               |
|        | Rd 7+000 to 9+100   | 2   | 2,100  |       |        | 4,200         | Rft               |
|        | RD 9+100 to 10+190  | 2   | 1,090  |       |        | 2,180         | Rft               |
|        |   |     |        |       |        |               |                   |
|        |   |     |        |       |        | <b>Total.</b> | <b>18,966 Rft</b> |
|        | <b>Water Bound Macadam</b>  |     |        |       |        |               |                   |
| 9      | Providing and laying base course of crushed stone (Water Bound Macadam) of approved quality and grade including, placing, mixing, spreading and compaction of base course material to required depth, camber and grade to achieve 100% maximum modified AASHTO dry density, including carriage of all material to site of work complete in all respect as per specifications and as directed by the engineer incharge. (Crushed stone aggregate from Sargodha quarry to site, actual compacted depth shall be considered for payment) |     |        |       |        |               |                   |
|        | Crushed stone aggregate from approved quarry  |     |        |       |        |               |                   |
|        | <b>For Carriage Way</b>   |     |        |       |        |               |                   |
|        | RD 0+000 to 3+400   | 1   | 3,400  | 16.00 | 0.33   | 17,952        | Cft               |
|        | RD 3+900 to 4+523   | 1   | 623    | 30.00 | 0.42   | 7,850         | Cft               |
|        | RD 4+730 to 5+500   | 2   | 770    | 24.00 | 0.50   | 18,480        | Cft               |
|        | RD 5+500 to 6+300   | 2   | 800    | 24.00 | 0.50   | 19,200        | Cft               |
|        | Rd 6+300 to 7+000   | 2   | 700    | 24.00 | 0.50   | 16,800        | Cft               |
|        | Rd 7+000 to 9+100   | 2   | 2,100  | 24.00 | 0.50   | 50,400        | Cft               |
|        | RD 9+100 to 10+190  | 2   | 1,090  | 24.00 | 0.67   | 35,054        | Cft               |
|        | <b>For Tuff Paver Shoulders</b>   |     |        |       |        |               |                   |
|        | RD 0+000 to 3+400   | 1   | 3,400  | 8.50  | 0.33   | 9,537         | Cft               |
|        | RD 3+400 to 3+900   | 1   | 500    | 3.00  | 0.33   | 495           | Cft               |
|        | RD 3+900 to 4+523   | 1   | 623    | 11.00 | 0.33   | 2,261         | Cft               |
|        | RD 4+730 to 5+500   | 1   | 770    | 15.75 | 0.33   | 4,002         | Cft               |
|        | RD 5+500 to 6+300   | 1   | 800    | 14.75 | 0.33   | 3,894         | Cft               |

**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**P-1 GOJRA TOBA ROAD**

**CALCULATION OF QUANTITIES**

**ROADS NET WORK**

| Sr. No | Description  | No. | Length | Width | Height        | Qty.            | Unit.       |
|--------|--|-----|--------|-------|---------------|-----------------|-------------|
|        | Rd 7+000 to 9+100  | 1   | 2,100  | 18.00 | 0.25          | 9,450           | Cft         |
|        | RD 9+100 to 10+190   | 1   | 1,090  | 9.50  | 0.33          | 3,417           | Cft         |
|        |  |     |        |       | Total         | 198,793         | Cft         |
|        |  |     |        |       | <b>Total.</b> | <b>1,987.93</b> | <b>%Cft</b> |
|        | <b>Prime Coat</b>  |     |        |       |               |                 |             |
| 10     | Providing and laying bituminous priming coat, using 10 lbs. kerosene oil and 10 lbs. binder per 100 Sft. or 0.5 Kg kerosene and 0.5 Kg binder per square metre.  |     |        |       |               |                 |             |
|        | RD 0+000 to 3+400  | 1   | 3,400  | 16.00 |               | 54,400          | Sft         |
|        | RD 3+900 to 4+523  | 1   | 623    | 30.00 |               | 18,690          | Sft         |
|        | RD 4+730 to 5+500  | 2   | 770    | 24.00 |               | 36,960          | Sft         |
|        | RD 5+500 to 6+300  | 2   | 800    | 24.00 |               | 38,400          | Sft         |
|        | Rd 6+300 to 7+000  | 2   | 700    | 24.00 |               | 33,600          | Sft         |
|        | Rd 7+000 to 9+100  | 2   | 2,100  | 24.00 |               | 100,800         | Sft         |
|        | RD 9+100 to 10+190   | 2   | 1,090  | 24.00 |               | 52,320          | Sft         |
|        | Approach Roads   | 7   | 25     | 15.00 |               | 2,625           | Sft         |
|        |  |     |        |       | Total         | 337,795         | Sft         |
|        |  |     |        |       | <b>Total.</b> | <b>3,377.95</b> | <b>%Sft</b> |
| 11     | Providing and laying bituminous tack coat, using 10 lbs. of bitumen per 100 Sft (0.49 Kg of bitumen per sq.m.)   |     |        |       |               |                 |             |
|        | RD 4+730 to 5+500  | 2   | 770    | 24.00 |               | 36,960          | Sft         |
|        | RD 5+500 to 6+300  | 2   | 800    | 24.00 |               | 38,400          | Sft         |
|        | Rd 6+300 to 7+000  | 2   | 700    | 24.00 |               | 33,600          | Sft         |
|        | Rd 7+000 to 9+100  | 2   | 2,100  | 24.00 |               | 100,800         | Sft         |
|        | RD 9+100 to 10+190   | 2   | 1,090  | 24.00 |               | 52,320          | Sft         |
|        |  |     |        |       | Total         | 262,080         | Sft         |
|        |  |     |        |       | <b>Total.</b> | <b>2,620.80</b> | <b>%Sft</b> |
|        | <b>Carpeting</b>   |     |        |       |               |                 |             |
|        | <b>ABC</b>   |     |        |       |               |                 |             |
| 12     | Providing and laying plant premixed bituminous carpet, including compaction and finishing to required camber, grade and density. (2 inch thick) (iii) 4% Bitumen |     |        |       |               |                 |             |
|        | RD 4+730 to 5+500  | 2   | 770    | 24.00 |               | 36,960          | Sft         |
|        | RD 5+500 to 6+300  | 2   | 800    | 24.00 |               | 38,400          | Sft         |

**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**P-1 GOJRA TOBA ROAD**

**CALCULATION OF QUANTITIES**

**ROADS NET WORK**

| Sr. No | Description  | No. | Length | Width | Height        | Qty.            | Unit.       |
|--------|--|-----|--------|-------|---------------|-----------------|-------------|
|        | Rd 6+300 to 7+000  | 2   | 700    | 24.00 |               | 33,600          | Sft         |
|        | Rd 7+000 to 9+100  | 2   | 2,100  | 24.00 |               | 100,800         | Sft         |
|        | RD 9+100 to 10+190   | 2   | 1,090  | 24.00 |               | 52,320          | Sft         |
|        |  |     |        |       | Total         | 262,080         | Sft         |
|        |  |     |        |       | <b>Total.</b> | <b>2,620.80</b> | <b>%Sft</b> |
|        | <b>AWC</b>   |     |        |       |               |                 |             |
| 13     | Providing and laying plant premixed bituminous carpet, including compaction and finishing to required camber, grade and density. (1.5 inch thick)<br>(iv) 4.5% Bitumen                       |     |        |       |               |                 |             |
|        | RD 4+730 to 5+500  | 2   | 770    | 24.00 |               | 36,960          | Sft         |
|        | RD 5+500 to 6+300  | 2   | 800    | 24.00 |               | 38,400          | Sft         |
|        | Rd 6+300 to 7+000  | 2   | 700    | 24.00 |               | 33,600          | Sft         |
|        | Rd 7+000 to 9+100  | 2   | 2,100  | 24.00 |               | 100,800         | Sft         |
|        | RD 9+100 to 10+190   | 2   | 1,090  | 24.00 |               | 52,320          | Sft         |
|        |  |     |        |       | Total         | 262,080         | Sft         |
|        |  |     |        |       | <b>Total.</b> | <b>2,620.80</b> | <b>%Sft</b> |
| 14     | Providing and laying plant premixed bituminous carpet, including compaction and finishing to required camber, grade and density. (2 inch thick)<br>(iv) 4.5% Bitumen                         |     |        |       |               |                 |             |
|        | RD 0+000 to 3+400  | 1   | 3,400  | 16.00 |               | 54,400          | Sft         |
|        | RD 3+900 to 4+523  | 1   | 623    | 30.00 |               | 18,690          | Sft         |
|        |  |     |        |       | Total         | 73,090          | Sft         |
|        |  |     |        |       | <b>Total.</b> | <b>730.90</b>   | <b>%Sft</b> |
|        | <b>Paint For Traffic Lanes</b>   |     |        |       |               |                 |             |
| 15     | Painting Traffic Lane Marking of specified width (1.5mm thick), with Thermoplastic (TP) Paint including Glass Beads, complete in all respect, as approved and directed by Engineer incharge. |     |        |       |               |                 |             |
|        | RD 0+000 to 3+400  | 2.5 | 3,400  |       |               | 8,500           | Rft         |
|        | RD 3+900 to 4+523  | 2.5 | 623    |       |               | 1,558           | Rft         |
|        | RD 4+730 to 5+500  | 5   | 770    |       |               | 3,850           | Rft         |
|        | RD 5+500 to 6+300  | 5   | 800    |       |               | 4,000           | Rft         |
|        | Rd 6+300 to 7+000  | 5   | 700    |       |               | 3,500           | Rft         |
|        | Rd 7+000 to 9+100  | 5   | 2,100  |       |               | 10,500          | Rft         |
|        | RD 9+100 to 10+190   | 5   | 1,090  |       |               | 5,450           | Rft         |
|        |  |     |        |       | <b>Total.</b> | <b>37,358</b>   | <b>Rft</b>  |



**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**P-1 GOJRA TOBA ROAD**

**CALCULATION OF QUANTITIES**

**ROADS NETWORK**

| Sr. No | Description   | No. | Length | Width | Height | Qty.          | Unit.          |
|--------|---|-----|--------|-------|--------|---------------|----------------|
| 16     | Providing and fixing precast Edge Kerb Stone (4" to 6" thick), of 3500 PSI Compressive Strength, embedded in PCC 1:2:4 over lean concrete 1:4:8 etc. complete in all respect.   |     |        |       |        |               |                |
|        | b) With Painting  |     |        |       |        |               |                |
|        | (i) 14" high  |     |        |       |        |               |                |
|        | RD 4+730 to 5+500   | 2   | 770    |       |        | 1,540         | Rft            |
|        | RD 5+500 to 6+300   | 2   | 800    |       |        | 1,600         | Rft            |
|        | Rd 6+300 to 7+000   | 2   | 700    |       |        | 1,400         | Rft            |
|        | Rd 7+000 to 9+100   | 2   | 2,100  |       |        | 4,200         | Rft            |
|        | RD 9+100 to 10+190  | 2   | 1,090  |       |        | 2,180         | Rft            |
|        |   |     |        |       |        |               |                |
|        |   |     |        |       |        | <b>Total.</b> | <b>10,920</b>  |
|        |   |     |        |       |        |               | <b>Rft</b>     |
|        | <b>Tuff Paver</b>   |     |        |       |        |               |                |
| 17     | Providing and laying Tuff pavers, having 7000 PSI, crushing strength of approved manufacturer, over 2" to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope. complete in all respect. (50% Grey / 50% Coloured) |     |        |       |        |               |                |
|        | c) 80-mm thick  |     |        |       |        |               |                |
|        | RD 0+000 to 3+400   | 1   | 3,400  | 8.50  |        | 28,900        | Sft            |
|        | RD 3+400 to 3+900   | 1   | 500    | 3.00  |        | 1,500         | Sft            |
|        | RD 3+900 to 4+523   | 1   | 623    | 11.00 |        | 6,853         | Sft            |
|        | RD 4+730 to 5+500   | 1   | 770    | 15.75 |        | 12,128        | Sft            |
|        | RD 5+500 to 6+300   | 1   | 800    | 14.75 |        | 11,800        | Sft            |
|        | Rd 6+300 to 7+000   | 1   | 700    | 3.00  |        | 2,100         | Sft            |
|        | Rd 7+000 to 9+100   | 1   | 2,100  | 18.00 |        | 37,800        | Sft            |
|        | RD 9+100 to 10+190  | 1   | 1,090  | 9.50  |        | 10,355        | Sft            |
|        |   |     |        |       |        |               |                |
|        |   |     |        |       |        | <b>Total.</b> | <b>111,436</b> |
|        |   |     |        |       |        |               | <b>Sft</b>     |
|        | <b>P.C.C (Between Asphalt and Tuff Paver)</b>   |     |        |       |        |               |                |
| 18     | Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate):  |     |        |       |        |               |                |
|        | (f) Ratio 1: 2: 4   |     |        |       |        |               |                |
|        | RD 0+000 to 3+400   | 2   | 3,400  | 0.33  | 0.50   | 1,122         | Cft            |
|        | RD 3+400 to 3+900   | 1   | 500    | 0.33  | 0.50   | 83            | Cft            |
|        | RD 3+900 to 4+523   | 2   | 623    | 0.33  | 0.50   | 206           | Cft            |
|        | RD 4+730 to 5+500   | 2   | 770    | 0.33  | 0.50   | 254           | Cft            |
|        | RD 5+500 to 6+300   | 2   | 800    | 0.33  | 0.50   | 264           | Cft            |
|        | Rd 6+300 to 7+000   | 2   | 700    | 0.33  | 0.50   | 231           | Cft            |

**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**P-1 GOJRA TOBA ROAD**

**CALCULATION OF QUANTITIES**

**ROADS NET WORK**

| Sr. No | Description  | No.  | Length | Width | Height        | Qty.         | Unit.       |
|--------|--|------|--------|-------|---------------|--------------|-------------|
|        | Rd 7+000 to 9+100  | 2    | 2,100  | 0.33  | 0.50          | 693          | Cft         |
|        | RD 9+100 to 10+190   | 2    | 1,090  | 0.33  | 0.50          | 360          | Cft         |
|        |  |      |        |       | Total         | 3,212        | Cft         |
|        |  |      |        |       | <b>Total.</b> | <b>32.12</b> | <b>%Cft</b> |
|        | <b>Cat Eyes</b>  |      |        |       |               |              |             |
| 19     | Providing & fixing Cat Eyes of size 4"x4"x3/4" duly casted with specified material having plastic strip containing mini retro-reflective glass beads of color white /red/ yellow having specifid reflections, quality & shape i/c the cost of self built in 12mm dia x120mm long steel zinc plate dnail, fixing to road with epoxy/ hammering with separate nail complete. |      |        |       |               |              |             |
|        | b) Aluminium Alloy   |      |        |       |               |              |             |
|        | (1) Dual-Directional   |      |        |       |               |              |             |
|        | (ii) 43x2=86 Glass beads a side  | 976  |        |       |               | <b>976</b>   | <b>Each</b> |
|        | (B) Uni-Directional  |      |        |       |               |              |             |
|        | (ii) 43 Glass beads a side   | 3040 |        |       |               | <b>3,040</b> | <b>Each</b> |
| 20     | Providing, fabrication and fixing pole mounted Direction Board/ road delineator of any shape and size, with specified Sheet and thickness, supported with G.I Channel, (excluding the cost of vertical post and painting) etc complete in all respect.   |      |        |       |               |              |             |
|        | (a) G.I Sheet 14 SWG   |      |        |       |               |              |             |
|        | CIRCULAR/TRIANGULAR  |      |        |       |               |              |             |
|        | 3 ft size  | 15   | 3.00   | 2.00  |               | <b>90</b>    | <b>Sft</b>  |
| 21     | Providing, fabrication and fixing Vertical Post comprising of medium quality G.I Pipe of specified diameter, including the cost of clamping arrangements, top cover, hold fasts embedded in PCC 1:2:4 etc, complete in all respect   |      |        |       |               |              |             |
|        | (b) 3 inch diameter  | 15   | 11     |       |               | <b>165</b>   | <b>Rft</b>  |
| 22     | Lettering and printing of signage /direction boards/ road delineators of any colour by machine i/c cost of Digital Lettering, Lamination & pasting etc complete in all respect.  |      |        |       |               |              |             |
|        | a) High Intensity Prismatic (HIP) Tape   |      |        |       |               | <b>90</b>    | <b>Sft</b>  |

**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**P-1 GOJRA TOBA ROAD**

**CALCULATION OF QUANTITIES**

**ROADS NET WORK**

| Sr. No                   | Description   | No. | Length | Width | Height | Qty.          | Unit.              |
|--------------------------|---|-----|--------|-------|--------|---------------|--------------------|
| <b>For Green Belt</b>    |   |     |        |       |        |               |                    |
| 23                       | Turfing slopes of banks or lawns with grass sods including ploughing, laying, setting and watering (Turf got from within a distance of 5 miles (8 Km.) and maintenance for 15 days).  |     |        |       |        |               |                    |
|                          | RD 4+730 to 5+500   | 1   | 770    | 5.00  |        | 3,850         | Sft                |
|                          | RD 5+500 to 6+300   | 1   | 800    | 5.00  |        | 4,000         | Sft                |
|                          | Rd 7+000 to 9+100   | 1   | 2,100  | 5.00  |        | 10,500        | Sft                |
|                          | RD 9+100 to 10+190  | 1   | 1,090  | 5.00  |        | 5,450         | Sft                |
|                          |   |     |        |       |        |               |                    |
|                          |   |     |        |       |        | <b>Total.</b> | <b>238.00 %Sft</b> |
| <b>DRAINAGE SYSTEM</b>   |   |     |        |       |        |               |                    |
| <b>Dismantling</b>       |   |     |        |       |        |               |                    |
| 1                        | c) Dismantling cement concrete 1:2:4 plain.   |     |        |       |        |               |                    |
|                          | Manhole Neck  | 19  | 8.64   | 0.75  | 0.50   | 61.56         | Cft                |
|                          |   |     |        |       |        |               |                    |
|                          |   |     |        |       |        | <b>Total</b>  | <b>0.62 %Cft</b>   |
| <b>Excavation</b>        |   |     |        |       |        |               |                    |
| 2                        | Earthwork excavation in open cutting upto 5'-0" (1.5 m) depth for storm water channels, drains, sullage drains in open areas, roads, streets, lanes, including under pinning of walls and shoring to protect existing works, shuttering and timbering the trenches, dressed to designed level and dimensions, trimming, removal of surface water from trenches, back filling and surplus excavated material disposed of and dressed within 50 ft. (15 m) lead:-<br>i) in ordinary soil. |     |        |       |        |               |                    |
|                          | Pipe Laying   | 15  | 20.00  | 1.50  | 2.50   | 1,125         | Cft                |
|                          | 1'-6" wide drain  | 1   | 5,853  | 4.25  | 3.00   | 74,626        | Cft                |
|                          | Culverts Extension  | 1   | 22     | 4.00  | 4.00   | 352           | Cft                |
|                          |   |     |        |       |        | Total         | 76,103 Cft         |
|                          |   |     |        |       |        | <b>Total</b>  | <b>76.10 %oCft</b> |
| <b>P.C.C</b>             |   |     |        |       |        |               |                    |
| 3                        | Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate):  |     |        |       |        |               |                    |
| <b>(i) Ratio 1: 4: 8</b> |   |     |        |       |        |               |                    |

**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**P-1 GOJRA TOBA ROAD**  
**CALCULATION OF QUANTITIES**  
**ROADS NET WORK**

| Sr. No | Description   | No. | Length | Width | Height       | Qty.          | Unit.       |
|--------|---|-----|--------|-------|--------------|---------------|-------------|
|        | 1'-6" wide drain  | 1   | 5,853  | 4.25  | 0.25         | 6,219         | Cft         |
|        | Culverts Extension  | 1   | 20     | 4.00  | 0.25         | 20            | Cft         |
|        |   |     |        |       | Total        | 6,239         | Cft         |
|        |   |     |        |       | <b>Total</b> | <b>62.39</b>  | <b>%Cft</b> |
|        | <b>(f) Ratio 1: 2: 4</b>  |     |        |       |              |               |             |
|        | 1'-6" wide drain  | 1   | 5,853  | 4.25  | 0.50         | 12,438        | Cft         |
|        | Benching  | 1   | 5,853  | 1.50  | 0.25         | 2,195         | Cft         |
|        | Topping   | 2   | 5,853  | 0.75  | 0.17         | 1,463         | Cft         |
|        | Pipe Laying   | 15  | 10     | 0.75  | 1.50         | 169           | Cft         |
|        | For manhole neck  | 19  | 8.64   | 0.75  | 0.50         | 62            | Cft         |
|        | Culverts Extension  | 1   | 20     | 2.50  | 0.25         | 13            | Cft         |
|        |   |     |        |       | Total        | 16,340        | Cft         |
|        |   |     |        |       | <b>Total</b> | <b>163.40</b> | <b>%Cft</b> |
| 4      | Pacca brick work other than building upto 10ft. (3 m) Cement, sand mortar:- Ratio 1:3 |     |        |       |              |               |             |
|        | 1'-6" wide drain  | 1   | 5,853  | 1.125 | 2.00         | 13,169        | Cft         |
|        |   | 1   | 5,853  | 0.75  | 2.00         | 8,780         | Cft         |
|        | For manhole neck  | 19  | 8.64   | 0.75  | 1.00         | 123           | Cft         |
|        | RD 0+000 to 3+900   | 2   | 3,900  | 0.75  | 0.50         | 2,925         | Cft         |
|        | RD 4+600 to 6+300   | 2   | 1,700  | 0.75  | 0.50         | 1,275         | Cft         |
|        | RD 9+100 to 10+190  | 2   | 1,090  | 0.75  | 0.50         | 818           | Cft         |
|        |   |     |        |       | Total        | 27,089        | Cft         |
|        |   |     |        |       | <b>Total</b> | <b>270.89</b> | <b>%Cft</b> |
| 5      | Extra for pacca brick work in steining of wells or any other circular masonry.        |     |        |       |              |               |             |
|        |   |     |        |       | <b>Total</b> | <b>1.23</b>   | <b>%Cft</b> |
| 6      | Cement plaster 1:3 upto 20' (6.00 m) height:-<br>b) ½" (13 mm) thick                  |     |        |       |              |               |             |
|        | 1'-6" wide drain  | 1   | 5,853  |       | 4.00         | 23,412        | Sft         |
|        | For manhole neck (19 x 2 = 38)  | 38  | 8.64   |       | 1.00         | 328           | Sft         |
|        | RD 0+000 to 3+900   | 2   | 3,900  |       | 0.50         | 3,900         | Sft         |
|        | RD 4+600 to 6+300   | 2   | 1,700  |       | 0.50         | 1,700         | Sft         |
|        | RD 9+100 to 10+190  | 2   | 1,090  |       | 0.50         | 1,090         | Sft         |
|        |   |     |        |       | Total        | 30,430        | Sft         |
|        |   |     |        |       | <b>Total</b> | <b>304.30</b> | <b>%Sft</b> |

**PUNJAB CITIES PROGRAM (PCP)  
DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
SUPERVISION IN 16 CITIES OF PUNJAB**

**P-1 GOJRA TOBA ROAD**

**CALCULATION OF QUANTITIES**

**ROADS NET WORK**

| Sr. No            | Description  | No.  | Length | Width | Height | Qty.         | Unit.           |
|-------------------|--|------|--------|-------|--------|--------------|-----------------|
| <b>R.C.C Work</b> |  |      |        |       |        |              |                 |
| 7                 | Providing and laying reinforced cement concrete (i/c pre-stressed concrete), using coarse sand and screened graded and washed aggregate, in required shape and design, i/c forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete (but excluding the cost of steel reinforcement, its fabrication and placing in position, complete |      |        |       |        |              |                 |
|                   | (a)(iii) Reinforced cement concrete in slab of rafts / strip foundation, base slab of column and retaining walls; etc and footing beams, other structural members other than those mentioned in 6(a) (i)&(ii) above not requiring form work (i.e. horizontal shuttering) complete in all respects:-  |      |        |       |        |              |                 |
|                   | (3) Type C (nominal mix 1: 2: 4)   | 1    | 20     | 3.84  | 0.67   | 51.00        | Cft             |
|                   |  |      |        |       |        | <b>Total</b> | <b>51.00</b>    |
|                   |  |      |        |       |        |              | <b>Cft</b>      |
|                   | a).(i) Reinforced cement concrete in roof slab, beams, columns, lintels, girders and other structural members laid in situ or pre-cast laid in position, or pre-stressed members cast in situ, complete in all respect. Type C (nominal mix 1:2:4)   |      |        |       |        |              |                 |
|                   | 1'-6" wide drain   | 0.4  | 5,853  | 3.50  | 0.67   | 5,490.00     | Cft             |
|                   | Wall   | 2    | 20     | 0.67  | 2.50   | 67.00        | Cft             |
|                   | Top Slab   | 1    | 20     | 3.84  | 0.67   | 51.00        | Cft             |
|                   | RD 0+000 to 3+900  | 0.25 | 3,900  | 3.75  | 0.67   | 2,450.00     | Cft             |
|                   | RD 4+600 to 6+300  | 0.25 | 1,700  | 4.00  | 0.67   | 1,139.00     | Cft             |
|                   | RD 9+100 to 10+190   | 0.25 | 1,090  | 3.00  | 0.67   | 548.00       | Cft             |
|                   |  |      |        |       |        | <b>Total</b> | <b>9,745.00</b> |
|                   |  |      |        |       |        |              | <b>Cft</b>      |
| <b>Steel</b>      |  |      |        |       |        |              |                 |
| 8                 | Fabrication of mild steel reinforcement for cement concrete, i/c cutting, bending, laying in position, making joints and fastening, i/c cost of bending wire and labour charges for bending of steel reinforcement (also includes removal of rust from deformed bars) Gade 60  |      |        |       |        |              |                 |
|                   | Concrete Qty   |      | 9,796  | Cft @ | 6.75   | 66,123       | lbs/cft         |

**PUNJAB CITIES PROGRAM (PCP)  
DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
SUPERVISION IN 16 CITIES OF PUNJAB**

**P-1 GOJRA TOBA ROAD**

**CALCULATION OF QUANTITIES**

**ROADS NET WORK**

| <b>Sr. No</b> | <b>Description</b>   | <b>No.</b> | <b>Length</b> | <b>Width</b> | <b>Height</b> | <b>Qty.</b>  | <b>Unit.</b>  |
|---------------|--|------------|---------------|--------------|---------------|--------------|---------------|
|               |  |            |               |              |               | 30,001       | kg            |
|               |  |            |               |              |               | <b>Total</b> | <b>300.01</b> |
|               |  |            |               |              |               |              | <b>Kg</b>     |
|               | <b>Gully Grating Chamber</b>   |            |               |              |               |              |               |
| 9             | Constructing standard gully grating chamber, 3'x2½' (900x750 mm), with chinaware trap as per PHED Drawing STD/PD No. 3 of 1977, complete in all respects.  | 15         |               |              |               | <b>15.00</b> | <b>Each</b>   |
| 10            | Supplying and filling sand under floor; or plugging in wells.  | 15         | 20.00         | 2.50         | 1.00          | <b>7.50</b>  | <b>%Cft</b>   |
|               | <b>uPVC Pipe</b>   |            |               |              |               |              |               |
| 11            | Providing, fixing, testing and commissioning of µ-PVC (Unplasticized polyvinyl Chloride) Nikasi /waste pipe make of dadex / Popular / Beta/ BBJ plain / socket ended conforming to code EN-1401 of specified SDR (Standard Dimension Ratio) including the cost of specials and Solvents complete in all respect as approved and directed by the Engineer Incharge. |            |               |              |               |              |               |
|               | <b>Type (SDR 41/SN-4)</b>  |            |               |              |               |              |               |
|               | (vii) 8"(200 mm)   | 15         | 20.00         |              |               | <b>300</b>   | <b>Rft</b>    |
|               | <b>Kerb Stone</b>  |            |               |              |               |              |               |
| 12            | Providing and fixing precast Edge Kerb Stone (4" to 6" thick), of 3500 PSI Compressive Strength, embedded in PCC 1:2:4 over lean concrete 1:4:8 etc. complete in all respect.  |            |               |              |               |              |               |
|               | b) With Painting   | 0.5        | 5,853         |              |               | <b>2,927</b> | <b>Rft</b>    |
|               | <b>RPC Manhole Cover</b>   |            |               |              |               |              |               |
| 13            | Providing and fixing RPC Manhole Cover Manufactured with 100% Reinforced Plastic Composite Material, 650 mm dia with clear opening size 600 mm (24" dia) and RPC manhole frame having dia meter 790 mm (Complete) (Certified under ISO 9001-2015)  | 19         |               |              |               | <b>19</b>    | <b>Each</b>   |

**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**P-1 GOJRA TOBA ROAD**  
**CALCULATION OF QUANTITIES**  
**ROADS NET WORK**

| Sr. No                          | Description  | No. | Length     | Width | Height       | Qty.         | Unit.        |
|---------------------------------|--|-----|------------|-------|--------------|--------------|--------------|
| <b>ELECTRICAL WORKS</b>         |  |     |            |       |              |              |              |
| <b>Scheduled Items (A)</b>      |  |     |            |       |              |              |              |
| <b>Excavation</b>               |  |     |            |       |              |              |              |
| 1                               | Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain (30 m) and lift upto 5 ft. (1.5 m)   |     |            |       |              |              |              |
|                                 | a) By Manual   |     |            |       |              |              |              |
|                                 | ii) in ordinary soil.  |     |            |       |              |              |              |
|                                 | For pipe 50mm dia from TR to LCP and LCP to poles  | 1   | 11,875     | 1.00  | 2.50         | 29,688       | Cft          |
|                                 | Light Poles  | 95  | 2.00       | 2.00  | 6.00         | 2,280        | Cft          |
|                                 |  |     |            |       | Total        | 31,968       | Cft          |
|                                 |  |     |            |       | <b>Total</b> | <b>31.97</b> | <b>%oCft</b> |
| <b>RCC Foundation for Poles</b> |  |     |            |       |              |              |              |
| 2                               | Providing and laying reinforced cement concrete (including prestressed concrete), using coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete (but excluding the cost of steel reinforcement, its fabrication and placing in position, etc.):- |     |            |       |              |              |              |
|                                 | (a)(iii) Reinforced cement concrete in slab of rafts / strip foundation, base slab of column and retaining walls; etc and footing beams, other structural members other than those mentioned in 6(a) (i)&(ii) above not requiring form work (i.e. horizontal shuttering) complete in all respects:-  |     |            |       |              |              |              |
|                                 | (2) Type B (nominal mix 1: 1½: 3)  |     |            |       |              |              |              |
|                                 | Light Poles  | 95  | 2.00       | 2.00  | 6.00         | 2,280        | Cft          |
|                                 |  |     |            |       | Total        | 2,280.00     | Cft          |
| <b>Steel Work</b>               |  |     |            |       |              |              |              |
| 3                               | Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):-  |     |            |       |              |              |              |
|                                 | (c) Deformed bars (Grade-60)   |     | 2.50Kg/Cft |       |              | 5,700        | Kg           |

**PUNJAB CITIES PROGRAM (PCP)  
DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
SUPERVISION IN 16 CITIES OF PUNJAB**

**P-1 GOJRA TOBA ROAD  
CALCULATION OF QUANTITIES  
ROADS NET WORK**

| Sr. No | Description   | No. | Length | Width | Height | Qty.          | Unit.        |           |
|--------|---|-----|--------|-------|--------|---------------|--------------|-----------|
|        |   |     |        |       |        | <b>Total</b>  | <b>57.00</b> | <b>Kg</b> |
| 4      | Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:-<br>i) 50 mm i/d  |     |        |       |        |               |              |           |
|        | From LCP to Pole and pole to pole (Up + Down)   | 95  | 125.00 |       |        | <b>11,875</b> | <b>Rft</b>   |           |
| 5      | Supply and erection of single core PVC insulated, PVC sheathed copper conductor, 660/1100 volts grade cable, in prelaid G.I. pipe/M.S. conduits/PVC pipe/G.I. wire/trenches, etc (rate for cable only):-<br>ii) 6 mm sq (7/0.044")  |     |        |       |        |               |              |           |
|        | For two nos. Earthing lead  | 95  | 20.00  |       |        | <b>1,900</b>  | <b>Rft</b>   |           |
| 6      | Supply and erection of copper conductor cables for service connection, in prelaid pipe/G.I. wire / trenches, etc. (rate for cable only):-<br>b) PVC insulated, PVC sheathed 3 core, 660/1100 volt cable:-<br>iii) 7/0.74 mm (7/0.029")  |     |        |       |        |               |              |           |
|        | From Terminal Box to light fixture on pole (P+N+E)  | 95  | 40.00  |       |        | <b>3,800</b>  | <b>Rft</b>   |           |
|        | c) PVC insulated, PVC sheathed 4 core, 660/1100 volt non armoured cable:-<br>vi) 10 mm (7/0.052")   | 95  | 125.00 |       |        | <b>11,875</b> | <b>Rft</b>   |           |
|        | vii) 16 mm (7/0.064")   | 1   | 100.00 |       |        | <b>100</b>    | <b>Rft</b>   |           |
| 7      | Supplying, installation testing and commissioning of Octagonal shape electric street light pole, made of hot dipped 4.5 mm thick (7 SWG) galvanized steel ,tapped from 225 mm at bottom to 100 mm at top,with 1500 mmx60 mm dia. arm for luminaire installation, duly G.I.welded with 470x470x20 mm base plate with the help of 4 no triangular stiffeners 100x350x20 mm of GI sheet,with built in junction box with shutter,i/c the cost of nuts & J-rag bolts, duly fixed in prelaid concrete foundation, foundation will be paid additionally as approved and directed by the Engineer Incharge. |     |        |       |        |               |              |           |
|        | a) Single Arm   |     |        |       |        |               |              |           |



**PUNJAB CITIES PROGRAM (PCP)  
DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
SUPERVISION IN 16 CITIES OF PUNJAB**

**P-1 GOJRA TOBA ROAD**

**CALCULATION OF QUANTITIES**

**ROADS NET WORK**

| <b>Sr. No</b> | <b>Description</b>  | <b>No.</b> | <b>Length</b> | <b>Width</b> | <b>Height</b> | <b>Qty.</b> | <b>Unit.</b> |
|---------------|---|------------|---------------|--------------|---------------|-------------|--------------|
|               | (i) 10 mtr height   | 41         |               |              |               | <b>41</b>   | <b>Nos</b>   |
|               | b) Double Arm   |            |               |              |               |             |              |
|               | (i) 10 mtr height   | 54         |               |              |               | <b>54</b>   | <b>Nos</b>   |
| 8             | Supplying, installation and commissioning of LED Cobra-head Luminaries of specified wattage and lumens conforming to IP 65, Philips/ Osram /Thorn with corrosion resistant die casted aluminum housing, silicon gas kit, thermally hardened glass complete with LED drivers, surge protection i/c the cost of all accessories/ components required for proper operation, fully flexible for future upgradation and easy replacements for maintenance purposes, bucket elevator charges as approved and directed by the Engineer Incharge.   |            |               |              |               |             |              |
|               | c) 120 Lm/Watt  |            |               |              |               |             |              |
|               | (v) 90 Watt with 10800 Lumens   | 149        |               |              |               | <b>149</b>  | <b>Nos</b>   |
| 9             | Supply and erection of electric energy meter, including meter testing fee, etc.   |            |               |              |               |             |              |
|               | b) three phase, 4 wires:  |            |               |              |               |             |              |
|               | ii) 3x50 Amp, 400 volts   | 1          |               |              |               | <b>1.00</b> | <b>Nos</b>   |
| 10            | Supply, installation, commissioning and testing of oil cooled type, Step down Power Transformer of specified rating, 11/0.415 kV, i/c the cost of lifting hooks, thermometers, LT & HT bushing 5-steps, tap changer, imported double float buchholz relay, 2 earthing terminals, roller wheels, connecting terminals for cables M.S box on transformer in order to cover complete L.T side, all necessary materials required for connections on H.T & L.T side, rated voltage 11000/415/240 V impedance 6.25% or as specified by WAPDA/IEC system earth: Delta / Star, neutral solidly earthed, i/c Wapda testing charges, complete in all respects made of PEL, Siemens, as approved and directed by the Engineer Incharge |            |               |              |               |             |              |
|               | (iii) 25 KVA  | 1          |               |              |               | <b>1.00</b> | <b>Nos.</b>  |

**PUNJAB CITIES PROGRAM (PCP)  
 DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
 SUPERVISION IN 16 CITIES OF PUNJAB**

**P-1 GOJRA TOBA ROAD**

**CALCULATION OF QUANTITIES**

**ROADS NET WORK**

| Sr. No | Description   | No. | Length | Width | Height | Qty.         | Unit.       |
|--------|---|-----|--------|-------|--------|--------------|-------------|
| 11     | Earthing of iron clad/aluminum switches, etc. with G.I. wire No. 8 SWG in G.I. pipe 15 mm (½") dia, recessed or on surface of wall and floor, complete with 1.5 metre long G.I. pipe, 50 mm (2") dia with reducing socket 4 to 5 metre below ground level, and 2 metre away from building plinth.   | 98  |        |       |        | <b>98.00</b> | <b>No.</b>  |
| 12     | Fabrication, Supply, testing and commissioning of following Light control panels (LCP), floor standing weather proof, IP 65 Rated of appropriate size, made of MS Sheet 16 SWG with hinged door, handle, catcher, 2 coats of antirust and powder coated paint of approved colour, AC3 magnetic contactor, photocell for automatic operation of lights, CBs, Hand/Off/Auto switch, push button and all necessary accessories complete in all respects. LCP shall be manufactured as per specifications, single line diagram complete in all respect up to the satisfaction of Engineer incharge. |     |        |       |        |              |             |
|        | LCP-3 Phase   | 1   |        |       |        | <b>1.00</b>  | <b>Nos.</b> |
| 13     | Shifting of 20 Nos. Wapda Electric Poles  |     |        |       |        |              |             |
| 14     | Electric Connection Charges   | 1   |        |       |        | <b>1.00</b>  | <b>Each</b> |

# ENVIRONMENTAL HEALTH SAFETY BUDGET

**PUNJAB CITIES PROGRAM (PCP)  
DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
SUPERVISION IN 16 CITIES OF PUNJAB**

**DETAILED COST ESTIMATE**

**ENVIRONMENT AND SOCIAL MITIGATION COST**

| <b>Sr No</b> | <b>Description</b>   | <b>Unit</b> | <b>Quantity</b> | <b>Unit Rate (Rs.)</b> | <b>Amount Rs.</b> |
|--------------|--|-------------|-----------------|------------------------|-------------------|
|              | <b>Labor Safety</b>  |             |                 |                        |                   |
| 1            | Face Masks (3 PLY)   | Nos         | 10.00           | 700.00                 | 7,000             |
| 2            | Safety Gum Shoes   | Nos         | 10.00           | 1,350.00               | 13,500            |
| 3            | Hand Gloves  | Nos         | 10.00           | 245.00                 | 2,450             |
| 4            | First Aid Box<br>(Including essential Medicine)  | Nos         | 1.00            | 5,000.00               | 5,000             |
| 5            | Safety Hard Helmets MSA  | Nos         | 10.00           | 2,000.00               | 20,000            |
| 6            | Safety Goggles   | Nos         | 10.00           | 550.00                 | 5,500             |
| 7            | Reflective Safety Vests  | Nos         | 10.00           | 550.00                 | 5,500             |
| 8            | Infrared Thermometer<br>(Benetech GM-2200 OR equivalent)   | Nos         | 1.00            | 45,000.00              | 45,000            |
|              |  |             |                 | <b>Sub Total</b>       | <b>103,950</b>    |
|              | <b>Working Site Safety</b>   |             |                 |                        |                   |
| 1            | Reflective Safety Signs Boards   | Nos         | 10.00           | 10,000.00              | 100,000           |
| 2            | Reflective Safety PVC Cones (18 inch)  | Nos         | 10.00           | 1,200.00               | 12,000            |
| 3            | Road Guiding Portable Delineators with Chain   | Nos         | 10.00           | 1,500.00               | 15,000            |
| 4            | Reflective Safety Barricading Tape   | Nos         | 10.00           | 1,500.00               | 15,000            |
| 5            | Emergency Portable Light   | Nos         | 10.00           | 5,000.00               | 50,000            |
| 6            | Solid Waste Collection Drums   | Nos         | 10.00           | 5,000.00               | 50,000            |
| 7            | Fire Extinguishers DCP   | Nos         | 10.00           | 7,000.00               | 70,000            |
|              |  |             |                 | <b>Sub Total</b>       | <b>312,000</b>    |
|              | <b>Others</b>  |             |                 |                        |                   |
| 1            | Pole Hanging Waste Bins  | Nos.        | 1.00            | 10,000                 | 10,000            |
| 2            | Water Sprinkling<br>(Dust Abatement)   | L.S         | 1.00            | 100,000                | 100,000           |
| 3            | Roadside Plantation  | L.S         | 1.00            | 57,050                 | 57,050            |
| 4            | Environmental Analytical Assessments<br>(Ambient Air Quality Testing, Noise Testing,<br>Vehicular Emissions Testing/Generators, Surface<br>Water & Ground Water Testing) | L.S         | 1.00            | 250,000                | 250,000           |
| 5            | Hiring of Environmentalist<br>(03 Months Budget)   | L.S         | 1.00            | 250,000                | 250,000           |
| 6            | Labor Campsite Management  | L.S         | 1.00            | 250,000                | 250,000           |
|              |  |             |                 | <b>Sub Total</b>       | <b>917,050</b>    |
|              | <b>Total Amount (Rs)</b>   |             |                 |                        | <b>1,333,000</b>  |

## RATE ANALYSIS

**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**Rate Analysis Road- 2**

| <b>Description</b>  |  |                                 |             |                  |            |                  |                    |
|---|--|---------------------------------|-------------|------------------|------------|------------------|--------------------|
| Providing and laying sub-base course of stone product of approved quality and grade including, placing, mixing, spreading and compaction of sub base material to required depth, camber and grade to achieve 98% maximum dry density determined according to AASHTO T-180 method-D, including carriage of all material to site of work complete in all respect as per specifications and as directed by the engineer incharge. (Crushed stone aggregate from Sargodha quarry to site, actual compacted depth shall be considered for payment) |  |                                 |             |                  |            |                  |                    |
| <b>Crush Stone</b>  |  |                                 |             |                  |            |                  | <b>125 KM</b>      |
| <b>Sr. No.</b>  | <b>1st BI-Annual-2023 (Jan to July)</b><br><b>Toba Tek Singh</b> | <b>Description</b>              | <b>Unit</b> | <b>Lead (Km)</b> | <b>Qty</b> | <b>Rate (Rs)</b> | <b>Amount (Rs)</b> |
| <b>1</b>  |  | <b>Material</b>                 |             |                  |            |                  |                    |
|   | 18-3 a(i)  | i) Pit run or bed run gravel.   | 100 Cft     | 1                | 1          | 6,503.25         | 6,503.25           |
| <b>2</b>  |  | <b>Carriage</b>                 |             |                  |            |                  |                    |
|   | 1/1  | 1st KM                          | 100 Cft     | 1                | 1.20       | 305.40           | 366.48             |
|   |  | 2nd KM                          | 100 Cft     | 1                | 1.20       | 145.65           | 174.78             |
|   |  | 3rd KM                          | 100 Cft     | 1                | 1.20       | 114.10           | 136.92             |
|   |  | 4th KM                          | 100 Cft     | 1                | 1.20       | 81.20            | 97.44              |
|   |  | 5th KM                          | 100 Cft     | 1                | 1.20       | 75.85            | 91.02              |
|   |  | 6th KM                          | 100 Cft     | 1                | 1.20       | 74.60            | 89.52              |
|   |  | 7th KM                          | 100 Cft     | 1                | 1.20       | 69.60            | 83.52              |
|   |  | 8th KM                          | 100 Cft     | 1                | 1.20       | 68.85            | 82.62              |
|   |  | 9th KM                          | 100 Cft     | 1                | 1.20       | 64.75            | 77.70              |
|   |  | 10th KM                         | 100 Cft     | 1                | 1.20       | 60.75            | 72.90              |
|   |  | From 11 km to 200 km            | 100 Cft     | 115              | 1.20       | 52.20            | 7,203.60           |
|   |  | <b>Total.</b>                   |             |                  |            |                  | <b>14,979.75</b>   |
|   |  | <b>Total Amount per 100 Cft</b> |             |                  |            |                  | <b>14,979.75</b>   |
|   |  | <b>Total cast for Per Cft</b>   |             |                  |            |                  | <b>149.80</b>      |

**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**Rate Analysis Road - 3**

Providing and laying base course of crushed stone (Water Bound Macadam) of approved quality and grade including, placing, mixing, spreading and compaction of base course material to required depth, camber and grade to achieve 100% maximum modified AASHTO dry density, including carriage of all material to site of work complete in all respect as per specifications and as directed by the engineer incharge. (Crushed stone aggregate from Sargodha quarry to site, actual compacted depth shall be considered for payment)

|         |  |   |         |           |      |           | 125 KM           |
|---------|--|---|---------|-----------|------|-----------|------------------|
| Sr. No. | 1st BI-Annual-2023 (Jan to July)<br>Toba Tek Singh | Description   | Unit    | Lead (Km) | Qty  | Rate (Rs) | Amount (Rs.)     |
| 1       | 18/4(a)  | Providing and laying base course of crushed stone (Water Bound Macadam) of approved quality and grade including, placing, mixing, spreading and compaction of base course material to required depth, camber and grade to achieve 100% maximum modified AASHTO dry density, including carriage of all material to site of work complete in all respect as per specifications and as directed by the engineer incharge. (Crushed stone aggregate from Sargodha quarry to site, actual compacted depth shall be considered for payment) | 100 Cft |           | 1    | 13,865.65 | 13,865.65        |
| 2       | 1/1  | Carriage of 100 cft of all materials like stone aggregate spawl kanker lime surkhi etc or 150 cft of timber by truck or by any other means owned by the contractor.   |         |           |      |           |                  |
|         |  | 1st KM  | 100 Cft | 1         | 1.22 | 305.40    | 372.59           |
|         |  | 2nd KM  | 100 Cft | 1         | 1.22 | 145.65    | 177.69           |
|         |  | 3rd KM  | 100 Cft | 1         | 1.22 | 114.10    | 139.20           |
|         |  | 4th KM  | 100 Cft | 1         | 1.22 | 81.20     | 99.06            |
|         |  | 5th KM  | 100 Cft | 1         | 1.22 | 75.85     | 92.54            |
|         |  | 6th KM  | 100 Cft | 1         | 1.22 | 74.60     | 91.01            |
|         |  | 7th KM  | 100 Cft | 1         | 1.22 | 69.60     | 84.91            |
|         |  | 8th KM  | 100 Cft | 1         | 1.22 | 68.85     | 84.00            |
|         |  | 9th KM  | 100 Cft | 1         | 1.22 | 64.75     | 79.00            |
|         |  | 10th KM   | 100 Cft | 1         | 1.22 | 60.75     | 74.12            |
|         |  | From 11 km to 200 km  | 100 Cft | 115       | 1.22 | 52.20     | 7,323.66         |
|         |  | <b>Total.</b>   |         |           |      |           | <b>22,483.43</b> |
|         |  | <b>Total Amount per 100 Cft</b>   |         |           |      |           | <b>22,483.43</b> |
|         |  | <b>Total cast for Per Cft</b>   |         |           |      |           | <b>224.83</b>    |

**PUNJAB CITIES PROGRAM (PCP)  
DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
SUPERVISION IN 16 CITIES OF PUNJAB**

**Rate Analysis Road - 4**

**ABC**

Providing and laying plant premixed bituminous carpet, including compaction and finishing to required camber, grade and density. (2 inch thick)  
(iii) 4% Bitumen

|         |  |   |                                |           |        |           | 125 Km           |
|---------|--|---|--------------------------------|-----------|--------|-----------|------------------|
| Sr. No. | 1st BI-Annual-2023 (Jan to July)<br>Toba Tek Singh | Description   | Unit                           | Lead (Km) | Qty    | Rate (Rs) | Amount (Rs.)     |
| 1       | 18/10/a  | Providing and laying plant premixed bituminous carpet, including compaction and finishing to required camber, grade and density. (2 inch thick)<br>(iii) 4% Bitumen | per inch thickness per 100Sft. |           | 1.00   | 12,951.30 | 12,951.30        |
| 2       | 1/1  | Carriage of 100 cft of all materials like stone aggregate spawl kanker lime surkhi etc or 150 cft of timber by truck or by any other means owned by the contrator.  |                                |           |        |           |                  |
|         |  | 1st KM  | 100 Cft                        | 1         | 0.1243 | 305.40    | 37.96            |
|         |  | 2nd KM  | 100 Cft                        | 1         | 0.1243 | 145.65    | 18.10            |
|         |  | 3rd KM  | 100 Cft                        | 1         | 0.1243 | 114.10    | 14.18            |
|         |  | 4th KM  | 100 Cft                        | 1         | 0.1243 | 81.20     | 10.09            |
|         |  | 5th KM  | 100 Cft                        | 1         | 0.1243 | 75.85     | 9.43             |
|         |  | 6th KM  | 100 Cft                        | 1         | 0.1243 | 74.60     | 9.27             |
|         |  | 7th KM  | 100 Cft                        | 1         | 0.1243 | 69.60     | 8.65             |
|         |  | 8th KM  | 100 Cft                        | 1         | 0.1243 | 68.85     | 8.56             |
|         |  | 9th KM  | 100 Cft                        | 1         | 0.1243 | 64.75     | 8.05             |
|         |  | 10th KM   | 100 Cft                        | 1         | 0.1243 | 60.75     | 7.55             |
|         |  | From 11 km to 200 km  | 100 Cft                        | 115       | 0.1243 | 52.20     | 746.17           |
|         |  | <b>Total.</b>   |                                |           |        |           | <b>13,829.32</b> |
|         |  | <b>Total Amount per 100 Sft</b>   |                                |           |        |           | <b>13,829.32</b> |
|         |  | <b>Total cast for Per Sft</b>   |                                |           |        |           | <b>138.29</b>    |



**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**Rate Analysis Road - 5**

**AWC**

Providing and laying plant premixed bituminous carpet, including compaction and finishing to required camber, grade and density. (1.50 inch thick)

(iv) 4.5% Bitumen

|         |  |   |                                |           |        |           | 125 Km           |
|---------|--|---|--------------------------------|-----------|--------|-----------|------------------|
| Sr. No. | 1st BI-Annual-2023 (Jan to July)<br>Toba Tek Singh | Description   | Unit                           | Lead (Km) | Qty    | Rate (Rs) | Amount (Rs.)     |
| 1       | 18/10/a  | Providing and laying plant premixed bituminous carpet, including compaction and finishing to required camber, grade and density. (1.50 inch thick)<br>(iv) 4.5% Bitumen | Per inch thickness per 100Sft. |           | 1.00   | 10,402.43 | 10,402.43        |
| 2       | 1/1  | Carriage of 100 cft of all materials like stone aggregate spawl kanker lime surkhi etc or 150 cft of timber by truck or by any other means owned by the contractor.     |                                |           |        |           |                  |
|         |  | 1st KM  | 100 Cft                        | 1         | 0.1243 | 305.40    | 37.96            |
|         |  | 2nd KM  | 100 Cft                        | 1         | 0.1243 | 145.65    | 18.10            |
|         |  | 3rd KM  | 100 Cft                        | 1         | 0.1243 | 114.10    | 14.18            |
|         |  | 4th KM  | 100 Cft                        | 1         | 0.1243 | 81.20     | 10.09            |
|         |  | 5th KM  | 100 Cft                        | 1         | 0.1243 | 75.85     | 9.43             |
|         |  | 6th KM  | 100 Cft                        | 1         | 0.1243 | 74.60     | 9.27             |
|         |  | 7th KM  | 100 Cft                        | 1         | 0.1243 | 69.60     | 8.65             |
|         |  | 8th KM  | 100 Cft                        | 1         | 0.1243 | 68.85     | 8.56             |
|         |  | 9th KM  | 100 Cft                        | 1         | 0.1243 | 64.75     | 8.05             |
|         |  | 10th KM   | 100 Cft                        | 1         | 0.1243 | 60.75     | 7.55             |
|         |  | From 11 km to 200 km  | 100 Cft                        | 115       | 0.1243 | 52.20     | 746.17           |
|         |  | <b>Total.</b>   |                                |           |        |           |                  |
|         | <b>Total Amount per 100 Sft</b>                    |   |                                |           |        |           | <b>11,280.45</b> |
|         | <b>Total cast for Per Sft</b>                      |   |                                |           |        |           | <b>112.80</b>    |

**PUNJAB CITIES PROGRAM (PCP)**  
**DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS**  
**SUPERVISION IN 16 CITIES OF PUNJAB**

**Rate Analysis Road - 5**

**AWC**

Providing and laying plant premixed bituminous carpet, including compaction and finishing to required camber, grade and density. (2.0 inch thick)

(iv) 4.5% Bitumen

|         |  |   |                                |           |        |           | 125 Km           |
|---------|--|---|--------------------------------|-----------|--------|-----------|------------------|
| Sr. No. | 1st BI-Annual-2023 (Jan to July)<br>Toba Tek Singh | Description   | Unit                           | Lead (Km) | Qty    | Rate (Rs) | Amount (Rs.)     |
| 1       | 18/10/a  | Providing and laying plant premixed bituminous carpet, including compaction and finishing to required camber, grade and density. (1.50 inch thick)<br>(iv) 4.5% Bitumen | Per inch thickness per 100Sft. |           | 1.00   | 13,869.90 | 13,869.90        |
| 2       | 1/1  | Carriage of 100 cft of all materials like stone aggregate spawl kanker lime surkhi etc or 150 cft of timber by truck or by any other means owned by the contractor.     |                                |           |        |           |                  |
|         |  | 1st KM  | 100 Cft                        | 1         | 0.1243 | 305.40    | 37.96            |
|         |  | 2nd KM  | 100 Cft                        | 1         | 0.1243 | 145.65    | 18.10            |
|         |  | 3rd KM  | 100 Cft                        | 1         | 0.1243 | 114.10    | 14.18            |
|         |  | 4th KM  | 100 Cft                        | 1         | 0.1243 | 81.20     | 10.09            |
|         |  | 5th KM  | 100 Cft                        | 1         | 0.1243 | 75.85     | 9.43             |
|         |  | 6th KM  | 100 Cft                        | 1         | 0.1243 | 74.60     | 9.27             |
|         |  | 7th KM  | 100 Cft                        | 1         | 0.1243 | 69.60     | 8.65             |
|         |  | 8th KM  | 100 Cft                        | 1         | 0.1243 | 68.85     | 8.56             |
|         |  | 9th KM  | 100 Cft                        | 1         | 0.1243 | 64.75     | 8.05             |
|         |  | 10th KM   | 100 Cft                        | 1         | 0.1243 | 60.75     | 7.55             |
|         |  | From 11 km to 200 km  | 100 Cft                        | 115       | 0.1243 | 52.20     | 746.17           |
|         |  | <b>Total.</b>   |                                |           |        |           |                  |
|         | <b>Total Amount per 100 Sft</b>                    |   |                                |           |        |           | <b>14,747.92</b> |
|         | <b>Total cast for Per Sft</b>                      |   |                                |           |        |           | <b>147.48</b>    |

**PUNJAB CITIES PROGRAM (PCP) DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS  
AND RESIDENTS SUPERVISION IN 16 CITIES OF PUNJAB**

**Rate Analysis Road - 6**

| Description  |                |                            |  |               |        |              |                  |               |                |
|--|----------------|----------------------------|--|---------------|--------|--------------|------------------|---------------|----------------|
| Dismantling / Demolishing of existing Tuff Paver as directed by Engineer's Incharge, Complete in all respect |                |                            |  |               |        |              |                  |               |                |
| <b>Dismantling of Tuff Paver</b>   |                |                            |  |               |        |              |                  | <b>Unit.</b>  | <b>100 Sft</b> |
| Sr. No.  | Ref Input Rate | Detail                     | Unit Rate (British System) per 100 Sft |               |        |              |                  |               |                |
|  |                |                            | Qty                                    | Rate Per Unit |        | Amount (Rs.) |                  |               |                |
|  |                | <b><u>LABOUR</u></b>       |  |               |        |              |                  |               |                |
| 2  | LB-015         | Cooly un-skilled           | 0.75                                   | Nos.          | 965.00 | per day      |                  | 723.75        |                |
|  |                |                            |  |               |        |              | <b>Total.</b>    | <b>723.75</b> |                |
|  |                | Sundries                   | 10                                     | %             |        |              |                  | 72.38         |                |
|  |                |                            |  |               |        |              | <b>Total Rs.</b> | <b>796.13</b> |                |
|  |                | Contractor's Profit        | 20                                     | %             |        |              |                  | 159.23        |                |
|  |                | <b>Total</b>               |  |               |        |              |                  | <b>955.35</b> |                |
|  |                | <b><u>ITEM RATES</u></b>   |  |               |        |              |                  |               |                |
|  |                | Composite rate per 100 Sft |  |               |        |              | Rs.              | <b>955.35</b> |                |
|  |                | Composite rate per Sft     |  |               |        |              | Rs.              | <b>9.56</b>   |                |

**PUNJAB CITIES PROGRAM (PCP)  
DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
SUPERVISION IN 16 CITIES OF PUNJAB**

**Rate Analysis Road - 7**

| Description  |                |                            |  |               |          |              |                  |                 |                |
|--|----------------|----------------------------|--|---------------|----------|--------------|------------------|-----------------|----------------|
| Dismantling / Demolishing of existing kerb stone as directed by Engineer's Incharge, Complete in all respect |                |                            |  |               |          |              |                  |                 |                |
| <b>Dismantling Kerb stone</b>  |                |                            |  |               |          |              |                  | <b>Unit.</b>    | <b>100 Rft</b> |
| Sr. No.  | Ref Input Rate | Detail                     | Unit Rate (British System) per 100 Rft |               |          |              |                  |                 |                |
|  |                |                            | Qty                                    | Rate Per Unit |          | Amount (Rs.) |                  |                 |                |
|  |                | <b><u>LABOUR</u></b>       |  |               |          |              |                  |                 |                |
| 2  | LB-015         | Cooly un-skilled           | 2.00                                   | Nos.          | 1,050.00 | per day      |                  | 2,100.00        |                |
|  |                |                            |  |               |          |              | <b>Total.</b>    | <b>2,100.00</b> |                |
|  |                | Sundries                   | 10                                     | %             |          |              |                  | 210.00          |                |
|  |                |                            |  |               |          |              | <b>Total Rs.</b> | <b>2,310.00</b> |                |
|  |                | Contractor's Profit        | 20                                     | %             |          |              |                  | 462.00          |                |
|  |                | <b>Total</b>               |  |               |          |              |                  | <b>2,772.00</b> |                |
|  |                | <b><u>ITEM RATES</u></b>   |  |               |          |              |                  |                 |                |
|  |                | Composite rate per 100 Rft |  |               |          |              | Rs.              | <b>2,772.00</b> |                |
|  |                | Composite rate per Rft     |  |               |          |              | Rs.              | <b>27.72</b>    |                |

**PUNJAB CITIES PROGRAM (PCP)  
DETAILED DESIGN OF INFRASTRUCTURE SUB-PROJECTS AND RESIDENTS  
SUPERVISION IN 16 CITIES OF PUNJAB**

**Rate Analysis Road - 8**

**Description**

Providing and fixing RPC Manhole Cover Manufactured with 100% Reinforced Plastic Composite Material, 650 mm dia with clear opening size 600 mm (24" dia) and RPC manhole frame having dia meter 790 mm (Complete) (Certified under ISO 9001-2015)

**Manhole Cover**

| Sr. No. | Ref Input Rate | Detail                   | Unit Rate (British System) per Each |               |                             |
|---------|----------------|--------------------------|-------------------------------------|---------------|-----------------------------|
|         |                |                          | Qty                                 | Rate Per Unit | Amount (Rs.)                |
|         | Page No112     |                          |                                     |               |                             |
| 1       | A              | RPC Manhole Cover        | 1.00                                | No            | 8,400.00                    |
|         |                | Carriage                 |                                     |               | 700                         |
|         |                |                          |                                     |               | <b>Total Rs. 9,100.00</b>   |
|         |                | <b><u>LABOUR</u></b>     |                                     |               |                             |
| 2       | LB-024         | Skilled Cooly            | 0.50                                | Nos.          | 700.00                      |
|         |                |                          |                                     |               | <b>Total. 700.00</b>        |
|         |                | Sundries                 | 10                                  | %             | 70.00                       |
|         |                |                          |                                     |               | <b>Total Rs. 770.00</b>     |
|         |                |                          |                                     |               | <b>Total (1+2) 9,870.00</b> |
|         |                | Contractor's Profit      | 20                                  | %             | 1,974.00                    |
|         |                | Total                    |                                     |               | <b>11,844</b>               |
|         |                | <b><u>ITEM RATES</u></b> |                                     |               |                             |
|         |                | Composite rate Set       |                                     |               | <b>Rs. 11,844</b>           |

**Annexure-C**  
**Project Economic Analysis**

## FINANCIAL ANALYSIS ROAD NETWORK

TABLE - 9.1

### AVERAGE OPERATING SPEEDS

Km/Hr

#### WITHOUT PROJECT CONDITION

| Years           | Cars/Jeeps | Hiace Wagon/<br>Pickup | Coaster/<br>Mini Buses | Buses | Trucks | Trucks              | Trucks<br>5-AXLE &<br>6-AXLE |
|-----------------|------------|------------------------|------------------------|-------|--------|---------------------|------------------------------|
|                 |            |                        |                        |       | 2-AXLE | 3-AXLE & 4-<br>AXLE |                              |
| Base Year(2022) | 25         | 20                     | 20                     | 15    | 15     | 15                  | 15                           |
| 2029            | 20         | 15                     | 15                     | 10    | 10     | 10                  | 10                           |
| 2037            | 15         | 10                     | 10                     | 10    | 10     | 10                  | 10                           |

#### WITH PROJECT CONDITION

| Years           | Cars/Jeeps | Hiace Wagon/<br>Pickup | Coaster/<br>Mini Buses | Buses | Trucks | Trucks              | Trucks<br>5-AXLE &<br>6-AXLE |
|-----------------|------------|------------------------|------------------------|-------|--------|---------------------|------------------------------|
|                 |            |                        |                        |       | 2-AXLE | 3-AXLE & 4-<br>AXLE |                              |
| Base Year(2022) | 25         | 20                     | 20                     | 15    | 15     | 15                  | 15                           |
| 2029            | 20         | 15                     | 15                     | 10    | 10     | 10                  | 10                           |
| 2037            | 15         | 10                     | 10                     | 10    | 10     | 10                  | 10                           |

**TABLE - 9.3**  
**VEHICLE OPERATING COSTS**  
**FOR POOR ROAD CONDITIONS**  
**WITHOUT PROJECT**

| Rs/Km  |                |          |       |       |          |       |                 |                             |                             |
|--------|----------------|----------|-------|-------|----------|-------|-----------------|-----------------------------|-----------------------------|
| SPEEDS | MOTOR<br>CYCLE | RICKSHAW | CAR   | WAGON | MINI-BUS | BUS   | TRUCK<br>2-AXLE | TRUCK<br>3-AXLE &<br>4-AXLE | TRUCK<br>5-AXLE &<br>6-AXLE |
| 10     | 4.94           | 6.86     | 56.39 | 57.04 | 68.24    | 97.79 | 103.44          | 109.08                      | 114.72                      |
| 15     | 4.21           | 5.89     | 47.21 | 47.89 | 57.70    | 82.34 | 86.88           | 92.52                       | 98.16                       |
| 20     | 3.80           | 5.35     | 42.43 | 43.08 | 52.15    | 74.07 | 75.86           | 81.50                       | 87.14                       |
| 25     | 3.53           | 5.00     | 39.47 | 40.32 | 48.67    | 68.87 | 67.55           | 73.19                       | 78.83                       |
| 30     | 3.35           | 4.76     | 37.48 | 38.27 | 46.28    | 65.37 | 61.01           | 66.65                       | 72.29                       |
| 35     | 3.23           | 4.60     | 36.09 | 36.79 | 44.55    | 63.00 | 55.82           | 61.46                       | 67.10                       |
| 40     | 3.16           | 4.51     | 35.10 | 35.70 | 43.28    | 61.46 | 51.79           | 57.43                       | 63.07                       |
| 45     | 3.12           | 4.47     | 34.42 | 34.89 | 42.35    | 60.58 | 48.80           | 54.44                       | 60.08                       |
| 50     | 3.12           | 4.47     | 33.99 | 34.31 | 41.69    | 60.28 | 46.78           | 52.42                       | 58.07                       |
| 55     | 3.16           | 4.53     | 33.76 | 33.91 | 41.26    | 60.48 | 45.70           | 51.34                       | 56.98                       |
| 60     | 3.22           | 4.64     | 33.71 | 33.68 | 41.03    | 61.14 | 45.52           | 51.16                       | 56.80                       |
| 65     | 3.30           | 4.77     | 33.82 | 33.58 | 40.98    | 62.24 | 46.22           | 51.86                       | 57.50                       |
| 70     | 3.42           | 4.95     | 34.09 | 33.62 | 41.09    | 63.76 | 47.80           | 53.44                       | 59.08                       |
| 75     | 3.56           | 5.18     | 34.49 | 33.77 | 41.36    | 65.68 | 50.23           | 55.87                       | 61.51                       |
| 80     | 3.73           | 5.42     | 35.02 | 34.04 | 41.76    | 67.99 | 53.51           | 59.15                       | 64.79                       |
| 85     | 3.93           | 5.73     | 35.68 | 34.41 | 42.31    | 70.68 | 57.63           | 63.28                       | 68.92                       |



**TABLE- 9.4  
FOR GOOD ROAD CONDITIONS  
WITH PROJECT**

| SPEEDS | MOTOR<br>CYCLE | RICKSHAW | CAR   | WAGON | MINI-BUS | BUS   | Rs/Km           |                              |                              |
|--------|----------------|----------|-------|-------|----------|-------|-----------------|------------------------------|------------------------------|
|        |                |          |       |       |          |       | TRUCK<br>2-AXLE | TRUCK<br>3-AXLE & 4-<br>AXLE | TRUCK<br>5-AXLE & 6-<br>AXLE |
| 10     | 3.71           | 5.12     | 35.59 | 34.99 | 41.42    | 61.63 | 65.14           | 69.34                        | 73.54                        |
| 15     | 3.08           | 4.29     | 28.49 | 28.17 | 33.56    | 50.94 | 54.02           | 58.23                        | 62.43                        |
| 20     | 2.73           | 3.83     | 24.80 | 24.60 | 29.44    | 45.22 | 46.71           | 50.92                        | 55.12                        |
| 25     | 2.50           | 3.53     | 22.53 | 22.35 | 26.84    | 41.60 | 41.22           | 45.42                        | 49.62                        |
| 30     | 2.35           | 3.33     | 21.00 | 20.80 | 25.05    | 39.13 | 36.87           | 41.08                        | 45.28                        |
| 35     | 2.25           | 3.19     | 19.92 | 19.67 | 23.75    | 37.40 | 33.40           | 37.60                        | 41.80                        |
| 40     | 2.19           | 3.11     | 19.16 | 18.83 | 22.77    | 36.21 | 30.65           | 34.85                        | 39.06                        |
| 45     | 2.15           | 3.07     | 18.62 | 18.20 | 22.05    | 35.43 | 28.55           | 32.76                        | 36.96                        |
| 50     | 2.15           | 3.08     | 18.26 | 17.73 | 21.51    | 35.01 | 27.06           | 31.26                        | 35.46                        |
| 55     | 2.17           | 3.12     | 18.06 | 17.39 | 21.13    | 34.89 | 26.13           | 30.33                        | 34.54                        |
| 60     | 2.21           | 3.19     | 17.99 | 17.17 | 20.88    | 35.05 | 25.76           | 29.96                        | 34.16                        |
| 65     | 2.28           | 3.30     | 18.04 | 17.06 | 20.76    | 35.48 | 25.92           | 30.12                        | 34.32                        |
| 70     | 2.37           | 3.44     | 18.19 | 17.03 | 20.74    | 36.14 | 26.61           | 30.81                        | 35.01                        |
| 75     | 2.49           | 3.61     | 18.45 | 17.09 | 20.83    | 37.04 | 27.82           | 32.02                        | 36.22                        |
| 80     | 2.62           | 3.81     | 18.80 | 17.23 | 21.01    | 38.17 | 29.54           | 33.74                        | 37.94                        |
| 85     | 2.77           | 4.04     | 19.24 | 17.44 | 21.29    | 39.52 | 31.77           | 35.98                        | 40.18                        |
| 90     | 2.95           | 4.31     | 19.77 | 17.73 | 21.65    | 41.08 | 31.77           | 35.98                        | 40.18                        |

**TABLE - 9.5  
VALUE OF TRAVEL TIME**

| DESCRIPTION  | MOTORCYCLE   | CAR           | WAGON         | COASTER/<br>FLYING COACH | TRUCK        | BUS            |
|--|--------------|---------------|---------------|--------------------------|--------------|----------------|
| <b><u>TRAVEL TIME VALUE OF PASSENGERS/OCCUPANTS</u></b>                  |              |               |               |                          |              |                |
| Average Income of Passenger (Rs./Month)                                  | 40,000       | 60,000        | 30,000        | 22,000                   | 35,000       | 30,000         |
| Average Income of Passenger (Rs./Annum)                                  | 480,000      | 720,000       | 360,000       | 264,000                  | 420,000      | 360,000        |
| Working Hours /Annum   | 2424         | 2424          | 2424          | 2424                     | 2424         | 2424           |
| Rate of passenger Rs./Hour   | 198          | 297           | 149           | 109                      | 173          | 149            |
| No. of Occupants   | 2.00         | 5.00          | 16.00         | 29.00                    | 2.00         | 45.00          |
| Travel Time Value of occupants---in financial terms (Rs./Hour)           | 396.04       | 1485.15       | 2376.24       | 3158.42                  | 346.53       | 6683.17        |
| <b>Travel Time Value of occupants---in economic terms (Rs./Hour) 25%</b> | <b>99.01</b> | <b>371.29</b> | <b>594.06</b> | <b>789.60</b>            | <b>86.63</b> | <b>1670.79</b> |

NOTE:- 'The value of travel time in a number of studies have been estimated at 25% to 33% of the wage rate due to lack of information on the split of work and non-work travel among passengers and the 'proportion of non-wage earners among passengers.

**TABLE - 9.6**  
**Gojra (3.1 km)**  
**ANNUAL VEHICLE OPERATING COST**  
**WITHOUT PROJECT**

(Million Rs.)

| Years                             | Voc/Km<br>(Rs.) | Traffic Volume<br>ADT | Distance<br>Annual<br>Km | Total Cost<br>Million Rs. |
|-----------------------------------|-----------------|-----------------------|--------------------------|---------------------------|
| <b>Motor Cycles\Rickshaw</b>      |                 |                       |                          |                           |
| Base Year(2022)                   | 4.26            | 3540                  | 1,132                    | 17.08                     |
| 2029                              | 4.57            | 6019                  | 1,132                    | 31.15                     |
| 2037                              | 5.05            | 10833                 | 1,132                    | 61.91                     |
| <b>Cars</b>                       |                 |                       |                          |                           |
| Base Year(2022)                   | 39.47           | 1384                  | 1,132                    | 61.83                     |
| 2029                              | 42.43           | 2353                  | 1,132                    | 112.98                    |
| 2037                              | 47.21           | 4236                  | 1,132                    | 226.26                    |
| <b>Wagons</b>                     |                 |                       |                          |                           |
| Base Year(2022)                   | 43.08           | 5                     | 1,132                    | 0.24                      |
| 2029                              | 47.89           | 9                     | 1,132                    | 0.46                      |
| 2037                              | 57.04           | 15                    | 1,132                    | 0.99                      |
| <b>Bus</b>                        |                 |                       |                          |                           |
| Base Year(2022)                   | 82.34           | 3                     | 1,132                    | 0.28                      |
| 2029                              | 97.79           | 5                     | 1,132                    | 0.56                      |
| 2037                              | 97.79           | 9                     | 1,132                    | 1.02                      |
| <b>T.Trolley + Trucks 2-AXLE</b>  |                 |                       |                          |                           |
| Base Year(2022)                   | 86.88           | 14                    | 1,132                    | 1.38                      |
| 2029                              | 103.44          | 24                    | 1,132                    | 2.79                      |
| 2037                              | 103.44          | 43                    | 1,132                    | 5.01                      |
| <b>Trucks 3-AXLE &amp; 4-AXLE</b> |                 |                       |                          |                           |
| Base Year(2022)                   | 92.52           | 3                     | 1,132                    | 0.31                      |
| 2029                              | 109.08          | 5                     | 1,132                    | 0.63                      |
| 2037                              | 109.08          | 9                     | 1,132                    | 1.13                      |
| <b>Trucks 5-AXLE &amp; 6-AXLE</b> |                 |                       |                          |                           |
| Base Year(2022)                   | 98.16           | 0                     | 1,132                    | -                         |
| 2029                              | 114.72          | 0                     | 1,132                    | -                         |
| 2037                              | 114.72          | 0                     | 1,132                    | -                         |
| <b>TOTAL</b>                      |                 |                       |                          |                           |
| Base Year(2022)                   |                 |                       |                          | <b>81.13</b>              |
| 2029                              |                 |                       |                          | <b>148.57</b>             |
| 2037                              |                 |                       |                          | <b>296.33</b>             |

Note : "VOC" means Vehicle Operating Cost

**TABLE - 9.7**  
**Gojra (3.1 km)**  
**ANNUAL VEHICLE OPERATING COST**  
**WITH PROJECT**

(Million Rs.)

| Years                             | Voc/Km (Rs.) | Traffic Volume ADT | Distance Annual Km | Total Cost Million Rs. |
|-----------------------------------|--------------|--------------------|--------------------|------------------------|
| <b>Motor Cycles\Rickshaw</b>      |              |                    |                    |                        |
| Base Year(2022)                   | 2.65         | 3540               | 1,132              | 10.61                  |
| 2029                              | 2.72         | 6019               | 1,132              | 18.52                  |
| 2037                              | 2.84         | 10833              | 1,132              | 34.84                  |
| <b>Cars</b>                       |              |                    |                    |                        |
| Base Year(2022)                   | 19.16        | 1384               | 1,132              | 30.00                  |
| 2029                              | 19.92        | 2353               | 1,132              | 53.05                  |
| 2037                              | 21.00        | 4236               | 1,132              | 100.66                 |
| <b>Wagons</b>                     |              |                    |                    |                        |
| Base Year(2022)                   | 18.83        | 5                  | 1,132              | 0.11                   |
| 2029                              | 19.67        | 9                  | 1,132              | 0.19                   |
| 2037                              | 20.80        | 15                 | 1,132              | 0.36                   |
| <b>Bus</b>                        |              |                    |                    |                        |
| Base Year(2022)                   | 36.21        | 3                  | 1,132              | 0.12                   |
| 2029                              | 37.40        | 5                  | 1,132              | 0.22                   |
| 2037                              | 39.13        | 9                  | 1,132              | 0.41                   |
| <b>T.Trolley + Trucks 2-Axle</b>  |              |                    |                    |                        |
| Base Year(2022)                   | 22.77        | 14                 | 1,132              | 0.36                   |
| 2029                              | 23.75        | 24                 | 1,132              | 0.64                   |
| 2037                              | 25.05        | 43                 | 1,132              | 1.21                   |
| <b>Trucks 3-AXLE &amp; 4-AXLE</b> |              |                    |                    |                        |
| Base Year(2022)                   | 34.85        | 3                  | 1,132              | 0.12                   |
| 2029                              | 37.60        | 5                  | 1,132              | 0.22                   |
| 2037                              | 41.08        | 9                  | 1,132              | 0.43                   |
| <b>Trucks 5-AXLE &amp; 6-AXLE</b> |              |                    |                    |                        |
| Base Year(2022)                   | 39.06        | 3                  | 1,132              | 0.13                   |
| 2029                              | 41.80        | 5                  | 1,132              | 0.24                   |
| 2037                              | 45.28        | 9                  | 1,132              | 0.47                   |
| <b>TOTAL</b>                      |              |                    |                    |                        |
| Base Year(2022)                   |              |                    |                    | <b>41.46</b>           |
| 2029                              |              |                    |                    | <b>73.08</b>           |
| 2037                              |              |                    |                    | <b>138.38</b>          |

Note : "VOC" means Vehicle Operating Cost

**TABLE - 9.8**  
**Gojra (3.1 km)**

(Million Rs.)

| YEARS           | VEHICLE OPERATING COSTS |              | SAVINGS       |
|-----------------|-------------------------|--------------|---------------|
|                 | WITHOUT PROJECT         | WITH PROJECT |               |
| Base Year(2022) | 81.13                   | 41.46        | 39.67         |
| 2029            | 148.57                  | 73.08        | 75.49         |
| 2037            | 296.33                  | 138.38       | 157.95        |
|                 |                         | <b>TOTAL</b> | <b>273.11</b> |

**TABLE - 9.9**  
**Gojra (3.1 km)**  
**ANNUAL VALUE OF TRAVEL TIME COST**  
**WITHOUT PROJECT**

| Years                             | VOT   | Traffic Volume<br>ADT | Distance<br>Annual<br>( Km) | Total Cost<br>Million Rs. |
|-----------------------------------|-------|-----------------------|-----------------------------|---------------------------|
|                                   | Rs/km |                       |                             |                           |
| <b>(Million Rs.)</b>              |       |                       |                             |                           |
| <b>Motor Cycles\Rickshaw</b>      |       |                       |                             |                           |
| Base Year(2022)                   | 3.96  | 3540                  | 1,132                       | 15.86                     |
| 2029                              | 4.95  | 6019                  | 1,132                       | 33.71                     |
| 2037                              | 6.60  | 10833                 | 1,132                       | 80.91                     |
| <b>Cars</b>                       |       |                       |                             |                           |
| Base Year(2022)                   | 14.85 | 1384                  | 1,132                       | 23.26                     |
| 2029                              | 18.56 | 2353                  | 1,132                       | 49.43                     |
| 2037                              | 24.75 | 4236                  | 1,132                       | 118.64                    |
| <b>Wagons</b>                     |       |                       |                             |                           |
| Base Year(2022)                   | 29.70 | 5                     | 1,132                       | 0.17                      |
| 2029                              | 39.60 | 9                     | 1,132                       | 0.38                      |
| 2037                              | 59.41 | 15                    | 1,132                       | 1.03                      |
| <b>Bus</b>                        |       |                       |                             |                           |
| Base Year(2022)                   | 39.48 | 3                     | 1,132                       | 0.13                      |
| 2029                              | 52.64 | 5                     | 1,132                       | 0.30                      |
| 2037                              | 78.96 | 9                     | 1,132                       | 0.82                      |
| <b>T.Trolley + Trucks 2-Axle</b>  |       |                       |                             |                           |
| Base Year(2022)                   | 5.78  | 14                    | 1,132                       | 0.09                      |
| 2029                              | 8.66  | 24                    | 1,132                       | 0.23                      |
| 2037                              | 8.66  | 43                    | 1,132                       | 0.42                      |
| <b>Trucks 3-AXLE &amp; 4-AXLE</b> |       |                       |                             |                           |
| Base Year(2022)                   | 5.78  | 3                     | 1,132                       | 0.02                      |
| 2029                              | 8.66  | 5                     | 1,132                       | 0.05                      |
| 2037                              | 8.66  | 9                     | 1,132                       | 0.09                      |
| <b>Trucks 5-AXLE &amp; 6-AXLE</b> |       |                       |                             |                           |
| Base Year(2022)                   | 5.78  | 3                     | 1,132                       | 0.02                      |
| 2029                              | 8.66  | 5                     | 1,132                       | 0.05                      |
| 2037                              | 8.66  | 9                     | 1,132                       | 0.09                      |
| <b>TOTAL</b>                      |       |                       |                             |                           |
| Base Year(2022)                   |       |                       |                             | 40                        |
| 2029                              |       |                       |                             | 84                        |
| 2037                              |       |                       |                             | 202                       |

Note : "VOT" means value of Travel Cost

**TABLE - 9.10**  
**Gojra (3.1 km)**  
**ANNUAL VALUE OF TRAVEL TIME COST**  
**WITH PROJECT**

(Million Rs.)

| Years                             | VOT   | Traffic Volume<br>ADT | Distance<br>Annual<br>( Km) | Total Cost<br>Million Rs. |
|-----------------------------------|-------|-----------------------|-----------------------------|---------------------------|
|                                   | Rs/km |                       |                             |                           |
| <b>Motor Cycles\Rickshaw</b>      |       |                       |                             |                           |
| Base Year(2022)                   | 2.65  | 3540                  | 1,132                       | 10.61                     |
| 2029                              | 2.72  | 6019                  | 1,132                       | 18.52                     |
| 2037                              | 2.84  | 10833                 | 1,132                       | 34.84                     |
| <b>Cars</b>                       |       |                       |                             |                           |
| Base Year(2022)                   | 19.16 | 1384                  | 1,132                       | 30.00                     |
| 2029                              | 19.92 | 2353                  | 1,132                       | 53.05                     |
| 2037                              | 21.00 | 4236                  | 1,132                       | 100.66                    |
| <b>Wagons</b>                     |       |                       |                             |                           |
| Base Year(2022)                   | 18.83 | 5                     | 1,132                       | 0.11                      |
| 2029                              | 19.67 | 9                     | 1,132                       | 0.19                      |
| 2037                              | 20.80 | 15                    | 1,132                       | 0.36                      |
| <b>Bus</b>                        |       |                       |                             |                           |
| Base Year(2022)                   | 36.21 | 3                     | 1,132                       | 0.12                      |
| 2029                              | 37.40 | 5                     | 1,132                       | 0.22                      |
| 2037                              | 39.13 | 9                     | 1,132                       | 0.41                      |
| <b>T.Trolley + Trucks 2-Axle</b>  |       |                       |                             |                           |
| Base Year(2022)                   | 22.77 | 14                    | 1,132                       | 0.36                      |
| 2029                              | 23.75 | 24                    | 1,132                       | 0.64                      |
| 2037                              | 25.05 | 43                    | 1,132                       | 1.21                      |
| <b>Trucks 3-AXLE &amp; 4-AXLE</b> |       |                       |                             |                           |
| Base Year(2022)                   | 34.85 | 3                     | 1,132                       | 0.12                      |
| 2029                              | 37.60 | 5                     | 1,132                       | 0.22                      |
| 2037                              | 41.08 | 9                     | 1,132                       | 0.43                      |
| <b>Trucks 5-AXLE &amp; 6-AXLE</b> |       |                       |                             |                           |
| Base Year(2022)                   | 39.06 | 3                     | 1,132                       | 0.13                      |
| 2029                              | 41.80 | 5                     | 1,132                       | 0.24                      |
| 2037                              | 45.28 | 9                     | 1,132                       | 0.47                      |
| <b>TOTAL</b>                      |       |                       |                             |                           |
| Base Year(2022)                   |       |                       |                             | <b>41.46</b>              |
| 2029                              |       |                       |                             | <b>73.08</b>              |
| 2037                              |       |                       |                             | <b>138.38</b>             |

**TABLE - 9.11**  
**Gojra (3.1 km)**

**(Million Rs.)**

| YEARS           | ANNUAL VALUE OF TRAVEL TIME COST (VOTT) |              | SAVINGS      |
|-----------------|---|--------------|--------------|
|                 | WITHOUT PROJECT                         | WITH PROJECT |              |
| Base Year(2022) | 39.56                                   | 41.46        | (1.90)       |
| 2029            | 84.16                                   | 73.08        | 11.09        |
| 2037            | 202.00                                  | 138.38       | 63.62        |
|                 |   | <b>TOTAL</b> | <b>72.81</b> |



**TABLE - 9.12**  
**Gojra (3.1 km)**  
**TOTAL PROJECT BENEFITS**

(Million Rs.)

| YEARS           | SAVINGS |        | TOTAL SAVINGS |
|-----------------|---------|--------|---------------|
|                 | VOC     | VOTT   |               |
| Base Year(2022) | 39.67   | (1.90) | 37.77         |
| 2029            | 75.49   | 11.09  | 86.58         |
| 2037            | 157.95  | 63.62  | 221.57        |
|                 | TOTAL   |        | <b>346</b>    |

**TABLE - 9.13**  
**Gojra (3.1 km)**  
**Calculation of Economic Internal Rate of Return**

Million Rs.

| Years                                   | PROJECT ECONOMIC COSTS |        |                                 | Project Economic Benefits | Net Benefits Pattern at Economic Prices |         |         |         |
|---|------------------------|--------|---------------------------------|---------------------------|---|---------|---------|---------|
|   | Investment             | O & M  | Total Costs                     |                           | (a)                                     | (b)     | (c)     | (d)     |
| 1                                       | 258.14                 | 0.00   | 258.14                          | 0.00                      | -258.14                                 | -258.14 | -283.95 | -283.95 |
| 2                                       |                        | 0.00   | 0.00                            | 37.77                     | 37.77                                   | 34.00   | 37.77   | 34.00   |
| 3                                       |                        | 0.00   | 0.00                            | 43.44                     | 43.44                                   | 39.10   | 43.44   | 39.10   |
| 4                                       |                        | 0.00   | 0.00                            | 49.96                     | 49.96                                   | 44.96   | 49.96   | 44.96   |
| 5                                       |                        | 0.00   | 0.00                            | 57.45                     | 57.45                                   | 51.71   | 57.45   | 51.71   |
| 6                                       |                        | 0.00   | 0.00                            | 66.07                     | 66.07                                   | 59.46   | 66.07   | 59.46   |
| 7                                       |                        | 0.00   | 0.00                            | 75.98                     | 75.98                                   | 68.38   | 75.98   | 68.38   |
| 8                                       |                        | 0.00   | 0.00                            | 87.38                     | 87.38                                   | 78.64   | 87.38   | 78.64   |
| 9                                       |                        | 0.00   | 0.00                            | 100.48                    | 100.48                                  | 90.43   | 100.48  | 90.43   |
| 10                                      |                        | 0.00   | 0.00                            | 115.55                    | 115.55                                  | 104.00  | 115.55  | 104.00  |
| <b>Total :</b>                          | 258.14                 | 0.00   | 258.14                          | 634.08                    | 375.94                                  | 312.53  | 350.13  | 286.72  |
| <b>DISCOUNT RATES</b>                   |                        |        |                                 |                           |   |         |         |         |
| <b>PRESENT WORTH OF COST</b>            |                        |        | <b>Present Worth of Benefit</b> | <b>NET PRESENT WORTH</b>  |   |         |         |         |
| 10 %                                    | 234.67                 | 234.67 | 270.29                          | 103.19                    | 69.40                                   | 79.72   | 45.93   |         |
| 12 %                                    | 230.48                 | 230.48 | 241.56                          | 71.47                     | 41.27                                   | 48.42   | 18.23   |         |
| 18 %                                    | 218.76                 | 218.76 | 176.60                          | 1.99                      | -20.09                                  | -19.89  | -41.96  |         |
| 20 %                                    | 215.12                 | 215.12 | 160.27                          | -14.78                    | -34.81                                  | -36.29  | -56.32  |         |
| ECONOMIC INTERNAL RATE OF RETURN 12% DR |                        |        |                                 |                           | 18.22                                   | 15.70   | 15.94   | 13.53   |
| BENEFIT COST / RATIO AT 12 % D.R        |                        |        |                                 | 1.05                      |   |         |         |         |

\* A factor of 0.9 has been used for Capital Cost and O&M Cost in the Economics Terms.

(a) Base Case assuming 10 Years period of analysis.

(b) Benefits decreased by 10 %

(c) Cost over-run by 10 %

(d) Benefit reduction and cost over-run both occurring simultaneously.

**Annexure-D**  
**Gant Chart**

**TENTATIVE PROJECT IMPLEMENTATION SCHEDULE FOR IMPROVEMENT & REHABILITATION OF ROADS IN  
GOJRA CITY  
YEAR (2022-2023)**

| <b>Road</b>          | <b>MAY-23</b> |  |  |  | <b>JUN-23</b> |  |  |  | <b>JUL-23</b> |  |  |  | <b>AUG-23</b> |  |  |  |
|----------------------|---------------|--|--|--|---------------|--|--|--|---------------|--|--|--|---------------|--|--|--|
| P1-(Gojra Toba Road) |               |  |  |  |               |  |  |  |               |  |  |  |               |  |  |  |

**Annexure-E**  
**E&S SOPs**

## *Environmental & Social Screening Checklist*

**Instructions:**

Environmental and Social Focal Persons (ESFPs)<sup>1</sup> nominated by the MCs for PCP environmental and social management, will use this checklist in field for environmental and social screening and categorization of each and every sub-project proposed to be executed under the Program.

Deputy Program Officers-Environmental and Social Management deputed by PMDFC in regional offices will technically assist and support the ESFPs/MCs in filling in of this Checklist

It is to be attached with the main document<sup>2</sup> of sub-projects at planning stage and will be duly signed by the relevant ESFP and endorsed by the respective DPO-ESM

This checklist focuses on environmental issues and social concerns. To ensure that social dimensions are adequately considered, Involuntary Resettlement Screening Checklist will also be used

(iii) The purpose of this E&S Screening Checklists is to identify potential “Negative” impacts of environmental and social attributes or to enhance the existing environmental & social benefits. Use the “remarks” section to discuss any anticipated mitigation measures.

|   |  |            |                                     |            |                          |            |                                     |            |                                     |            |                          |            |                          |
|---|--|------------|-------------------------------------|------------|--------------------------|------------|-------------------------------------|------------|-------------------------------------|------------|--------------------------|------------|--------------------------|
| <b>Name of ESFP:</b>                              | Shahrukh Arif MOI, M. Asad MOP   |            |                                     |            |                          |            |                                     |            |                                     |            |                          |            |                          |
| <b>Name of MC:</b>                                | MC Gojra   |            |                                     |            |                          |            |                                     |            |                                     |            |                          |            |                          |
| <b>Sub-Project Sector:</b>                        | Roads of Gojra   |            |                                     |            |                          |            |                                     |            |                                     |            |                          |            |                          |
| <b>Sub-Project Title:</b>                         | Rehabilitation of P-1 Gojra Toba Road near Railway Chowk, Toba Tek Sigh 3.1 km   |            |                                     |            |                          |            |                                     |            |                                     |            |                          |            |                          |
| <b>Sub- Project Categorization:</b>               | <table style="width: 100%; border: none;"> <tr> <td style="width: 25%;"><b>E-1</b></td> <td style="width: 25%; text-align: center;"><input type="checkbox"/></td> <td style="width: 25%;"><b>S-1</b></td> <td style="width: 25%; text-align: center;"><input type="checkbox"/></td> </tr> <tr> <td><b>E-2</b></td> <td style="text-align: center;"><input checked="" type="checkbox"/></td> <td><b>S-2</b></td> <td style="text-align: center;"><input checked="" type="checkbox"/></td> </tr> <tr> <td><b>E-3</b></td> <td style="text-align: center;"><input type="checkbox"/></td> <td><b>S-3</b></td> <td style="text-align: center;"><input type="checkbox"/></td> </tr> </table> | <b>E-1</b> | <input type="checkbox"/>            | <b>S-1</b> | <input type="checkbox"/> | <b>E-2</b> | <input checked="" type="checkbox"/> | <b>S-2</b> | <input checked="" type="checkbox"/> | <b>E-3</b> | <input type="checkbox"/> | <b>S-3</b> | <input type="checkbox"/> |
| <b>E-1</b>  | <input type="checkbox"/>   | <b>S-1</b> | <input type="checkbox"/>            |            |                          |            |                                     |            |                                     |            |                          |            |                          |
| <b>E-2</b>  | <input checked="" type="checkbox"/>  | <b>S-2</b> | <input checked="" type="checkbox"/> |            |                          |            |                                     |            |                                     |            |                          |            |                          |
| <b>E-3</b>  | <input type="checkbox"/>   | <b>S-3</b> | <input type="checkbox"/>            |            |                          |            |                                     |            |                                     |            |                          |            |                          |
| <b>Date of Screening:</b>                         | <b>16/11/2022</b>  |            |                                     |            |                          |            |                                     |            |                                     |            |                          |            |                          |
| <b>Anticipated Project Activities</b>             | <ul style="list-style-type: none"> <li>Geometric Improvement</li> <li>Asphalt Pavement</li> <li>Tuff Pavement on Shoulders</li> <li>Pavement Marking</li> <li>Street Lighting</li> <li>Improvement of drainage system</li> </ul>   |            |                                     |            |                          |            |                                     |            |                                     |            |                          |            |                          |
| <b>Estimated Cost of Subprojects as per PC-1:</b> | <b>295.88 million PKR – PC1</b><br><br><b>Estimated Cost of ESMP 1333000/-pkr</b>  |            |                                     |            |                          |            |                                     |            |                                     |            |                          |            |                          |
| <b>Completion Time/Duration</b>                   | <b>3 Months</b>  |            |                                     |            |                          |            |                                     |            |                                     |            |                          |            |                          |
| <b>Estimated Labor for Subproject</b>             | <b>20-25</b>   |            |                                     |            |                          |            |                                     |            |                                     |            |                          |            |                          |

<sup>1</sup> In all MCs, ESFPs are notified by Local government; MO (I&S) are focal persons for environmental sector and MO(P) are focal persons for social sectors.

<sup>2</sup> It is meant as PC-I and/or engineering estimates of sub-project

| Screening Questions   | Yes | No | Remarks  |
|---|-----|----|--|
| <b>A. Project Siting</b><br>Is the Sub-Project area adjacent to or within any of the following:   |     |    |  |
| <b>Environmentally sensitive areas?</b>   |     |    |  |
| Legally protected Area  |     | ✓  | <p>The road to be rehabilitated is a commercial or central business area surrounded by multiple shops, small food outlets, banks and so on. It doesn't come under any environmental sensitive area category. Details are shown hereunder:</p> <ul style="list-style-type: none"> <li>• Not a legally protected area</li> <li>• No surface body found within 250 meters of the proposed project.</li> <li>• No estuary and coastal water body found in the project area</li> <li>• Not a protected area for biodiversity</li> <li>• Not a buffer zone or having mangroves or manmade forest or any other area of environmental importance that sought special attention or measures.</li> </ul> |
| Any surface water body (river, canal, stream, lake, wetland) within 250 meter of the proposed sub project <sup>3</sup>  |     | ✓  |  |
| Estuarine   |     | ✓  |  |
| Special area for protecting biodiversity  |     | ✓  |  |
| Buffer zone of protected area   |     | ✓  |  |
| Mangroves Forest  |     | ✓  |  |
| Man-made forest /game reserve, orchid /crops or any other area of environmental importance  |     |    |  |
| <b>Socially sensitive /important areas/communities/ people?</b>   |     |    |  |
| PCRs and or any site of cultural/religious importance (Graveyard, Shrine, Mosque, Church, <i>Gordwarah</i> , Temple, Fort, archeological/historical site) within 100 m of the proposed subproject <sup>4</sup>  | ✓   |    | Mosque and Church were observed within 100 m of the proposed sub-project but these will not be affected by the project activities. Mitigation measures will be provided in the ESMP  |
| Sensitive receptors (Schools, colleges, hospitals and clinics) within 100 meter of the proposed sub project <sup>5</sup>  | ✓   |    | Educational institutes were observed within 100 meters of project site. However, the probability of any negative impact to these sensitive receptors owing to project activities is low.   |
| Any graveyard of local community (Muslims or Christians)  |     | ✓  | Graveyard of any local community isn't present at the proposed project site  |
| Any demographic or socio-economic aspects of the sub-project area that are already vulnerable (e.g., high incidence of marginalized populations, rural-urban migrants, illegal settlements, squatters, ethnic minorities, people with disabilities, people in old age, socially isolated segments <sup>6</sup> of the society and women or children)? |     | ✓  | It's a small scale project regarding rehabilitation of existing road surface. Hence, no demographically or socio-economically vulnerable aspects of the sub-project were observed.   |
| Already existing infrastructure <sup>7</sup> (including public amenities) which may be required to dismantle or may be affected temporarily by any means?   |     | ✓  | The land belongs to MC and all sub-project activities will be carried out there. Similarly, existing road is to be rehabilitated hence, portable items of the shopkeepers will be relocated temporarily. Encroachment in the form of 17 structures was observed in the form of cemented floors, tuft tiles pavements and footsteps that would be dismantled before execution phase. Moreover, one weigh station owned by MC Gojra is over there which covers some portion of the road that   |

| Screening Questions   | Yes | No | Remarks   |
|---|-----|----|---|
|   |     |    | will be covered by tuff pavement through design change to avoid dismantling.<br>For the compensation of loss of 17 structures, a detailed ARAP will be developed.<br>20 Electric poles will be shifted as per information given in the PC-I |
| <b>B. Potential Environmental Impacts</b><br>Will the Sub-Project cause...  |     |    |   |
| Disturbance to habitats/biodiversity of environmentally sensitive or protected areas?   |     | ✓  | The proposed project site doesn't have any environmentally sensitive or protected areas.  |
| Cutting of trees?   |     | ✓  | No tree cutting is required as per scope of work under Sub-Project.   |
| Disruption to habitats/biodiversity of surrounding ecosystem/environment?   |     | ✓  | No disruption to any habitat/ecosystem due to any Sub-project activities.   |
| Generation of wastewater during construction or operation?  |     | ✓  | No wastewater generation is anticipated as per scope of work during execution and operational phase.  |
| Pollution of surface water/ground water due to wastewater discharge from construction site or due to direct/indirect disposal of waste water?               |     | ✓  | No such impact on surface and ground water is anticipated owing to project execution phase.   |
| Alteration of surface water hydrology of waterways resulting in increased sediment in streams/rivers or due to increased soil erosion at construction site? |     | ✓  | No alteration of any waterway involved in the scope of Sub-Project.   |
| Deterioration of surface water quality due to silt runoff and sanitary wastes from worker-based camps and chemicals used in construction?                   |     | ✓  | No labor camps are required to be established as per limited work activities under Sub-Project. However, EHS SOPs developed by PMDFC will be strictly ensured to be followed  |
| Over pumping of ground water, leading to salinization and ground subsidence?  |     | ✓  | Over pumping of ground water is not required for this sub project.  |
| Serious contamination of soil due to construction works?  |     | ✓  | No such impact is expected as per scope of work   |
| Aggravation of solid waste problems in the area?  | ✓   |    | No such impact is expected as per scope of work. However, mitigation plan is proposed to tackle generated waste.  |
| Generation of hazardous waste?  |     | ✓  | Not envisaged   |
| Increased air pollution due to sub-project construction and operation?  | ✓   |    | Suspended dust particles during execution phase might pollute the surrounding air. Hence, water sprinkling at the site is proposed.   |

<sup>3</sup> Ibid.

<sup>4</sup> According to Environmental Assessment Guidelines adopted by Punjab EPA

<sup>5</sup> Ibid.

<sup>6</sup> due to caste, creed, religion or gender e.g. transgender

<sup>7</sup> Sewerage /Drainage system, Water supply lines, tube-wells, WAPDA/Telephone transmission lines/electric poles, Railway tracks, Gas pipelines, Roads, Shops/Plazas, Banks, Industry, Disposal stations etc.



| Screening Questions   | Yes | No | Remarks  |
|---|-----|----|--|
| Noise and vibration due to sub-project construction or operation?   | ✓   |    | Minor impact of noise and vibration owing to movement of heavy vehicles is envisaged during execution phase.   |
| Creation of temporary breeding habitats for diseases such as those transmitted by mosquitoes and rodents due to solid/liquid?   |     | ✓  | No such impact is anticipated as probability of liquid waste is low. However, waste bins at the site would be placed for storage of organic waste if any.  |
| Use of chemicals during construction?   |     | ✓  | In the light of sub-project scope, no hazardous chemical will be used during execution phase.  |
| <b>C: Potential Social Impacts</b>  |     |    |  |
| Will the Sub-Project cause...   |     |    |  |
| Impairment of historical/cultural areas; disfiguration of landscape or potential loss/damage to Physical Cultural Resources (PCRs)?   |     | ✓  | No damage or loss to PCR's is expected due to this sub project.  |
| Displacement or involuntary resettlement of people? (physical displacement and/or economic displacement)<br>(If "Yes", please also fill Involuntary Resettlement Screening Checklist)   |     | ✓  | No significant displacement/ any sort of resettlement/ economic loss is envisaged due to any Sub-Project interventions. However, minor encroached surfaces of shops might be dismantled during execution phase. Hence, ARAP to compensate the economic losses would be prepared. |
| Disproportionate impacts on the poor, women and children and or other vulnerable groups <sup>8</sup> (mentioned above)?   |     | ✓  | No Disproportionate impacts on the poor, women and children and or other vulnerable groups are anticipated during execution phase  |
| Temporary impediments in movements of people/transport and animals?   | ✓   |    | There will be temporary hindrance in the movement of traffic and pedestrians during execution phase of the project. Nearby shop owners have been informed during public consultation phase.  |
| Large population influx during sub-project construction and operation that causes increased burden on social infrastructure and services (such as water supply and sanitation systems)? |     | ✓  | It's a small-scale time framework project so population influx or increased burden on social infrastructure and services will not be effected.   |
| Social conflicts if workers from other areas are hired?   |     | ✓  | Preference will be given locals for work to avoid any conflict.  |
| Risks and vulnerabilities related to occupational health and safety (OHS) due to physical, chemical, biological, and radiological hazards during project construction and operation?    | ✓   |    | Measures would be taken to address or alleviate the probability of OHS risk during execution phase through administrative controls. However, stringent SOPs regarding actualization of PPEs during execution phase will be implemented at the proposed project site.             |

<sup>8</sup> Women, Children, Women headed households, People in old age, people having disabilities, socially isolated community groups and or people living below the poverty line

| Screening Questions  | Yes | No | Remarks  |
|--|-----|----|--|
| Risks to community health and safety due to the transport, storage, and use and/or disposal of materials such as explosives, fuel and other chemicals during construction and operation?   |     | ✓  | Likelihood of such risks and hazards is low as per the scope of the project.   |
| Community safety risks due to both accidental and natural causes, especially where the structural elements or components of the project are accessible to members of the affected community or where their failure could result in injury to the community throughout project construction, operation and decommissioning? | ✓   |    | To avoid unfortunate events, site safety should be implemented in true spirit in the form of signages, reflective tapes awareness boards by the contractors and so on.   |
| Any impact on sensitive receptors (mentioned above)  |     | ✓  | No significant impact is anticipated during execution phase. However, water sprinkling would be ensured to tackle the suspended dust particles.  |
| Any impact of negative nature on already existing infrastructure including public amenities  | ✓   |    | There is no major significant impact expected to any public infrastructure owing to project activities except the only weigh station that covers some of the road portion. Moreover, minor encroached areas might be affected during construction of storm water drain and affected persons (APs) will be compensated for that through ARAP. In addition, access to business would be temporarily disturbed; already informed during public consultation phase. In the long run, this project is in the favor of local community and they are willing to cooperate and wanted MC to get this project completed in a timely manner. |

**Prepared By:**

**Name:** Haider Ali

**Designation :** Consultant

**Signature:**



**Date:** 16-11-2022

**Reviewed By:**

**Name:** Asif Gillani

**Designation** DPO PMDFC

**Signature:**

**Date:**

**Endorsed By:**

**Name:**

**Designation** MOI&S

**Signature:**

**Date:**

## INVOLUNTARY RESETTLEMENT SCREENING CHECKLIST

**Name of City/MC/LG:** MC Gojra

ESFP: Asad MOP

**Sub-Project Sector:** Roads

**Sub-Project Title:** Rehabilitation of Gojra-Toba Road

**Sub- Project Categorization:** S-1  S-2  S-3

**Date of Screening:** 16 -11-2022

| SECTION I   | Yes | No | Expected | Remarks  |
|---|-----|----|----------|--|
| Does the project require land acquisition? Yes/No   | ✓   |    |          | Land acquisition is required for this project. Ramps and footsteps are found within RoW and to be dismantle. One weight station owned by MC but further on lease which will not be dismantled or shifted rather design change will cover that portion with tuff pavements. |
| If yes, then describe the type of land being acquired from the categories below:              |     |    |          |  |
| Has any AED been conducted at the proposed location by the government? Yes/No                 |     | ✓  |          | No AED has been conducted at the proposed project location by MC and it was confirmed during public consultation   |
| Land (Quantify and describe types of land being acquired in “remarks column”).                |     | ✓  |          | Not applicable   |
| Government and LG owned land free of occupation (agriculture or settlement)                   |     | ✓  |          | Sub-project site under possession of MC and free from all sort of settlements. Shops for commercial activities over there also belong to MC Gojra.   |
| Government or state-owned land (other than LG) free of occupation (agriculture or settlement) |     | ✓  |          |  |
| Private land  |     | ✓  |          |  |
| Residential   |     | ✓  |          |  |
| Commercial  |     | ✓  |          |  |
| Agricultural  |     | ✓  |          |  |
| Communal  |     | ✓  |          |  |
| Others (specify in “remarks”).  |     | ✓  |          |  |
| Name of owner/owners and type of ownership document if available.                             |     | ✓  |          | MC Gojra owns the land for Sub-Project.  |
| If land is being acquired, describe any structures constructed on it                          |     | ✓  |          | Ramps and footsteps are found within RoW and to be dismantle for which   |

| SECTION I  | Yes | No | Expected | Remarks  |
|--|-----|----|----------|--|
|  |     |    |          | ARAP will be developed to compensate the loss of structure   |
| Land-based assets:   |     |    |          | Not Applicable   |
| Residential structures   |     | ✓  |          |  |
| Commercial structures (specify in "remarks")                         |     | ✓  |          |  |
| Community structures (specify in "remarks")                          |     | ✓  |          |  |
| Agriculture structures (specify in "remarks")                        |     | ✓  |          |  |
| Public utilities (specify in "remarks")                              |     | ✓  |          | Ramps and footsteps are found within RoW and to be dismantled  |
| Others (specify in "remarks")  |     | ✓  |          | Not applicable   |
| If agricultural land is being acquired, specify the following:       |     |    |          | The proposed project site is a commercial zone and belongs to MC Gojra. Hence, no agriculture land is required under sub-project.  |
| Agriculture related impacts  |     | ✓  |          | Not Applicable   |
| Crops and vegetables (specify types and cropping area in "remarks"). |     | ✓  |          |  |
| Trees (specify number and types in "remarks").                       |     | ✓  |          |  |
| Others (specify in "remarks").                                       |     | ✓  |          |  |
| Affected Persons (APs)   |     |    | ✓        | No significant impact to APs. Only encroached footsteps and cemented structure need to be dismantled owing to project activity, which will be compensated through ARAP before start of civil work. |
| Will any people be displaced from the land when acquired? Yes/No     |     | ✓  |          | Not Applicable   |
| Number of APs  |     | ✓  |          |  |
| Males  |     | ✓  |          |  |
| Females  |     | ✓  |          |  |
| Titled landowners  |     | ✓  |          |  |
| Tenants and sharecroppers  |     | ✓  |          |  |
| Leaseholders   |     | ✓  |          |  |
| Agriculture wage laborers  |     | ✓  |          |  |
| Encroachers and squatters (specify in remarks column)                |     |    | ✓        | No squatters observed. Encroached structures would be compensated. Displayed portable items outside the shops can be moved and for that no compensation is required. This aspect has been          |

| SECTION I   | Yes | No | Expected | Remarks  |
|---|-----|----|----------|--|
|   |     |    |          | discussed during public consultation phase.  |
| Vulnerable APs (e.g. women headed households, minors and aged, orphans, disabled persons, and those below the poverty line). Specify the number and vulnerability in “remarks”. |     | ✓  |          | No vulnerable APs identified.  |
| Others (specify in “remarks”)   |     | ✓  |          | Not applicable   |
| How will people be affected?  |     |    | ✓        | Construction of storm water drain can temporarily disturb the business activities. This aspect has been covered and communicated to the public during public consultation phase and mitigation provided in the ESMP. |

<sup>1</sup> The sub-projects have to avoid all locations where any government led AED has been conducted.

**Prepared By:**

**Name:** Haider Ali

**Designation:** Consultant

**Signature:**

**Date:** 16-11-2022



**Reviewed By:**

**Name:**

**Designation:** DPO ESM

**Signature:**

**Date:**

**Endorsed By:**




**Name:**

**Designation:** MOP


**Signature:**

**Date:**


## Pictures of Project Siting











ترقیاتی منصوبوں کی تعمیر و مرمت  
کے دوران کام کرنے والے مزدوروں / ورکرز  
(بشمول خواتین لیبر / ورکرز) کی صحت، حفاظت  
اور ماحول کے لئے معیاری اصول و ضوابط



# حق اشاعت

جملہ حقوق محفوظ ہیں۔

اس اشاعت کا کوئی بھی حصہ پی ایم ڈی ایف سی (PMDFC) کی پیشگی اجازت کے بغیر کسی بھی شکل میں الیکٹرانکس، مکینیکل، فوٹوکاپی، ریکارڈنگ یا کسی اور طرح سے دوبارہ بنایا یا منتقل نہیں کیا جاسکتا۔



## پیش لفظ

لوکل گورنمنٹ اینڈ کمیونٹی ڈویلپمنٹ ڈیپارٹمنٹ اور پنجاب میونسپل ڈویلپمنٹ فنڈ کمپنی (PMDFC) نے ورلڈ بینک کے اشتراک سے پنجاب سٹیٹس پروگرام (PCP) کا کامیابی سے اجرا کر دیا ہے۔ اس منصوبے کے تحت صوبہ پنجاب کے 16 چھوٹے شہروں (MCs) بشمول بہاولنگر، بورویالا، خانیوال، کوٹ ادو، وہاڑی، گوجرہ، جھنگ، کمالیہ، اوکاڑا، ڈسکہ، حافظ آباد، جہلم، کاموکی، مرید کی، اور میانوالی کی ترقیاتی کاموں پر کامیابی سے کام جاری ہے۔ ان ترقیاتی منصوبوں میں ویسٹ مینجمنٹ، پانی کی فراہمی، نکاسی آب اور سڑکوں کی مرمت، کمیونٹی پارکس کی بحالی اور قدرتی آفات کی روک تھام کے منصوبہ جات شامل ہیں۔

پنجاب سٹیٹس پروگرام (PCP) کے منصوبہ جات کی تکمیل کے دوران سماجی اور ماحولیاتی مسائل کی جانچ پڑتال اور اس کے حل کے لئے انوائرنمنٹل اینڈ سوشل سیف گارڈز (ESSs) ٹیم نے انوائرنمنٹل اینڈ سوشل مینجمنٹ فریم ورک (ESMF) بنایا ہے۔ مختلف منصوبہ جات اسی فریم ورک کی رو سے پایہ تکمیل تک پہنچ رہے ہیں۔

تعمیراتی اور ترقیاتی کاموں کی تکمیل میں تعمیراتی جگہوں پر کام کرنے والے مزدوروں (بشمول خواتین) کی صحت اور کام کرنے کے دوران حفاظت بہت اہمیت رکھتی ہے۔ اس اہم مسئلہ کو ملحوظ خاطر رکھتے ہوئے، پی ایم ڈی ایف سی کے زیر اہتمام پنجاب سٹیٹس پروگرام کی انوائرنمنٹ اینڈ سوشل مینجمنٹ ٹیم نے "ترقیاتی منصوبوں کی تعمیر و مرمت کے دوران کام کرنے والے مزدوروں، ورکرز (بشمول خواتین لیبر ورکرز) کی صحت، حفاظت اور ماحول کیلئے بنیادی اصول و ضوابط" مرتب کیے ہیں تاکہ متعلقہ میونسپل کمیٹیز/کارپوریشنز (MCs) کے عہدیداران اور ٹھیکیداران کو آگاہی فراہم کی جائے۔



## اغراض و مقاصد

۱۔ مجوزہ معیاری اصول و ضوابط پنجاب سیٹیز پروگرام (PCP) کے تحت پنجاب میونسپل ڈویلپمنٹ فنڈ کمپنی (PMDFC) کے ماہرین ماحولیات نے پروگرام ڈائریکٹر (PCP) اور ڈپٹی پروگرام ڈائریکٹر (PCP) کی زیر نگرانی تشکیل دیئے ہیں۔

۲۔ شہری ترقی کے ترقیاتی منصوبہ جات کی تعمیر و مرمت میں مزدور ورکرز بنیادی کردار ادا کرتے ہیں۔ ان (SOPs) کا بنیادی مقصد مزدور ورکرز (بشمول خواتین لیبر ورکرز) کو تعمیراتی جگہوں (Construction sites) اور لیبر کیمپس میں ماحولیاتی اور سماجی تحفظ فراہم کرنا اور صحت، ماحولیات اور کسی خطرناک صورتحال سے بچنے کے لئے حفاظت فراہم کرنا ہے۔

۳۔ یہ SOPs (PCP) پنجاب سیٹیز پروگرام کے تحت 16 شہروں کی میونسپل کمیٹیز/کارپوریشنز میں تعمیر و مرمت کے تمام پراجیکٹس پر لاگو ہوں گے۔

۴۔ یہ SOPs مزدوروں/کام کرنے والوں/دیہاڑی دار (بشمول خواتین) پر بلا تخصیص لاگو ہوں گے۔

۵۔ ان SOPs کو موثر اور یقینی بنانے کے لئے انھیں ٹھکیداروں کے کنٹریکٹ کا حصہ بنانا اور ان پر عمل درآمد کرنا میونسپل کمیٹیز/کارپوریشنز کی ذمہ داری ہے۔ جسے پی ایم ڈی ایف سی کی متعلقہ پروگرام ٹیم یقینی بنائے گی۔



## پیغام



پاکستان کی ترقی میں تعمیراتی کاموں کے دوران کام کرنے والا مزدور طبقہ نہایت اہمیت کا حامل ہے اور انکے صحت و تندرستی سے متعلق مسائل کا مؤثر حل انتہائی ضروری ہے۔ "ترقیاتی منصوبوں کی تعمیر و مرمت کے دوران کام کرنے والے مزدوروں / ورکرز (بشمول خواتین لیبر ورکرز) کی صحت، حفاظت اور ماحول کیلئے بنیادی اصول و ضوابط" کی اشاعت و

ترویج اور ان پر بروقت عمل درآمد بے حد ضروری ہے جس سے اس طبقے کے بنیادی حقوق کا تحفظ یقینی بنایا جاسکے گا اور اس طرح اس طبقے کی کارکردگی میں بھی بہتری نظر آئے گی۔ ان اصولوں کے تحت ہر ٹھیکیدار کو ورکرز کی صحت اور حفاظت کی ذمہ داری دی گئی ہے۔ مزدور تعمیراتی کاموں کے دوران خطرات کے مطابق ذاتی حفاظتی سامان بھی استعمال کریں گے جس سے دوران کام حادثات میں بھی نمایاں کمی نظر آئے گی۔ ماحولیات اور صحت کے اصولوں کو مد نظر رکھتے ہوئے ہر سطح پر ہم اس بات کو یقینی بنانے کی کوشش کریں گے کہ ہماری پالیسیاں اور طرز عمل فعال ہوں۔ ماحولیات، صحت اور حفاظت (EHS) کے اصولوں کو اپنانے میں کسی بھی قسم کا سمجھوتہ نہیں کیا جائے گا۔ میں امید کرتا ہوں کہ ان اصول و ضوابط کی روشنی میں مزدور / ورکرز (بشمول خواتین لیبر) کے حقوق کی پاسداری کو ایک نیا رخ ملے گا اور حکومتی عہدیداران اور ٹھیکیداران بھی اپنی ذمہ داریوں کا احساس کریں گے۔ اور اس سلسلے میں پی ایم ڈی ایف سی اور پنجاب سیٹییز پروگرام کی انوائرنمنٹ اینڈ سوشل سیف گارڈز (ESSs) ٹیم بلاشبہ مبارکباد کی مستحق ہے اور یہ توقع کی جاسکتی ہے کہ وہ مستقبل میں ان قواعد و ضوابط کی نگرانی کے لئے بھرپور اقدامات کریں گے۔

محمد عامر نذیر

پروگرام ڈائریکٹر  
پنجاب سیٹییز پروگرام (PCP)



## زیر نگرانی

### عاشق چوہدری

سینئر پروگرام آفیسر (انفراسٹرکچر)  
پنجاب سیٹیز پروگرام (PCP)

### افتخار رسول

ڈپٹی پروگرام ڈائریکٹر  
پنجاب سیٹیز پروگرام (PCP)

## تکنیکی ٹیم

### رضوانہ انجم

پروگرام آفیسر (انوائرنمنٹ اینڈ سوشل سیف گارڈز)  
پنجاب سیٹیز پروگرام (PCP)

### کنز می ندیم

ریسرچ اینالسٹ  
پنجاب سیٹیز پروگرام (PCP)

### تہمینہ کرن

ڈپٹی پروگرام آفیسر (ESSs)  
پنجاب سیٹیز پروگرام (PCP)





# (۱) لیبر کیمپس کے لئے معیاری اصول و ضوابط

## سرگرمیاں

۱. مزدور / لیبر کیلئے عارضی کیمپ / رہائش گاہ کے انتظام و قیام کے لئے جگہ کا انتخاب

## مسائل

- ◆ مقامی آبادی کے وسائل پر اضافی بوجھ
- ◆ مقامی آبادی سے تنازعات کا خدشہ
- ◆ سماجی، مذہبی، اور سیورٹی کے مسائل۔

## حفاظتی اقدامات

تھیکیدار لیبر کیمپس کے قیام کے وقت مندرجہ ذیل باتوں کا خیال رکھے گا :

- ◆ کیمپس ایسی جگہوں پر لگائے جائیں جو ماحولیاتی، مذہبی، سماجی اور ثقافتی نقطہ نظر سے قابل قبول ہوں۔
- ◆ مقامی آبادی کے ساتھ کسی تنازعہ سے بچنے کے لئے آبادی سے دور جگہ کا انتخاب کیا جائے
- ◆ لیبر کیمپ کی جگہ اور سہولیات سے متعلق ایک تفصیلی نقشہ تیار کر کے متعلقہ میونسپل کمیٹی / کارپوریشن میں جمع کرایا جائے۔
- ◆ دیگر مقامی ادارے جیسے صحت، سیورٹی وغیرہ کو لیبر کیمپ کے مقام اور مدت کے بارے میں مطلع کیا جائے تاکہ کسی ناگہانی صورتحال سے بچا جاسکے۔
- ◆ لیبر کیمپس کے قیام کیلئے عارضی جگہ زمین کا حصول زمین کے مالک کی مرضی، طے کردہ کرایہ اور باقاعدہ تحریری معاہدے کی صورت میں کیا جائے۔
- ◆ لیبر کیمپس سے ملحقہ بنیادی سہولتوں جیسے پینے کا پانی اور نکاسی آب کے انتظامات سے ماحولیاتی آلودگی میں اضافہ نہ ہو





## سرگرمیاں

۲. لیبر کیمپ میں مہیا کی جانے والی سہولیات

## مسائل

- ◆ مناسب انفراسٹرکچر کی کمی
- ◆ بنیادی ضروریات اور سہولیات جیسے پانی اور بجلی کی فراہمی، صفائی ستھرائی کی سہولیات اور نکاسی آب کی فراہمی

## حفاظتی اقدامات

تھیکیدار کیمپ سائٹس پر درج ذیل باتوں کا خیال رکھے گا:

- ◆ ہوادار اور صاف ستھری رہائش گاہ
- ◆ عارضی کمروں کیلئے ایسے میٹریل کا استعمال جو جلد آگ نہ پکڑیں۔
- ◆ نہانے، دھونے اور پانی پینے کیلئے صاف اور مناسب پانی کی فراہمی۔
- ◆ تمام مزدوروں کیلئے مناسب جگہ کی موجودگی اور محفوظ ماحولیاتی معیار۔
- ◆ صاف ستھرے واش رومز اور نکاسی آب کا مناسب انتظام۔
- ◆ خواتین لیبر کیلئے پردے اور پرائیویسی کا انتظام اور الگ کمروں کا قیام مزید براں خواتین لیبر کی موجودگی کی صورت میں اُنکے لیے علیحدہ ٹوائلٹس رومز کا انتظام۔
- ◆ بین الاقوامی معیار کے مطابق ہر دس افراد کیلئے مطلوبہ ٹوائلٹ کی سہولت کی تعداد ایک ہے۔
- ◆ اگر لیبر کیمپ طویل مدت کیلئے لگایا جانا ہو تو بارشوں، سیلاب کے پانی سے بچنے کیلئے مناسب انتظامات کا ہونا اور نکاسی آب کی فراہمی بے حد ضروری ہے۔
- ◆ ٹوائلٹس اور عارضی رہائش گاہوں میں بجلی کی فراہمی کو یقینی بنایا جائے۔

## سرگرمیاں

۳. لیبر کیمپ سے پیدا ہونے والا سالڈ اور لیکوئڈ ویسٹ

## مسائل

- ◆ تغفن اور بدبو
- ◆ صحت کے لئے نقصان
- ◆ ماحولیات کے لئے نقصان
- ◆ مقامی آبادی کے لئے نقصان
- ◆ بیماریاں پیدا کرنے والے بیکٹیریا اور مچھروں کا ذریعہ





## حفاظتی اقدامات

- ◆ روزمرہ پیدا ہونے والے کوڑا کرکٹ اور چکن کے کوڑا کرکٹ کے لیے الگ الگ کوڑا دانوں کا انتظام
- ◆ میونسپل کمیٹی رکارپوریشن کی جانب سے منتخب کردہ جگہ پر روزانہ کی بنیاد پر کوڑے کو اٹھانے اور تلف کرنے کا مناسب انتظام۔
- ◆ عارضی ٹوائلٹس سے پیدا شدہ فضلے اور لیکویڈ ویسٹ کو حفظان صحت کے اصولوں کے مطابق ٹھکانے لگانے کا انتظام۔
- ◆ فضلے کو ٹھکانے لگانے کے لیے رہائش گاہ سے کم از کم 500 میٹر دور جگہ کا انتخاب کیا جائے جس کے ارد گرد لوگوں کی رہائش نہ ہو۔
- ◆ عارضی ٹوائلٹس سے پیدا شدہ فضلے کو ٹھکانے لگانے کے لیے منتخب کردہ جگہ کے ارد گرد باڑا لگائی جائے یا درخت لگا دے جائیں تاکہ بچے اور دیگر رہائشی داخل نہ ہوں اور چھرا اور بدبو بھی پیدا نہ ہو۔

## سرگرمیاں

۴. کھانا پکانے کے لیے ایندھن کی فراہمی

## مسائل

- ◆ گیس اور دیگر ایندھن سے چلنے والے چولہوں کے پھٹنے کا اندیشہ
- ◆ ایندھن کے لیے لکڑی کے حصول کے لیے درختوں کی کٹائی

## حفاظتی اقدامات

ٹھیکیدار کیمپ سائٹس پر درج ذیل سہولیات مہیا کرے گا۔

- ◆ لیبر کیمپس میں کھانا پکانے، کمروں کے گرم رکھنے نیز سردیوں میں نہانے اور دھونے کے لیے گرم پانی کے لیے ایندھن کی لکڑی یا دیگر بائیو گیس استعمال کرنے کی حوصلہ شکنی کریں اور ایندھن کیلئے درختوں کی کٹائی نہ کریں۔
- ◆ درختوں اور ارد گرد جنگلات کی حفاظت کیلئے مزدوروں/لیبر کو آگاہی دی جائے۔
- ◆ کھانا پکانے کے لیے قدرتی گیس یا مٹی کے تیل کے محفوظ چولہے استعمال کیے جائیں۔







## سرگرمیاں

۵۔ جانوروں / پرندوں کا شکار خرید و فروخت

## مسائل

- ◆ جنگلی حیات کو خطرات
- ◆ ماحولیاتی وسائل کو خطرات

## حفاظتی اقدامات

◆ لیبر / مزدوروں کو گاہی فراہم کی جائے کیونکہ ارد گرد موجود کسی بھی قسم کی جنگلی حیات کو نقصان پہنچانا ، ان کے گھونسلوں / پناہ گاہوں میں کوئی مداخلت کرنا، شکار کرنا یا جانوروں / پرندوں کو قید کرنا اور خرید و فروخت کرنا، پنجاب وائلڈ لائف (پروٹیکشن، پریزرویشن، کنزرویشن اینڈ مینجمنٹ ایکٹ 1974) کے مطابق ممنوع اور سزا قابل تعزیر جرم ہے۔

## سرگرمیاں

۶۔ حفظانِ صحت کے اصول

## مسائل

◆ حفظانِ صحت کے رہنما اصولوں پر عملدرآمد کرنے کی صورت میں مختلف بیماریاں مثلاً کرونا وائرس، ملیئرہ اور ایچ آئی وی ایڈز اور دیگر انفیکشنز کے پھیلنے کا خطرہ کم ہوگا۔



## حفاظتی اقدامات

تھیکیدار لیبر کیمپس میں درج ذیل انتظامات مہیا کرے گا:

- ◆ لیبر کیمپس میں صحت و صفائی کی مناسب سہولیات کی فراہمی
- ◆ بیرونی علاقوں سے آنے والے مزدوروں کی صحت کی ابتدائی سکریننگ

- ◆ چوبیس گھنٹے لیبر کیمپس میں پرفرسٹ ایڈیکس کی سہولت موجود ہو۔ کیمپ سائنس میں ابتدائی طبی امداد سے متعلقہ دواؤں کا موجود ہونا یقینی بنایا جائے۔ اور طویل المدتی کیمپ کی صورت میں کسی ڈسپنسر رڈاکٹر کیمپ میں موجود ہونا چاہئے۔
- ◆ کسی ایمرجنسی کے دوران مزدوروں کے لیے ایمرجنسی کی سہولت فراہم کی جائے اور ایمرجنسی سروسز 1122 یا 15 پر کال کرنے کے لیے ٹیلیفون رموبال کی سہولت مہیا کی جائے۔
- ◆ حفظانِ صحت کے بہترین اصولوں، صفائی ستھرائی اور صحت کی دیکھ بھال کے امور کیلئے مزدوروں/لیبر کو تربیت فراہم کی جائے جس میں تمام مزدوروں کی شرکت کو یقینی بنایا جائے۔
- ◆ جنسی طور پر منتقل ہونے والی بیماریوں اور ایڈز وغیرہ کے بارے میں مزدوروں کو مکمل معلومات فراہم کی جائیں اور ان بیماریوں سے بچنے کے لیے حفاظتی اصول اپنانے پر زور دیا جائے۔
- ◆ چھڑوں اور دیگر بیکٹیریا کو پیدا ہونے سے روکنے کیلئے حفاظتی سپرے لازمی کرائے جائیں۔
- ◆ کرونا سے بچنے کے لیے ابتدائی سکریننگ یقینی بنائیں اور بار بار ہاتھ دھونے پر زور دیں اور علامات ظاہر ہونے پر فوری طور پر دیگر مزدوروں سے آئسولیشن کے مکمل اصولوں پر سختی سے عمل کیا جائے۔
- ◆ لیبر کیمپس کے اندر مناسب مقامات پر حفظانِ صحت کے اصولوں سے متعلقہ پیغامات اور طریقے ڈسپلے کیے جائیں اور تربیتی پروگرام کا اہتمام کیا جائے۔
- ◆ قریبی ڈسپینسری/ہیلتھ کلینک/ہسپتال کے رابطہ نمبر وغیرہ واضح مقامات پر آویزاں کئے جائیں۔





## سرگرمیاں

۷. سکیورٹی اور حفاظت کی سہولیات

## مسائل

- ◆ سکیورٹی کے مسائل
- ◆ چوری کا خطرہ
- ◆ دہشت گردی کا خطرہ
- ◆ آگ لگنے کے خطرات

## حفاظتی اقدامات

- ◆ کیپ کے گرد حفاظتی باڑی فراہمی
- ◆ حفاظتی اہلکار (پولیس یا نجی سکیورٹی گارڈز / ہوم گارڈ وغیرہ) کی تعیناتی
- ◆ کیپ میں موجود افراد کی صحیح تعداد اور آمدورفت کا حساب کتاب رکھنے کے لیے رجسٹر میں اندراج۔
- ◆ آگ سے بچاؤ کے لیے لیبر کیپ بنانے میں ایسا کوئی میٹریل استعمال نہ کیا جائے جس سے آگ لگنے کا اندیشہ ہو۔
- ◆ بارش، طوفان، سیلاب وغیرہ سے بچنے کیلئے اس بات کو یقینی بنایا جائے کہ کیپ سائٹ اور عارضی کمرے / ہائٹس گاہیں محفوظ رہیں۔
- ◆ لیبر کیپس میں آگ بجھانے والی آلات موجود ہوں جن پر انکی آخری معیاد کی تاریخ درج ہو۔ اور سکیورٹی گارڈ یا لیبر وغیرہ میں سے نمایاں افراد کو آگ بجھانے والے آلہ استعمال کرنے کی تربیت دی جائے۔
- ◆ لیبر کیپ میں واضح مقامات پر ہنگامی ایمر جنسی رابطہ نمبر نمایاں درج ہوں۔
- ◆ ٹھیکیدار، لیبر کے ساتھ ماہانہ میٹنگز میں ایمر جنسی کی صورت میں ہر ایک مزدور کو اسکی ذمہ داریوں اور تربیت سے آگاہ کرے اور اسکی تفصیلات کنسلٹنٹ اور میونسپل کمیٹی رکارڈز پر اپڈیشن کو فراہم کرے۔ اور کسی بھی قسم کی شکایات ایک رجسٹر میں درج کرے۔









## سرگرمیاں


10. تعمیراتی کام ختم ہونے کے بعد کی ذمہ داریاں


## مسائل

◆ فالتو سامان اور کوڑا کرکٹ کی گندگی

## حفاظتی اقدامات

- ◆ کیپ سائٹ کو اصل حالت میں بحال کیا جائے۔
- ◆ تعمیراتی کام کے مکمل ہونے پر فریم اور باڈ لگنے والے دروازوں سمیت لیبر کیپ میں قائم تمام سہولیات کو ایسے ختم کیا جائے کہ وہاں کا کوئی کام نہ رہے۔
- ◆ کام کم ہونے کے ساتھ لیبر کیپ کو مرحلہ وار ختم کیا جائے (پورے کام کی تکمیل کا انتظار نہ کریں)
- ◆ لیبر کیپ کو مسما کرنے کے دوران شور اور کسی بھی قسم کی آلودگی مثلاً گرد و غبار، آبی آلودگی وغیرہ پھیلانے سے گریز کریں۔
- ◆ مسما شدہ ملبہ کو دوبارہ استعمال کرنے اور دوبارہ قابل استعمال کرنے کیلئے کسی لوکل ڈیلر/ٹھیکیدار کی خدمات حاصل کریں۔
- ◆ کوڑا کرکٹ اور دوبارہ ناقابل استعمال سامان کو متعلقہ میونسپل کمیٹی/کارپوریشن کی جانب سے مقرر کردہ مقام پر مناسب طریقے سے تلف کیا جائے۔
- ◆ لیبر کیپ کی زمین رجگہ کے مالک کے ساتھ طے شدہ معاہدے کے مطابق کام کریں اور کسی بھی قسم کے اختلاف یا جھگڑے سے گریز کریں۔
- ◆ جگہ کو متفقہ منصوبہ کے مطابق اسکے حوالے کیا جائے۔
- ◆ لیبر مزدوروں سے آئندہ کام یا مراعات کے چھوٹے وعدے ہرگز نہ کیے جائیں۔





## سرگرمیاں

۱. تمام قسم کے تعمیراتی سرگرمیاں اور کام

## مسائل

- ◆ انجریز اور چوٹیں وغیرہ
- ◆ نامناسب دیکھ بھال اور بروقت امداد نہ ملنے کی باعث ہلاکت
- ◆ دہشت گردی اور سیوریٹی سے متعلق خطرات

## حفاظتی اقدامات

- ◆ تمام مزدوروں / لیبر سے مقامی / بین الاقوامی معیار کے مطابق مناسب حفاظتی اور قانونی ضوابط کی پیروی کروائی جائے۔
- ◆ کام کی جگہ پر ارد گرد کے علاقوں میں موجود دہشت گردی اور سیوریٹی کے خطرات کے مطابق حکمت عملی کی بروقت تیاری اور ایک محفوظ و صحت مند ماحول مہیا کیا جائے۔
- ◆ مزدوروں / لیبر کیلئے ذاتی حفاظت کے سامان (PPEs) کی فراہمی مثلاً حفاظتی جوتے، ہیلیمٹ، ماسک، دستانے، حفاظتی لباس، چشمے، چہرے اور کان کی حفاظت کے سامان وغیرہ کی فراہمی
- ◆ تمام مزدوروں / لیبر کو ذاتی حفاظت کے ساز و سامان کے بارے میں مکمل آگاہی اور استعمال کے طریقے کار کے بارے میں تربیت کا انتظام۔
- ◆ اگر تعمیراتی کام ایک ماہ سے زائد عرصہ کیلئے جاری رہنا ہو تو تمام مدت کے لیے صحت، صفائی اور تربیت یافتہ ماحولیات کی تعیناتی کی جائے جو مزدوروں کی صحت، صفائی اور ماحولیات کے امور کی نگرانی کرے اور انہیں تربیت و آگاہی فراہم کرے۔
- ◆ تعمیراتی کاموں کے دوران کسی چوٹ لگنے / انجریز کی صورت میں مزدور / لیبر کے علاج معالجے کی سہولت مہیا کرنا اور بروقت ہسپتال / ڈسپنسری وغیرہ پہنچانا ٹھیکیدار کی ذمہ داری ہے۔
- ◆ مزید برآں دوران تعمیراتی کام کی وجہ سے لگنے والی چوٹ / انجریز کے نتیجے میں ہلاکت ہو جانے کی وجہ سے مزدور / لیبر کی انشورنس اور اس کی بروقت ادائیگی کو یقینی بنایا جائے۔
- ◆ ایمرجنسی رابطہ نمبر مثلاً ریسکیو 1122 یا 15 اور دیگر قریبی ہسپتالوں / ڈسپنسری وغیرہ کے نمبر تعمیراتی جگہوں پر واضح درج ہونے چاہیں اور کال کی سہولت فراہم کی جائے۔
- ◆ شہری ترقی کے تعمیراتی منصوبہ جات کے آغاز سے قبل صحت، مذہبی امور اور شہری تحفظ / سیوریٹی فراہم کرنے والے مقامی اداروں کو آگاہ رکھا جائے اور اس سلسلے میں متعلقہ میونسپل کمیٹی / رکارپوریشن کے تعاون سے موثر حکمت عملی تشکیل دی جائے۔



## سرگرمیاں


۲. تمام قسم کی تعمیراتی سرگرمیاں اور کنسٹرکشن کے کام

## مسائل

- ◆ 15 سال سے کم عمر بچوں کی صحت اور تعلیم کا نقصان
- ◆ 18 سال اور اس سے کم عمر بچوں کی صحت کا نقصان
- ◆ حاملہ مزدور عورتوں کی صحت سے متعلقہ خطرات

## حفاظتی اقدامات

- ◆ دی پنجاب رسٹرکشن آن ایمپلائمنٹ آف چلڈرن ایکٹ 2016 کے مطابق 15 سال سے کم عمر بچوں کو مزدوری یا کسی سرگرمی کے لیے کام پر نہیں رکھا جاسکتا۔
- ◆ ویسٹ پاکستان میٹرنٹی بانیٹ آرڈیننس 1958 کے مطابق حاملہ خواتین یا ایسی خواتین جنہوں نے چھ ہفتے قبل بچے کو جنم دیا ہو، کو مزدوری یا کسی سرگرمی کے لیے کام پر نہیں رکھا جاسکتا۔
- ◆ دی پنجاب رسٹرکشن آن ایمپلائمنٹ آف چلڈرن ایکٹ 2016 کے مطابق 18 سال اور اس سے کم عمر کے بچوں کو محنت مزدوری کے ایسے کام کے لیے نہیں رکھا جاسکتا جن میں صحت کو نقصان پہنچنے یا چوٹ لگنے یا کسی کیمیائی زہریلے مادے سے نقصان پہنچنے یا جہاں ہڈی ٹوٹنے کا اندیشہ ہو۔





## سرگرمیاں

۳. دوران تعمیر حادثات کا پیش آنا

## مسائل

◆ فوری طبی امداد کی کمی

◆ اردگرد کے علاقوں میں ابتدائی طبی سہولیات اور صحت عامہ کا فقدان

## حفاظتی اقدامات


◆ تعمیراتی جگہ پر فرسٹ ایڈ باکس کی موجودگی کہ یقینی بنایا جائے اور فرسٹ ایڈ باکس میں تمام ضروری ادویات اور طبی امداد کا ضروری سامان موجود ہو۔

◆ تعمیراتی کاموں کے دوران پیش آنے والے حادثات بیمار یوں اور واقعات کا مکمل ریکارڈ رکھا جائے۔ اسی طرح حادثات کی نوعیت و وجوہات کا مکمل ریکارڈ موجود ہو۔


◆ مزدوروں کی صحت و سیورٹی سے متعلق ممکنہ خطرات کی بروقت نشاندہی کی جائے خاص کر وہ خطرات جو جان لیوا ثابت ہو سکتے ہیں۔ اور ضروری حفاظتی اقدامات بروقت کئے جائیں۔

◆ تعمیراتی کاموں سے متعلق مشینری چلانے والے ڈرائیوروں کو دوران ڈرائیونگ قواعد و ضوابط پر سختی سے عملدرآمد کرانے کے لئے آگاہی فراہم کی جائے۔

◆ تعمیراتی علاقوں اور سڑکوں کے ساتھ ساتھ روشنی کا معقول انتظام ہو۔







## سرگرمیاں

۴. تعمیراتی مقامات پر پانی اور صفائی ستھرائی کی سہولیات اور سالڈ ویسٹ مینجمنٹ

## مسائل

- ♦ صحت کو خطرہ
- ♦ ارد گرد علاقے کے لوگوں کے لئے ناگواری کا باعث
- ♦ چھردوں اور دیگر بیکٹیریا کی افزائش نسل کا ذریعہ


## حفاظتی اقدامات

- ♦ تعمیراتی جگہوں پر تمام مزدوروں کے لئے پینے کے لئے صاف ستھرا پانی مہیا کیا جائے۔
- ♦ اگر تقریباً 25 مزدور ایک مہینہ کے لئے سارا دن کام کر رہے ہوں تو ان کے لئے تعمیراتی جگہوں پر پورٹ ایبل ٹوائلٹ کا انتظام کیا جائے جو مقامی ڈرنیج سسٹم سے ملحق ہوں اور مقامی ڈرنیج سسٹم کی غیر موجودگی میں مقامی ندی نالوں وغیرہ سے کم از کم 6 میٹر کے فاصلے پر ہوں۔ مزید برآں پورٹ ایبل ٹوائلٹس کی صفائی ستھرائی کو روزانہ کی بنیاد پر یقینی بنایا جائے۔
- ♦ تعمیراتی کاموں کے دوران کھدائی سے حاصل شدہ گارا، مٹی، ریت، کنکریٹ وغیرہ کو تعمیراتی جگہ پر ایک دن سے زائد مدت کے لئے کھلانا نہ دیا جائے۔ اور روزانہ کی بنیاد پر متعلقہ میونسپل کمیٹی رکارڈ پر پوریشن کی جانب سے مقرر کردہ جگہ پر مناسب طریقے سے ٹھکانے لگایا جائے۔

پی ایم ڈی ایف سی

۱۷

انوائٹمنٹ اینڈ سوشل سیف گارڈز



# COVID-19

CORONAVIRUS DISEASE 2019


## سرگرمیاں

کرونا وائرس کی وبا کے دوران حفاظتی تدابیر

## حفاظتی اقدامات

گورنمنٹ آف پنجاب اور ورلڈ بینک کی ہدایات کے مطابق کرونا کی وبا کے دوران درج ذیل حفاظتی اقدامات کی پابندی کروانا کنٹریکٹر کی ذمہ داری ہے:

- ◆ کرونا وائرس کی وبا کے دنوں میں کنسٹرکشن سائٹ پر ہاتھ دھونے کیلئے پانی (پورٹ ایبل ہینڈ واشنگ کی سہولت) اور صابن مہیا کیا جائے اور لیبر کو بار بار صابن سے ہاتھ دھونے کی تلقین کی جائے۔
- ◆ لیبر کیمپس میں اور کنسٹرکشن سائٹ پر سوشل ڈسٹینسنگ (6m کا فاصلہ) کے اصولوں کو مدنظر رکھا جائے۔
- ◆ کرونا وائرس کی وبا کے دوران اس بات کا خاص خیال رکھا جائے کہ اگر کنسٹرکشن سائٹ پر آبادی میں وبا پھیلی ہوئی ہے تو آبادی اور مقامی لوگوں سے دور رہیں اور کسی قسم کا میل جول نہ رکھیں۔ اسی طرح اگر کوئی مزدور وبا کے علاقے سے روزانہ کی بنیاد پر آ رہا ہے تو اسے باقی لوگوں/مزدوروں سے میل جول سے دور رکھا جائے۔
- ◆ اگر کسی مریض میں وائرس کی علامات (خشک کھانسی، نزلہ، زکام، بخار وغیرہ) پائی جائیں تو اسے فوراً دوسرے مزدوروں سے آئسولیٹ کر دیا جائے اور ٹیسٹ کروانے کیلئے کہا جائے۔
- ◆ وبا کے دوران کنسٹرکشن سائٹ پر دیگر PPEs کے ساتھ ساتھ مزدوروں کو ماسک لازمی استعمال کرایا جائے۔





# تعمیراتی کاموں کے دوران خطرات / حادثات سے بچنے کیلئے سامان برائے ذاتی حفاظت کا خلاصہ












| تعمیراتی کام  | مقصد                            |
|---|---------------------------------|
| اڑنے والے ذرات کا استعمال جیسے پکھلی ہوئی دھات مائع کیمیکل، گیسوں، اور بخارات، روشنی کی شعاعیں۔   | آنکھوں اور چہرے کی حفاظت / تحفظ |
| ایسے تمام کام جن میں گرنے کا خطرہ ہو، بلندی پر کام کرنا، تعمیراتی کام کو سنبھالنے اور دوسری جگہ پر منتقل کرنے والے کام۔                 | سر کی حفاظت / تحفظ              |
| کھدائی / شور پیدا کرنے والے کام یا بھاری مشینری استعمال کرنے کی وجہ سے شور۔   | سماعت کی حفاظت / تحفظ           |
| تمام تعمیراتی کام جن میں چیزوں کا گرنا یا گھمانا، نوکیلی اشیاء شامل ہوں۔ گلانے والا یا گرم مائع، کچرے کے ڈھیر سے کچرا اٹھانا۔           | پاؤں کی حفاظت / تحفظ            |
| جسمانی صحت کیلئے نقصان دہ سامان جیسے کچرے کو سنبھالنا، ایسے کام جس میں کاٹ یا گہرے زخم لگنے کا اندیشہ ہو، ارتعاش، بہت زیادہ درجہ حرارت۔ | ہاتھوں کی حفاظت / تحفظ          |
| دھول، دھند، شعلے، گیسوں، دھواں، بخارات  | تحفظ تنفس                       |
| آکسیجن کی کمی   | جسم / ٹانگوں کی حفاظت / تحفظ    |
| تمام کام جن میں شدید درجہ حرارت، نقصان دہ مواد، حیاتیاتی ایجنٹ، چھوٹے یا گہرے زخم لگنے کا اندیشہ ہو                                     | اونچائی پر کام کرتے ہوئے حفاظت  |
| تمام تعمیراتی کام جو 4 فٹ یا اس سے زیادہ کی اونچائی پر کے جانے ہوں بشمول سٹریٹ لائٹس وغیرہ  | اونچائی پر کام کرتے ہوئے حفاظت  |
| تمام تعمیراتی کام جو 4 فٹ یا اس سے زائد اونچائی پر مسلسل ایک دن کیلئے کیے جانے ہوں  | اونچائی پر کام کرتے ہوئے حفاظت  |

## تجویز کردہ سامان برائے ذاتی حفاظت

|  |  |
|--|--|
| حفاظتی عینکیں  | اپر اور اطراف سے نقصان سے بچاؤ کیلئے پلاسٹک کے ہیلمٹ   |
| ساعت کی حفاظت کے آلہ جات جیسے کن پوٹ یا ایئر پگ  | ہلنے اور گرنے والی اشیاء، مائع اور کیمیائی مواد سے بچاؤ کیلئے حفاظتی جوتے یا بوٹ                 |
| رہڑیا مصنوعی مواد (نیوروپین)، چمڑا، سٹیل، غیر موصل مواد سے بنے گلووز   | ایک جگہ سے دوسری جگہ لے جانے والے یا ایک ہی جگہ پڑے مواد کی فراہمی تعمیراتی جگہ پر بچاؤ کا سامان |
| چہرے کے ماسک جن میں دھول ہٹانے اور ہوا کو صاف رکھنے کیلئے (کیمیائی مواد، دھند، بخارات اور گیسوں سے) مناسب فلٹر لگے ہوں | مناسب میٹرل سے بنے غیر موصل کپڑے، ایپرن وغیرہ  |
| ہیلمٹ، حفاظتی عینکیں، گلووز اور ربڑ کے بوٹ   | ایسکر، بیلٹ، رسی، کنیکٹر، سہلے، تھمہ جگہ اور ایک ساتھی فرد                                       |



# Summary of Recommended Personal Protective Equipment According to Hazard

| Objective               | Workplace Hazards   | Suggested PPE   | Pictures   |
|-------------------------|---|---|--|
| Eye and face protection | Flying particles, molten metal, liquid chemicals, gases or vapors, light radiation. | Safety Glasses with side-shields, protective shades, etc.   |   |
| Head protection         | Falling objects, inadequate height clearance, and overhead power cords.             | Plastic Helmets with top and side impact protection.  |   |
| Hearing protection      | Noise, ultra-sound.   | Hearing protectors (ear plugs or ear muffs).  |   |
| Foot protection         | Falling or rolling objects, pointed objects. Corrosive or hot liquids.              | Safety shoes and boots for protection against moving & falling objects, liquids and chemicals.  |   |
| Hand protection         | Hazardous materials, cuts or lacerations, vibrations, extreme temperatures.         | Gloves made of rubber or synthetic materials (Neoprene), leather, steel, insulating materials, etc.   |    |
| Respiratory protection  | Dust, fogs, fumes, mists, gases, smokes, vapors.                                    | Facemasks with appropriate filters for dust removal and air purification (chemicals, mists, vapors and gases). Single or multi-gas personal monitors, if available. | <br> |
|                         | Oxygen deficiency   | Portable or supplied air (fixed)  |   |
| Body/leg protection     | Extreme temperatures, hazardous materials, biological agents, cutting and           | Insulating clothing, body suits, aprons etc.  |   |
| Working at *height      | Rehabilitation Projects   | Helmet, Safety glasses,   |   |
|                         | New Construction Projects   | Anchor, belt, lanyard,  |   |

\*In general, use of PPEs is required for any height of 4 ft or more. Ref: OSHA standards



### (3) مقامی آبادی روکنا داروں اور رہائشیوں کی صحت، ماحولیات اور سماجیات سے متعلق رہنما اصول و حفاظتی تدابیر

#### سرگرمیاں

۱. تعمیراتی کاموں کے لئے منتخب کردہ مقام / جگہ پر کام کا آغاز

#### مسائل

- ◆ مقامی آبادی رہائشیوں کیلئے تعمیراتی کام کی عدم آگاہی
- ◆ لیبر مزدوروں کے داخلے سے رہائشی عورتوں کے پردے اور پرائیویسی کے مسائل
- ◆ مقامی آبادی کے ثقافتی، سماجی، مذہبی ورثہ، اور تاریخی مقامات و عمارتوں کو نقصان

#### حفاظتی اقدامات

تھیکیدار کو چاہئے کہ:

- ◆ متعلقہ میونسپل کمٹی کے انوائزمنٹ اینڈ سوشل فوکل پرسن (ز) منتخب کردہ اور متعلقہ ریجنل آفس میں موجود ڈپٹی پروگرام آفیسر (انوائزمنٹ اینڈ سوشل سیف گارڈز) کی موجودگی میں مقامی آبادی رہائشیوں اور دکانداروں کو تعمیراتی کام کے آغاز سے قبل تعمیراتی کام کی نوعیت، اثرات و نتائج اور تکمیل کی معینہ مدت کے بارے میں مکمل آگاہی فراہم کرے۔
- ◆ تعمیراتی کام کے دوران پیش آنے والے ممکنہ سماجی اور ماحولیاتی مسائل اور ان کے مطابق حفاظتی اقدامات کے بارے میں مقامی رہائشیوں دکانداروں کو کام کے آغاز سے قبل مکمل آگاہی دی جائے۔
- ◆ تعمیراتی کام کے آغاز سے پہلے مقامی رہائشیوں اور دکانداروں کو تعمیراتی کاموں کی وجہ سے سماجی اور ماحولیاتی مسائل کی نکاحی ریشلیاں تجاویز کیلئے مندرجہ ذیل رابطہ نمبرز کے بارے میں مکمل آگاہی فراہم کی جائے۔
  - (a) تھیکیدار کا موبائل ریٹیلینون نمبر
  - (b) متعلقہ میونسپل کمٹی کارپوریشن کے فوکل پرسن (ز) کے رابطہ نمبرز
  - (c) متعلقہ (PCP) ریجنل آفس میں تعینات ڈپٹی پروگرام آفیسر (ESSs) کے رابطہ نمبرز
- ◆ تعمیراتی کام کے آغاز سے پہلے تعمیراتی مقام ریکارڈ کو فیتہ کی مدد سے باقی علاقہ سے الگ کر دیا جائے۔



تعمیراتی جگہ پر واضح بورڈ نصب کر دیئے جائیں، جن پر درج ذیل پیغامات احکامات لکھے ہوں:

(a) تعمیراتی کام کی نوعیت

(b) ٹریفک میں رکاوٹ کی صورت میں متبادل راستے کا نشان اور عارضی رکاوٹ کا پیغام

(c) ایئر جیسی اور شکایت کیلئے رابطہ نمبرز

(d) (PMDFC) کی جانب سے جاری کردہ سماجی و ماحولیاتی پیغامات پر مبنی پوسٹرز۔

تعمیراتی کام کی جگہ کے ارد گرد 100 میٹر تک کی حدود میں موجود ثقافتی، سماجی، مذہبی ورثہ، تاریخی عمارتوں اور مذہبی مقامات جیسے قبرستان، مساجد، مندر، گرجا گھروں وغیرہ کو کسی قسم کا نقصان نہ پہنچایا جائے اور ان کی حدود میں کوڑا کرکٹ ڈالنے یا فالتو پانی چھوڑنے سے گریز کیا جائے۔ مزید برآں کھدائی کے دوران کسی نئے آثارِ قدیمہ ملنے کی صورت میں متعلقہ مقامی محکمے سے رجوع کیا جائے اور کھدائی کا کام بند کر کے تعمیراتی کام روک دیا جائے۔

## سرگرمیاں

2- کھدائی کی جگہ اور اس سے متعلقہ کام اور نالوں کی صفائی اور اس سے حاصل شدہ بھل وغیرہ

## مسائل



کھدائی سے حاصل شدہ مٹی رکنکر کے ڈھیر (Debris) سے رہائشیوں کی آمدورفت اور ٹریفک میں رکاوٹ

مقامی رہائشیوں کیلئے ناگواری کا باعث

چٹخروں اور دیگر بیماری پھیلانے والے جراثیم کی افزائش کا ذریعہ

کھدائی کی جگہ پر گرنے اور حادثات کے خطرات



## حفاظتی اقدامات

- ◆ تعمیر کے دوران کھدائی کے تمام مقامات کے ارد گرد حفاظتی ٹیپ رپٹی لگائی جائے اور کھدائی کی جگہ کو عارضی طور پر بند کر دیا جائے جس کے باہر اس جگہ سے دور رہنے کیلئے واضح پیغامات لکھے ہوں۔
- ◆ کھدائی سے حاصل شدہ مٹی رکنکر پتھر وغیرہ کو ایک دن سے زیادہ اس جگہ پر موجود نہ رہنے دیا جائے بلکہ روزانہ کی بنیاد پر متعلقہ میڈیکل کمیٹی رکارڈ پوریشن کی منتخب کردہ جگہ پر محفوظ طریقے سے ٹھکانے لگایا جائے۔
- ◆ نالوں کی صفائی سے حاصل شدہ بھل ریت وغیرہ کو ایک دن سے زیادہ اس جگہ پر موجود نہ رہنے دیا جائے بلکہ روزانہ کی بنیاد پر اٹھوایا جائے اور بھل و ایک جگہ سے دوسری جگہ منتقلی کے دوران ٹریکٹر/ٹرائی کو تریپال کی مدد سے ڈھانپ کر لے جایا جائے۔

## سرگرمیاں

3- تعمیراتی مشینری / تعمیراتی مٹیریل اور تعمیراتی کاموں کی وجہ سے عارضی بندش

## مسائل

- ◆ ٹریفک میں رکاوٹ۔

## حفاظتی اقدامات

- ◆ ٹریفک میں ممکنہ رکاوٹ کے پیش نظر متبادل راستے کا انتخاب اور اس کی نشاندہی کیلئے پیغامات واضح درج کیے جائیں۔
- ◆ ٹریفک کونز (cones) کی مدد سے رکاوٹ والی جگہ کو الگ کر دیا جائے تاکہ حادثات سے بچا جاسکے۔
- ◆ ٹریفک میں زیادہ دنوں تک مسلسل رکاوٹ کی صورت میں مقامی ٹریفک پولیس کو آگاہ کیا جائے اور ان کے ساتھ مل کر ٹریفک مینجمنٹ پلان کو تشکیل دیا جائے جس کو واضح مقام پر نصب کیا جائے اور مقامی آبادی رہائشیوں کو اس کے بارے میں مکمل آگاہی دی جائے۔



پی ایم ڈی ایف سی

۲۳

انوائٹ مینٹ اینڈ سوشل سرف گارڈز ٹیم

## سرگرمیاں

4- تعمیراتی کاموں کی وجہ سے راستوں میں عارضی رکاوٹ اور زمین کا عارضی حصول

## مسائل

- روزمرہ معمولات اور کاموں میں رکاوٹ
- رہائشی خواتین کیلئے آنے جانے میں رکاوٹ
- دکانداروں کے دکانوں کے آگے رکاوٹیں اور گاہکوں کیلئے مشکلات
- مستقل و عارضی سائز لگا کر بیچنے والے چھوٹے بڑے مستقل دکانداروں کا گاہک کم ہو جانے کی وجہ سے مالی نقصان

## حفاظتی اقدامات

- تعمیراتی علاقے میں ارد گرد موجود تمام چھوٹی بڑی دکانوں، ٹھیلوں، عارضی خوانچہ فروشوں اور گھروں کا مکمل سروے (تعداد اور مالی حیثیت وغیرہ) اور ان پر ممکنہ سماجی اور ماحولیاتی اثرات کا جائزہ لے کر ایک تفصیلی رپورٹ اور متعلقہ پلان میونسپل کمیٹی رکارپوریشن کے دفتر میں موجود ہونی چاہئے جو کہ فوکل پرسنز، متعلقہ علاقائی آفس میں موجود ڈپٹی پروگرام آفیسر (ESSs) کے ساتھ تعمیراتی کاموں کی مالیت کا اندازہ لگائے وقت تیار کیا جائیگی۔ اس رپورٹ اور پلان میں موجود سماجی اور ماحولیاتی مسائل کے حل کیلئے مختص رقم اور ان کا صحیح طریقے سے استعمال ٹھیکیدار کے کنٹریکٹ حصہ ہوگا۔
- رہائشیوں کیلئے آنے جانے اور دکانوں، گھروں تک رسائی کے لیے متبادل راستے مہیا کرنا ٹھیکیدار کی ذمہ داری ہے۔
- دکانوں، تھڑوں، ٹھیلوں وغیرہ کے باہر کسی بھی قسم کے نقصان یا توڑ پھوڑ کی صورت میں ٹھیکیدار طے شدہ ضوابط کے مطابق اس کی قیمت متاثرہ لوگوں کو ادا کرے گا۔
- لیبر مزدور کو تربیت دی جائے کہ وہ ارد گرد رہائشی عورتوں اور بچوں کے آنے جانے میں کوئی رکاوٹ نہ بنیں اور رہائشیوں کے ساتھ بلا ضرورت کوئی میل جول نہ رکھیں۔
- تعمیراتی ٹیمپ لگانے، تعمیراتی کام کرنے یا مشینری اور تعمیراتی سامان رکھنے کے لیے عارضی طور پر حاصل کی گئی زمین کا کرایہ مالک مکان کو وقت پر ادا کیا جائے گا۔ اور تحریری معاہدے کی صورت میں ٹھیکیدار تمام قواعد و ضوابط کا پابند ہوگا۔
- تعمیراتی کاموں کی ٹیمپ وغیرہ لگانے کے لیے عارضی زمین حاصل کرنے کے لئے مقامی رہائشیوں سے مشاورت اور دنوں کے حساب سے کرایہ اور اس کا مکمل طریقہ کار وضع کر کے باقاعدہ لکھا جائے گا۔ اور خلاف ورزی کی صورت میں ٹھیکیدار ذمہ دار ہوگا۔





## سرگرمیاں

5. تعمیراتی کام اور ہیوی مشینری کا استعمال

## مسائل

- ◆ شورغل
- ◆ پانی کی آلودگی
- ◆ ہوائی آلودگی
- ◆ دیگر ماحولیاتی مسائل

## حفاظتی اقدامات

◆ تعمیراتی علاقے میں موجود ہسپتالوں، سکولوں رکالوجوں وغیرہ اور رہائشی گھروں ردکانوں کی تمام تفصیلات کی رپورٹ متعلقہ میونسپل کمیٹی کے دفتر میں موجود ہونی چاہئے جو کہ ٹھیکیدار کے کنٹریکٹ کا حصہ ہوگی۔ اور ٹھیکیدار ان تفصیلات کے مطابق ایسا پلان ترتیب دے گا جس سے ارد گردی عمارتوں پر ہائیکیوں اور ردکانوں کو کم سے کم پریشانی کا سامنا کرنا پڑے مثلاً زیادہ شور پیدا کرنے والے کام دن کے اس حصے میں کئے جائیں جب ہسپتالوں، اور سکولوں رکالوجوں وغیرہ کے مصروف اوقات کار نہ ہوں اور ایسے کام جن کی وجہ سے راستوں کی عارضی بندش ضروری ہوں وہ رات کو کیئے جائیں جب رہائشیوں کی آمدورفت نہ ہو۔

◆ تعمیراتی کاموں کے دوران پیدا شدہ فاضل پانی یا پورٹیل ٹوائلٹس کا پانی فضلہ وغیرہ کا محفوظ اور مناسب طریقے سے ٹھکانے لگانے کا بندوبست کیا جائے اور فاضل پانی کو پینے کے صاف پانی کے ساتھ شامل ہونے سے بچانے کا ہر ممکن قدم اٹھایا جائے۔

◆ دائر سہائی کی سیموں یا ایسی تمام کام جن کی وجہ سے رہائشیوں کو پانی یا سیوریج وغیرہ میں عارضی بندش کا سامنا کرنا پڑ سکتا ہو، ایسے تمام کاموں کے آغاز سے پہلے رہائشیوں کو پیشگی اطلاع دی جائے اور متبادل انتظامات کا خطر خواہ انتظام کیا جائے۔

◆ تعمیراتی کاموں کی وجہ سے درختوں کی کٹائی سے ہر حال میں گریز کیا جائے اور ناگزیر صورت حال میں ایک درخت کی کٹائی کے متبادل کے طور پر چار درخت لگانا ضروری ہیں۔

◆ تعمیراتی جگہ پر پیدا ہونے والے کوڑا کرکٹ کو ٹھکانے لگانے کیلئے ڈسٹ بن لگائے جائیں اور ان کو روزانہ کی بنیاد پر متعلقہ میونسپل کمیٹی کی طرف سے مقرر کردہ مقام پر ٹھکانے لگایا جائے۔

◆ کوڑا کرکٹ اور فاضل پانی ارد گرد موجود فصلوں اور ندی نالوں میں پھینکنے سے گریز کریں۔

◆ گردوغبار اور ہوائی آلودگی کی صورت میں پانی کا باقاعدہ چھڑکاؤ کریں۔

◆ تعمیراتی کام کی مدت اور نوعیت کے مطابق کام کے آغاز سے پہلے، کام کے دوران اور کام کے بعد پانی کی آلودگی، ہوائی آلودگی اور آبی آلودگی کے نمونہ جات حاصل کر کے ان کی جانچ پڑتال کرنا ٹھیکیدار کی ذمہ داری ہے۔ اس سلسلے میں ریجنل آفس میں موجود ڈپٹی پروگرام آفیسر (ESS) سے مزید رہنمائی حاصل کریں۔

◆ تعمیراتی کام مکمل ہو جانے کے بعد علاقے کی صفائی ستھرائی اور ماحولیاتی خوبصورتی کا خاص خیال رکھیں اور پہلے سے بہتر حالت میں چھوڑیں۔

\* سپریم کورٹ آف پاکستان کے سو موٹو کیس نمبر 25 برطابق 2009 حوالہ نمبر 1 کنگ آف نرین فار کینال دو ایڈونٹک پراجیکٹ لاہور، تعمیراتی کاموں کے دوران ہر ایک درخت کی کٹائی کے متبادل چار درخت لگانے کا حکم ہے۔

انوائٹرنمنٹ اینڈ سوشل سیف گارڈ ٹیم

پی ایم ڈی ایف سی

۲۵

ترقیاتی منصوبوں کی تعمیر و مرمت کے دوران کام کرنے والے  
مزدوروں، ورکرز، (بشمول خواتین لیبر / ورکرز) کی صحت، حفاظت  
اور ماحول کے لئے معیاری اصول و ضوابط درج ذیل پالیسیز،  
قوانین اور نوٹیفیکیشنز کا تجزیہ کر کے تجویز کئے گئے ہیں۔

- ◆ The Punjab Occupational Health & Safety Act, 2019
- ◆ General Environment, Health & Safety (EHS) Guidelines by International Finance Corporation (IFC), World Bank
- ◆ International Labour Standards of International Labour Organization (ILO)
- ◆ Punjab Tehsil/Town Municipal Administration (Works) Rules 2003 (Amendments 2016)
- ◆ The Punjab Restriction on Employment of Children Act, 2016
- ◆ The West Pakistan Maternity Benefit Ordinance, 1958
- ◆ ESF/Safeguards Interim Note: COVID-19 Considerations in Construction / Civil Works Projects - World Bank Guidelines
- ◆ Health & safety SOPs for Construction Workers/Sector for COVID 19
- ◆ Punjab Wildlife (Protection, Preservation, Conservation and Management) Act, 1974

